MASS GRADING
MODIFIED ATTACHMENT "D"
Subdivision Construction Inspection
General Notes For Mass Grading Only

1. A pre-construction meeting shall be required with the Department of Construction Management and Inspection (DCMI) to discuss construction phasing, unusual site conditions, special requirements, etc. Please call 301-600-3512, 5 days in advance and between the hours of 7:30 A.M. and 4:30 P.M.

2. An inspection of the construction stakeout is required by DCMI.

3. All work and construction methods and materials shall be in accordance with the Maryland State Highway Standard Specifications for Construction and Materials dated January 2001 and all current revisions and supplements.

4. The contractor shall be required to contact DCMI 24 hours in advance of placing any controlled fill within the proposed road right-of-way. Moisture/density testing is required in accordance with the approved specifications and Section 204 of the Maryland Highway Standard Specifications for Construction and Materials dated January 2001 and all current revisions and supplements. All moisture density for fill areas, subgrade, culvert and structure backfill is to be performed by the developer's geotechnical engineer and monitored by DCMI. Any proposed subgrade drainage must be designed by a Maryland Professional Engineer and approved by the Frederick County Division of Permitting and Development Review (DPDR) prior to installation. Soil bearing capacity shall be certified.

5. Benchmarks shall be established and maintained until acceptance of the improvements.

6. The contractor shall schedule proof roll inspections with DCMI a minimum of 24 hours in advance, prior to placement of pavement and after satisfactory completion of subgrade density/moisture testing; MD 204.03.04 Specifications shall apply.