



FREDERICK COUNTY GOVERNMENT

DIVISION OF FINANCE

Erin M. White, CPA, Acting Director

Department of Procurement & Contracting

Diane L. George, CPPB, Director

Winchester Hall, 12 East Church Street
Frederick, Maryland 21701

www.FrederickCountyMD.gov

O: 301-600-1069 F: 301-600-2521

Commissioners

Blaine R. Young
President

C. Paul Smith
Vice President

Billy Shreve
David P. Gray
Kirby Delauter

Lori L. Depies, CPA
County Manager

January 31, 2014

IFB# 14-027-CP

Jefferson Technology Park Waterline Addendum No. 5

This addendum contains revisions, clarifications, responses to bidder questions, pre-bid conference sign-in sheets and information pertinent to the bid documents of the referenced project and shall supplement, amend, and become part of the procurement documents for the title project and contract. All bids shall be based on this Addendum, in accordance with the bid documents.

Acknowledgment of this addendum shall be made on the Proposal Form, including addendum number and date. Failure to acknowledge addendum may subject the bidder to disqualification.

The bid due date has not been revised.

Except as noted herein, all terms and conditions of the document referenced, as heretofore changed, remain unchanged and in full force and effect.

Tim Kepp, Project Manager

Addendum No. 5
IFB# 14-027-CP

BIDDER QUESTIONS

1. Response to Addendum No. 2 question 16 is modified as follows:

16. The information provided on page 27 of appendix B outlines the requirements for pre and post-construction surveys of existing buildings and structures within 150 feet of blasting. However, the blasting requirements provided within section 02200 of the project specifications do not make any reference to pre and post-construction surveys. Please confirm whether or not the requirements outlined in appendix B will apply to this project.

*Response: No. 16: Yes, the pre and post-construction surveys apply to this project. For the purposes of bidding, assume the structures currently under construction for the Route 340 exit/overpass will be existing at the time of water main installation. See Figure A-2b in Appendix B for locations of these structures. However, due to the sensitive nature of the existing water storage tank, **no blasting operations shall be permitted from station 0+00 and 1+84, and within the SHA R/W.***

2. Response to Addendum No. 2 question 17 is modified as follows:

17. The information provided on page 28 of appendix B outlines the requirements for vibration monitoring when explosives are used. However, the blasting requirements provided within section 02200 of the project specifications do not make any reference to vibration monitoring. Please confirm whether or not the requirements outlined in appendix B will apply to this project. Additionally, if the requirements in appendix B are applicable to this project will the two week monitoring period prior to blasting be required?

Response: No. 17: Yes, monitoring shall be required for this project. Pre-blasting monitoring shall be a minimum of two days prior to conducting blasting operations.

CLARIFICATIONS/ADDITIONS

None for this addendum.

ATTACHMENTS

None for this addendum.