


The
SUGARLOAF
Treasured Landscape Management Plan

DRAFT

September 2021





Planning and Permitting Division

Steve Horn, Director

Livable Frederick Planning and Design Office

Kimberly Golden Brandt, Director

Tim Goodfellow, AICP

John Dimitriou, R.A.

Dial Keju

Denis Superczynski, AICP

Amanda Whitmore

Interagency Information Technologies, GIS Department

Kevin Szatmary

Mary McCullough



The
SUGARLOAF
Treasured Landscape Management Plan

DRAFT

Frederick County, Maryland

July 2021



Contents

Introduction and Background	1
Why do we choose to undertake a plan for the Sugarloaf Area?	2
Sugarloaf Area Vision Statement	4
Sugarloaf Treasured Landscape Management Plan Goals	4
Geographical Context	5
History and Culture	11
European Settlement	11
Early Industry	11
Transportation	12
Stronghold Incorporated and Sugarloaf Mountain	19
The Many Roles of Stronghold, Incorporated: Nature, Recreation, and History	21
Land Use	33
The Planning Area	33
Land Use Tools	33
Land Use in the Sugarloaf Planning Area	34
Septic Systems, Groundwater, and Land Use	36
Sole Source Aquifer	37
Livable Frederick Master Plan, Thematic Plan Diagram, and Comprehensive Plan Map	38
Zoning	40
Land Subdivision	41
Sugarloaf Rural Heritage Overlay Zoning District	41
Urbana Community Growth Area	42
Land Conservation	43
Transportation Network	63
Maryland Interstate Highway System Projects	65
Scenic Roads	68
Watershed Water Quality	75
Maryland's Designated Use Classes for Surface Waters (COMAR 26.08.02)	76
Stream Habitat	77
Water Quality	79
Biological Condition	79
Impervious Surface	81
Monitoring Water Quality Impacts from Impervious Cover and Land Use	83
Coldwater Biological Resources in the Sugarloaf Planning Area	83
Brook Trout Watersheds - Bear Branch and Furnace Branch	86
Urbana Branch Watershed	90

Forestlands, Green Infrastructure, and Biodiversity	99
Maryland's 2020 Forest Action Plan	99
Programmatic Opportunities for Reforestation	104
Biodiversity	106
Ecologically Significant Areas	109
Climate Change	119
Local and State Action	119
Agriculture and Carbon Sequestration	123
Forests and Carbon Sequestration	124
Local Impacts and Solutions	125
Citations and Footnotes	129
Appendix	A-1
Sugarloaf Historic Resources Inventory	A-1
Sugarloaf Area Planning History, 1959-2012	A-13
Sugarloaf Rural Heritage Overlay Zoning District Regulations	A-19
Frederick County Streams and Use Classes	A-27
Demographic Profile – Sugarloaf Planning Area	A-29
Frederick County Council 2020 Climate Emergency Resolution	A-30
Sugarloaf Survey District Form (pp 1-12) (survey file F-7-32)	A-33

Tables and Figures

Table 1A. Existing Comprehensive Plan Designations within Sugarloaf Planning Area	39
Table 1B. Proposed Changes to Comprehensive Plan Designations within Sugarloaf Planning Area, July 2021	40
Table 1C. Existing Zoning Districts within Sugarloaf Planning Area	40
Table 1D. Proposed Changes to Zoning Districts within Sugarloaf Planning Area, July 2021	40
Table 2. Subdivision Activity by Zoning District within the Sugarloaf Planning Area through 2020	41
Table 3. Sugarloaf Plan Scenic Road Recommendations	72
Table 4. Maryland Physical Habitat Index – Condition Class Thresholds	77
Table 5. Maryland Benthic Index of Biotic Integrity – Condition Class Thresholds	80
Figure 1. Relationship Between the BIBI and Forested Land Use	82
Figure 2. Relationship Between the BIBI and Urban Land Use	82
Figure 3. Stressor Identification Index (adapted from Tetra-Tech, 2008, Bennett Creek Watershed Assessment)	85
Table 6. Sugarloaf Resource Watersheds of Concern	86
Table 7. Brook Trout Populations, Bear Branch Watershed – Mt. Ephraim Road (Maryland DNR)	87
Table 8. Brook Trout Temperature Exceedance for Furnace Branch and Bear Branch	87
Table 9. Urbana Branch Watershed – Stream Waders Biological Monitoring	90
Table 10. Forest Interior Dwelling Species Criteria – Sugarloaf Planning Area (MD DNR)	101
Table 11. Biological Conservation Network (BioNet) – Sugarloaf Planning Area (Maryland DNR)	108
Table 12. Ecologically Significant Areas in the Sugarloaf Planning Area	109

Maps

1-1 Planning Area Boundary	8
1-2 Sugarloaf/Stronghold, DNR, and Conservation Easements	9
2-1 Historic Sites	17
4-1 Piedmont Sole Source Aquifer	47
4-2 Comprehensive Plan Land Use Designations	48
4-3 Land Use Designations with Treasured Landscape	49
4-4 Zoning Districts	50
4-5 Subdivisions	51
4-6 Proposed Land Use Designations	52
4-7 Proposed Land Use Designations	53
4-8 Proposed Land Use Designations	54
4-9 Proposed Land Use Designations	55
4-10 Proposed Zoning	56
4-11 Proposed Zoning	57
4-12 Proposed Zoning	58
4-13 Proposed Zoning	59
4-14 Proposed Overlay Zoning District	60
4-15 Carrollton Manor Rural Legacy Area Proposed Expansion	61
5-1 Reported Vehicle Crash Incidents	73
6-1 Watersheds	92
6-2 Aquatic Monitoring Sites	93
6-3 Aquatic Monitoring Sites	94
6-4 Aquatic Monitoring Sites	95
6-5 Watersheds of Concern	96
6-6 Designated Use Classes	97
7-1 Biodiversity Conservation Network	113
7-2 Ecologically Significant Areas	114
7-3 Forest Interior Dwelling Species	115
7-4 Forest Cover	116
7-5 DNR Green Infrastructure	117



Introduction and Background

The Sugarloaf Treasured Landscape Management Plan is a long-range planning document that exists within the context of a broader planning initiative known as Livable Frederick. With the adoption of the Livable Frederick Master Plan in September 2019, Frederick County created a new framework for making strategic decisions about the County's future. The Livable Frederick Comprehensive Plan serves as an umbrella under which a multitude of plans, policies, studies, and regulations are continuously emerging and evolving. The Sugarloaf Treasured Landscape Management Plan is one such document.

The Livable Frederick Comprehensive Plan is composed of:


The Livable Frederick Master Plan A vision-based strategic plan for the county's long term future well-being. The LFMP features a Vision, a Development Framework featuring a Thematic Plan Diagram, and an Action Framework detailing goals and initiatives addressing the four fundamental themes of Community, Health, Economy, and Environment.

The Comprehensive Land Use Plan Map A map, or map series, that identifies broad categories of land uses and other related long-range planning features. Generally, this map is revised and updated with the adoption of new plans under the Livable Frederick framework.

Community and Corridor Plans These plans are the beating heart of the Livable Frederick concept, and will constitute the primary means of implementing the vision presented in the Livable Frederick Master Plan. Plans are prepared for community growth areas, key economic or transportation corridors, county lands surrounding the county's incorporated municipalities, and other geographic places in need of detailed study. These plans are focused on creating great places to live and work in Frederick County.


Large Area Plans These planning documents are prepared to address larger geographic areas that include multiple communities or neighborhoods, significant natural landscapes or features, or broad land areas under the influence of forces or conditions warranting dedicated planning attention by the county. The Sugarloaf Treasured Landscape Management Plan is a large area plan.

Functional Plans A functional plan addresses issues related to planning for the systems or networks that are generally not tied to a specific geography within the county. Two such documents identified in the Livable Frederick Master Plan are the Green Infrastructure Plan and the Agricultural Infrastructure Plan, each serving to establish a coordinated planning approach to topics involving an array of places, activities, and forces.



The Sugarloaf Treasured Landscape Management Plan Planning Area

LIVABLE FREDERICK COMPREHENSIVE PLANNING




Note: Plan types and locations shown are purely illustrative and do not indicate any proposed future planning efforts.

Opportunity Plans These planning documents are deployed to address time-sensitive challenges faced by the county. The Livable Frederick framework acknowledges the need to remain nimble in the face of challenges and opportunities. This type of focused planning work allows the county to work within the Livable Frederick framework, while addressing issues that may not arise in the normal course of long-range planning. Such documents may address specific economic, environmental, or mobility opportunities.

As each of these plans is developed and adopted by elected officials, the new documents will constitute amendments to the Livable Frederick Comprehensive Plan.

With the adoption of the Sugarloaf Treasured Landscape Management Plan, the Livable Frederick Comprehensive Plan now reflects the county's long-range vision for the Sugarloaf area and anticipates actions, both public and private, to achieve that vision. The future is often unpredictable, yet planning to face the challenges of the future remains our best option as a community. To that end, a shared community vision of our desired future for the Sugarloaf area will guide our land use planning, refine our public policies, and bring resources to bear on the challenges and opportunities that lie ahead.



Why do we choose to undertake a plan for the Sugarloaf Area?

The Livable Frederick Master Plan articulates a long-range vision for Frederick County that includes a concept called "Treasured Landscapes." These Treasured Landscapes are places that stand out in a county with many inspiring, productive, and naturally-diverse lands. The LFMP identifies these landscapes as ones that can benefit from the focused attention that a separate planning effort affords. The Sugarloaf Area is, perhaps, the ultimate example of a Frederick County Treasured Landscape — visually-prominent and recognized by nearly everyone. Yet the Sugarloaf Area is still subject to the same forces that impact all of our neighborhoods, no matter where in Frederick County we call home. It is time for us to acknowledge that if this mountain — and its surrounding lands and waterways — is beautiful and recognizable enough to grace the covers of our government documents, inspire the logos and

trademarks of local businesses and organizations, and serve as the namesake of our children's schools, it is clearly important enough for us to make every effort to plan for its continued health, beauty, and economic vitality.

The global Covid-19 pandemic has caused distortions and radical shifts in everyday life, work, and commerce, in addition to causing sickness and mortality. The pandemic underscores the importance of planning as a defense against the unpredictability of the future.

While our future, generally, may be difficult to predict with complete accuracy, the future of our climate and weather patterns are more certain, albeit dire, based on current observations, data trends, and climate and weather models from the vast majority of scientists from academic, research, and governmental institutions. Our future climate poses serious environmental, public health, and economic threats to our society. These threats, though global in origin, affect how we might choose to plan locally. Among the most impactful changes as a result of our changing climate are: increased storm intensity and frequency, flooding and associated stream erosion, heat waves, urban heat island effects, droughts, species loss, and habitat alterations. Increased energy costs, negative impacts on food production, water supply shortages, and damage to our community infrastructure are other grim predictions of our future. This affects, and must inform, how we prepare for the coming decades.

With adoption of Council Resolution No. 20-22 on July 21, 2020, the Frederick County Council formally acknowledged the climate emergency and pledged to evaluate local policy and legislative actions through the lens of climate change. The resolution established a climate emergency mobilization workgroup to develop recommendations to: address global warming, reduce County-wide greenhouse gas emissions, and sequester carbon.

On a smaller, localized level, the Sugarloaf Treasured Landscape Management Plan addresses reducing greenhouse gas emissions, mitigating and adapting to climate change, and working towards climate change resilience through a variety of policies, land use recommendations, and community initiatives.

The Sugarloaf Planning Area possesses multiple environmental elements that make it highly sensitive to change, including extensive and contiguous forestlands, significant wildlife habitat, high-quality waters, and the only mountain in the Maryland Piedmont. The Sugarloaf Treasured Landscape Management Plan articulates the rationale and need for stewardship, preservation, and enhancement of these environmental resources. The Plan focuses on the protection of the natural resource base and rural landscape of the Sugarloaf Area.

To provide insight and focus in the development of the Sugarloaf Treasured Landscape Management Plan, the County convened a Sugarloaf Stakeholders' Advisory Group comprised of landowners, community residents, business owners, and individuals with professional and personal ties to the Sugarloaf Area. Crafted in collaboration with the Sugarloaf Stakeholders' Advisory Group, the Sugarloaf Area Vision Statement is a positive and descriptive narrative that articulates a preferred future for the Sugarloaf Planning Area. The Vision Statement forms the aspirational basis from which the overarching goals, policy declarations, and specific initiatives are derived.

Sugarloaf Area Vision Statement

A unique geologic landform in Maryland, Sugarloaf Mountain is a defining element of Frederick County's treasured scenic and rural landscape. The mountain and the area surrounding it possess a sublime beauty and significant biodiversity, where a high-quality environment is maintained. Forestlands, aquatic resources, wildlife habitat, inspiring vistas, and historic resources are valued and protected. Land uses are sensitive to both the natural environment and rural character of the area. Stewardship of the area's natural assets and cultural resources ensures healthy, resilient, and economically productive lands for current and future generations. As we face climate change challenges, Sugarloaf Mountain and the surrounding landscape provide ecosystem benefits to the residents of both Frederick County and the wider region, enhancing the sustainability of our shared environment.

Distilled from the Vision Statement are broad goals that identify what the Sugarloaf Treasured Landscape Management Plan strives to accomplish and achieve. Policies and initiatives are dispersed throughout the Plan with associated narratives to provide contextual linkage.

Sugarloaf Treasured Landscape Management Plan Goals

Protect and enhance the Sugarloaf Area's natural resources and environmental assets, including its forests, waters, biodiversity, and wildlife habitats.

Strengthen the distinct place-based identity of the Sugarloaf Area through the stewardship of its scenic and rural character, and its agricultural and cultural resources.

Foster a resilient human ecology through the mitigation of, and adaptation to, climate change.




Geographical Context


The Sugarloaf Planning Area is 17,140 acres in size. Physical proximity and visual relationships to Sugarloaf, as well as overall landscape-related associations with the mountain determined the Planning Area boundary, which is bordered generally by MD 80 (Fingerboard Road) and the historic Hope Hill community to the north and Thurston Road, Bennett Creek, and Interstate 270 to the east. The western boundary includes the Monocacy River, Greenfield Road, and a portion of MD 28, Tuscarora Road. The Planning Area ends at Frederick County's southern border with Montgomery County. See Map 1-1 for a graphical representation of the Sugarloaf Planning Area.

The most prominent and defining feature of the Sugarloaf Planning Area is Sugarloaf Mountain, a unique and isolated geologic feature known geologically as a "monadnock." A monadnock is a type of mountain and is what remains after surrounding lands have eroded over the course of millennia. Sugarloaf Mountain rises 800 feet above the surrounding flat lands and is comprised of Sugarloaf Quartzite, a large, white quartzite stone resistant to erosion, with tight fracture joints intermixed with slate and phyllite. Rising 1,282 feet above sea level, Sugarloaf Mountain has two primary summits, as well as accessory ridgelines with lesser peaks and lower elevations.

Adding to the Sugarloaf Area's grand, natural resplendence is the Monocacy Natural Resource Management Area (MNRMA), which consists of approximately 1,800 acres under management and ownership of the Maryland Department of Natural Resources (DNR). These public lands are adjacent to



Urbana District No. 7. In: *Atlas of Frederick County Maryland*. Philadelphia, PA: C.O. Titus & Co., 1873. As reproduced by: Unigraphic, Inc., 1976. Page 21



the Monocacy River and the privately-owned Sugarloaf Mountain and contain expansive forestlands, fields, and agricultural lands. Ecological research and environmental studies are conducted at MNRMA, including riparian buffer research and experiments with rotational timber harvesting, deer exclusions, and agroforestry practices. Map 1-2 displays the locations of the MNRMA, lands comprising Sugarloaf Mountain, and other private lands under protective conservation easement.

Sugarloaf Mountain towers above a landscape of forestlands, low hills, streams and rivers, agricultural fields, and very low-density residential development. The roadway network today mirrors its late-19th century antecedents on the 1873 Titus Map. The iconic mountain contributes significantly to the area's unique place identity. In a landscape setting with distinctive scenic qualities, rich natural assets, and a unique history, the mountain dominates the visual landscape for miles around.

Sugarloaf Mountain is the centerpiece in an expansive assemblage of natural communities, ecosystems, connected forestlands, and open space that include the C&O Canal Historic Park, Monocacy Natural Resource Management Area, Little Bennett Regional Park, Montgomery County's Agricultural Reserve, and the Monocacy and Potomac River systems. These linked landscapes comprise a larger ecoregion in southern Frederick County and northern Montgomery County.


The exceptional beauty, expansive forest cover, and rural qualities of the landscape around Sugarloaf Mountain also make the area an attractive place in which to live. Small, distinctive, historic communities — Buckeystown, Comus, Hyattstown, Barnesville, Beallsville — are nestled in the mountain's environs and are emblematic of the area's historic economic value, as well as its rural qualities and characteristics. However, the character of an area and the health of the land can change over time. Land use changes are shaped by a wide variety of factors including demographic trends, economic markets, access to transportation infrastructure, laws and regulations, social and cultural preferences, politics, and technology.

Policy 1.1	Support natural resource protection, respond to climate change, and ensure the scale and location of development is compatible with surrounding rural land uses and achieves the Vision for the Sugarloaf Planning Area.
Policy 1.2	Protect the scenic landscape character and rural setting of the Sugarloaf Planning Area to ensure its continued beauty and unique charm.
Policy 1.3	Ensure that residents, businesses, and students have access to practical and affordable high-speed data services.



Map 1-1

Planning Area Boundary






Map 1-2

Sugarloaf/Stronghold, MD Department of Natural Resources (MD-DNR), and Conservation Easements

Monocacy Natural Resource Management Area and Urbana Lake
Maryland Environmental Trust Easement
MD-DNR Easements
Stronghold Inc

Rural Roads
Sugarloaf Study Area





History and Culture

A major impetus for the development of the Sugarloaf Treasured Landscape Management Plan is the historic and cultural status of the Sugarloaf Area in Frederick County and the surrounding region. Its location and natural characteristics, while important in many critical ways, are best understood as the catalysts for decisions — large and small — made by communities and individuals over the previous three centuries. The sum of these decisions, whether made by farmers, merchants, industrialists, soldiers, or adopted Frederick Countians such as Gordon Strong, have given us the Sugarloaf area we know today.

In addition to providing residents, business owners, land stewards, and planners with a basic inventory and deeper comprehension of the many historic and cultural resources that remain in the Sugarloaf area, the following section of the plan gives us something that is arguably of greater importance. It gives us critical insight into why we are developing a plan in the first place.

The historic and cultural resources of the Sugarloaf area, and the stories they continue to tell us, should inform the decisions we make on behalf of our future selves. Let us understand the historic and cultural context of Sugarloaf Mountain and use this understanding to establish a plan for the area that protects its character, honors its past, expands and improves its environmental and economic vitality, and establishes a clear direction for public and private decision-making over the course of the next generation.

European Settlement

Forests covered the area prior to European settlement. Native Americans were the first to utilize the area for camps, seasonal hunting, and migration. Archeological evidence of hunting trails and camps have been identified along the Potomac and Monocacy Rivers. European fur traders were next to find use in the Sugarloaf Mountain area in the late 16th and early 17th centuries, including Christoph de Graffenreid who was the first to name and describe the mountain in 1712. A few years earlier, in 1707, Louis Michael made a map of the Potomac area that included the mountain ranges and Sugarloaf.

English and German settlers began to permanently settle in the area by the 1740s. English settlers were traveling northwest from southern Maryland and Virginia, while German settlers were traveling south from Pennsylvania and New York. The English brought tobacco farming and corn, while the Germans brought small grains and subsistence farming. The German farmsteads also consisted of large bank barns, wagon sheds, corncribs, hog pens, chicken houses, and small shops.

Early Industry

Soon after German and English settlers arrived, local industries were established, first with mills to support the new agricultural uses of the land. The Johnson Furnace, built by Roger Johnson — whose brother was Thomas Johnson, the first governor of Maryland — was one of the earliest industries to be built in the region in about 1775-1780. This furnace was built near the confluence of the Monocacy and Potomac Rivers and a forge was established on what was known as the "Bloomsbury" tract



General Store in Park Mills Survey District: A former general store, built sometime between 1850 and 1870, is located in the Park Mills Survey District at Bear Branch and Mt. Ephraim Roads. It is identified in Maryland Historical Trust records as MIHP F-7-26. The district is moderately significant for its association with several demolished rural industrial sites in the vicinity that operated from about 1800 to 1870. These industrial sites include the Amelung Glassworks, the Kohlenberg Glassworks, the Fleecy Dale Woolen Factory, and the Ordeman's Distillery.



Amelung Glass: From 1795 to 1875, a factory called the New Bremen Glass Factory run by John Frederick Amelung operated in the Sugarloaf area and rivaled many European glass factories in its size. Amelung's production is best known from a small group of copper-wheel-engraved covered goblets and flips — large flaring glasses — now in museums and private collections.

on Bennett Creek. The pig iron produced at Johnson's Furnace was taken in shallow draft barges up the Monocacy River and onto Bennett Creek during high flows to the Bloomery forge near Urbana for the production of bar iron. In 1784, Johann Friedrich Amelung established a glass works near the Park Mills village, the New Bremen Works on Bennett Creek, followed by Adam Kohlenberg's glass factory near the same location. These mills and industrial sites are no longer standing; however, a few houses associated with the Johnson Furnace and Amelung's glass works are extant. Other industries that were established in the Sugarloaf area by the mid-1800s include stone and slate quarries. The principal rural industries continued to be small service shops such as blacksmiths, wheelwrights, cobblers, distilleries, lumbermills, and flourmills.

Transportation

In addition to the industrial and agricultural development occurring in the region in the 18th and 19th centuries, the transportation network was also growing. Charles Varle's 1808 map of Frederick and Washington counties shows only the Georgetown Turnpike constructed near Sugarloaf Mountain. On Titus' 1873 atlas, several roads, the Baltimore and Ohio Railroad, and the C&O Canal are depicted. The C&O Canal began

construction on July 4, 1828 and reached the Sugarloaf area in 1833 with the completion of the 516-foot-long, seven-arch aqueduct over the Monocacy River. The Metropolitan Branch of the B&O Railroad, a portion of which runs between Point of Rocks and Dickerson southwest of Sugarloaf Mountain, was completed in 1873. The B&O provided a direct rail connection to Washington, D.C., as well as points west. The enhanced transportation network provided access to more markets for the industries and farmers in the region.

The improved transportation network also brought tourism from areas such as Washington, D.C. One such tourist who travelled to Frederick County in 1899 was Gordon Strong, who was in search of a secluded retreat. After exploring the Catoctin Mountains, Strong was on his way back to Washington when he noticed the physical prominence of Sugarloaf Mountain and took an interest in the area. In the early 1900s, Strong began to acquire large tracts of land on the mountain, developing the property as a private preserve, while also pursuing philanthropic goals. At the time of his death in 1954, he had amassed over 2,000 acres, including the mountain. Strong conveyed the land to a private, non-profit corporation, Stronghold, Incorporated, for the long-term care of the land. Since its inception, Stronghold has made the property available to the public for the enjoyment of nature and outdoor beauty. Principal historic resources onsite include two large Georgian Revival mansions, a vocational school, and two local schools. The property also includes formal gardens near Strong Mansion, hiking trails, and overlooks around the mountain summit.

In 1990, Sugarloaf Regional Trails, a volunteer group dedicated to the conservation and preservation of historic resources in the Sugarloaf Mountain area, completed a National Register nomination for the Sugarloaf Mountain Historic District. The nomination included approximately 16,000 acres of cultural landscapes and natural areas around Sugarloaf Mountain in both Frederick and Montgomery Counties. This nomination involved surveying historic architectural and cultural resources and researching the history and significance of the area. Influence of early German settlement and distinct regional characteristics (especially before 1830) are apparent; however, a variety of building materials and styles are also evident.

While the Sugarloaf Mountain Historic District was not submitted to the National Park Service for consideration, it was determined eligible for listing on the National Register by the Maryland Historical Trust (MHT), the State Historic Preservation Office. This determination triggers a review of projects by the MHT for compliance with State and federal laws only if State or federal funds, licenses, or permits are involved. In such cases, MHT determines if cultural resources within the district will be impacted and seeks to mitigate the effects. The surveyed area is inventoried in MHT's database as MIHP F-7-120.



Flint Hill Methodist Church is located off of Park Mills Road with a cornerstone in the southeast corner stating "Flint Hill Church 1898." It is identified in Maryland Historical Trust records as MIHP F-7-30. The building is framed construction with gothic windows and an extended tower and belfry on the façade.



The Abraham R. Simmons House, located off of Thurston Road, is a two-story log dwelling with a modern addition. The house was probably built circa 1850 in the vicinity of a mill known as Simmons Mill (now demolished) on Bennett Creek. The house likely had a two-story porch on the façade, which has been replaced with a deck. The Maryland Historical Trust records identify this historic resource as MIHP F-7-72.



Strong Mansion



Gordon Strong's former vocational school at the intersection of Comus Road and Sugarloaf Mountain Road.



Also part of the Park Mills Survey District, located off of Bear Branch Road, this two-story stone dwelling is three bays wide with a central entrance and was built about 1820-1850.

Small communities and villages were established in the immediate areas surrounding Sugarloaf Mountain, including Park Mills, Hope Hill, Flint Hill, and Della. The small village known as Park Mills grew near the glass works industries and included a couple of small general stores, a few residences, a school, and a church. Hope Hill and Della were African-American communities built largely by formerly enslaved persons at the edges of the farms and industrial sites where they worked. Della was located on the Monocacy River near Greenfield Mills and centered on the St. Paul's A.M.E. Church. Hope Hill, located in the northern part of the Planning Area, is where the Hope Hill A.M.E. Church and the Hope Hill Colored School still stand today near the center of the original settlement.

The 20th century brought a few notable changes to the landscape of the Sugarloaf area. By the 1930's, several farms in the region had switched their operations to dairy farming to meet increased demand from the expanding Washington, D.C., regional market. Additionally, following World Wars I and II, much of the local agricultural labor force left to work in cities. As employment in the Washington, D.C., region increased, and as the U.S. government incentivized suburban development through lending programs serving returning military veterans, commuting became convenient and necessary. Interstate 270, which borders the eastern edge of the study area, was built during the 1950's as US 240 connecting Washington, D.C., with its burgeoning suburban communities in Montgomery and Frederick Counties. Lily Pons, an aquaculture operation, was established during the early 20th century on the western edge of the area near the Monocacy River. A few small residential developments were established on former farmland in the late 1960's and early 1970's. Two golf courses and two power transmission lines were developed during the latter half of the 20th century in the planning area. The golf courses, both 18-hole facilities, include a clubhouse, restaurant, and maintenance buildings, and were approved in the late 1990's under the agricultural zoning regulations in place at that time. Despite this development activity and the success of Sugarloaf Mountain as a natural, recreational, and educational destination primarily accessed by motor vehicles, rural gravel roads still exist in the area including Peters Road, Banner Road, Monocacy Bottom Road, Page Road, Mt. Ephraim Road, and Comus Road, plus portions of Roderick Road and Sugarloaf Mountain Road.

Most building types in the Sugarloaf area in the mid-18th through 19th centuries were of log and stone construction. Homes were often expanded as needed with rear wings and additional stories, while weatherboard siding was frequently added to log structures. For the most part, the houses in the study area follow a vernacular style of architecture, typically L-shaped farmhouses with a gable roof or side gabled houses. Very few structures exemplify a more refined or high style of architecture. Gordon Strong's Georgian Revival mansion

and Johann Amelung and Roger Johnson's Georgian-style masonry houses are some of the better examples of buildings demonstrating the formal styles of the day.

Today, portions of the Sugarloaf area look similar to their appearance in the early 20th century. Nearly 90 historic resources have been identified in the planning area; however, in many cases these resources are deteriorating or have been altered so as to diminish their historic integrity. Without further protection for these cultural resources, this rural area will lose a significant feature of its history and character.

The Appendix contains a listing of properties and sites in the Planning Area that are listed on the National Register of Historic Places and/or the Maryland Inventory of Historic Properties. Also included is a list of historic properties from the County's 1993-1995 Urbana Region Field Survey, which describes properties and sites that are potentially significant, and the 1993 Stronghold Survey District Form.



George W. Horman House, located off of Roderick Road, is a circa 1901 Queen Anne style house that has had moderate exterior alterations. The house was once part of a thriving dairy farm that included a milking barn, a silo, a milk house, and a dairy processing and bottling building. Today the dairy barn, silo, and milk house still exist. George Horman and his sons Elmer, Russell, George, and William ran the dairy farm in the first half of the 20th century under the name "Tip Top Dairy."

Policy 2.1 **Design new buildings, subdivisions, infrastructure, and signs in the Sugarloaf Planning Area to be compatible in scale and siting with existing, adjoining historic structures and settlements.**

Initiative 2A	Develop historic context statements for the Planning Area, with potential themes including prehistoric use of the area, the communities established by African-American residents, and settlement and development from 1700 to the 1960's.
Initiative 2B	Utilizing research from the context statements, conduct architectural and archaeological surveys to identify sites of significance in the Planning Area.
Initiative 2C	Update the Maryland Inventory of Historic Properties for the Planning Area.
Initiative 2D	Pursue a National Register District nomination for the Stronghold Survey District, which is included in the Maryland Inventory of Historic Properties as record F-7-32.
Initiative 2E	Actively promote the Frederick County Rural Historic Preservation Grant Program to eligible property owners in the Sugarloaf Planning Area.
Initiative 2F	Study the creation of a locally designated Rural Historic District within the Sugarloaf Planning Area.

Sugarloaf Mountain in the Civil War


Sugarloaf Mountain stood at the heart of troop movements, military encampments, and minor skirmishes during America's Civil War. The mountain played an important role in the prelude to the catastrophic Battle of Antietam. Although Maryland did not secede from the Union, many men from Montgomery and Frederick Counties crossed the Potomac River to join up with the Confederate fighting forces.

Because of its strategic location and unimpeded view, Sugarloaf's summit (then owned by William Corcoran) became a signal station for the Union cause and served as a field training center for the Signal Corps. Signals were relayed back and forth across the countryside from the mountain ridges to the west and on to Poolesville and Washington, D.C., through the use of signal flags, flares, and telegraph.

On a day in early September 1862, a Lieutenant Miner was in command of the Sugarloaf signal station. What he saw from the summit that day was the prelude to what still stands as the bloodiest single day in American history: the Battle of Antietam. Miner signaled news of his observations on toward the capital in Washington, D.C., where George McClellan's Union forces were gathering. Lee's army was crossing the Potomac River into Maryland at White's Ford (about a mile downriver from the present-day Dickerson Conservation Park).

Soon after the White's Ford crossing, Confederate forces captured the Sugarloaf signal station and held it for several days before it was recaptured by Union forces. During the war at least one makeshift hospital was set up at the base of the mountain in a cottage that still stands. Many Civil War artifacts have been recovered on and near the mountain, including buttons, shells, swords, and bullets.

From *Sugarloaf. The Mountain's History, Geology, and Natural Lore* by Melanie Choukas-Bradley with illustrations by Tina Thieme Brown





Stronghold Incorporated and Sugarloaf Mountain

Sugarloaf Mountain and the immediate adjacent lands owned by Stronghold, Incorporated comprise approximately 3,000 acres. The privately-owned mountain is open to the public for hiking, bird watching, educational activities, and communing with nature. Sugarloaf Mountain is a unique geologic and environmental asset in the region, with its vast woodlands, distinctive topography, biodiversity, and ecological significance, including Wetlands of Special State Concern. Recognizing Sugarloaf's exceptional qualities, the National Park Service designated Sugarloaf Mountain as a National Natural Landmark in 1969. One of just six such sites in Maryland, National Natural Landmarks are chosen for their "condition, illustrative character, rarity, diversity, and value to science and education."¹

Policy 3.1

Promote Sugarloaf Mountain and the surrounding lands owned by Stronghold, Incorporated as a national model for privately-owned, publicly-accessible open space conservation that provides environmental and health benefits to residents of a major metropolitan area.

Forest cover dominates the Stronghold lands; however, approximately 230 acres of agricultural land is also included in the corporation's approximately 3,000 acres. Steeper, rockier sections of the mountain with south- to west-facing slopes contain tree species that are more tolerant of dry conditions, like white and red oak and pine. Flatter sections and areas with northeast to northwest facing orientation are slightly wetter and contain a wider variety of trees and shrubs. The riparian areas and bottomlands contain numerous wooded swamps, small seeps, and springs, plus trees that are tolerant of seasonally-wet conditions. According to the Maryland Department of Natural Resources (Maryland DNR), there are five main forest cover types associated with the Stronghold lands: Oak-Hickory, Oak-Pine, Mixed Hardwood, Northern Floodplain, and Early Successional forests. Common trees include tulip poplar, black oak, chestnut oak, black birch, eastern hemlock, dogwood, and sassafras.

The quartzite that forms Sugarloaf Mountain causes soils to be acidic in nature, supporting an array of plants that thrive in this type of soil. The understory forest includes mountain laurel, pinxter flower, flowering dogwood, wild hydrangea, and maple-leaved viburnum. Native wildflowers like pink lady's slipper, Canada mayflower, and rattlesnake weed are found in pockets of soil and rocky outcrops all over the mountain. Along streams and in swampy areas, skunk cabbage dominates, along with species including downy arrowwood, yellow corydalis, tall meadow-rue, and marsh blue violet. The mountain and surrounding lands provide habitat for many animals, such as deer, fox, bear, coyote, bobcat, and mountain lion. Birds, such as the red-shoulder hawk, wild turkey, pileated woodpecker, and great horned owl, as well as smaller migratory birds like the scarlet tanager and black and white warbler are present on the mountain and surrounding lands.

The forestlands of Sugarloaf Mountain contain State Forests of Recognized Importance (FORI). According to the DNR, these woodland areas contain exceptional ecological, social, cultural, or biological resource value. The forested areas that comprise the Bear Branch Watershed are a State-identified FORI. The majority of the Stronghold lands are also part of the State's Green Infrastructure Network and within Ecologically Significant Areas (ESA) as described by the DNR's Wildlife and Heritage Service. ESAs are buffered habitats of rare, threatened, and endangered species, as well as significant or rare habitats and ecological systems. Some of the plant populations at the Sugarloaf Mountain ESA have a Maryland conservation status ranking of "Highly State Rare" and "State Rare," indicating the organism is at high or very high risk of extinction or extirpation due to restricted or very restricted ranges, few or very few populations or occurrences, steep or very steep declines, severe or very severe threats, or other factors.



Mountain view from Mt. Ephraim Road

Sugarloaf Mountain's forests and the surrounding forestlands in the Sugarloaf Planning Area are part of Maryland's Lower Monocacy-Potomac Forest Legacy Area. Maryland has eight (8) Forest Legacy Areas which, according to MD-DNR, have the highest environmental and economic value that benefit Maryland's wildlife, wood products industry, and residents. Forest Legacy Areas possess one or more of the following characteristics:

- Is threatened by present or future conversion to non-forest use or fragmentation into smaller non-contiguous forest tracts
- Support ecologically significant forests, including habitat size and quality, and importance for water quality and biodiversity
- Support forests with high economic potential
- Support outdoor recreation and natural resources through proximity to scenic resources and publicly protected lands

The Forest Legacy Area designation identifies these critical lands and, in conjunction with the U.S. Forest Service, provides programmatic funding for perpetual conservation easements or fee-simple purchase of forestlands from willing landowners.



Mountain view from Peach Tree Road

The Many Roles of Stronghold, Incorporated: Nature, Recreation, and History

In 1946, Gordon Strong created Stronghold, Incorporated, a 501c(3) non-profit corporation, and an irrevocable trust to fund the preservation of the mountain, acquire more land, and maintain the park and Strong Mansion. Stronghold's mission is to promote environmental education and appreciation.

Stronghold's sustainable management of the land is evidenced by numerous Forest Stewardship Plans (1948, 1966, 1979, 1987, 1992, 2010, 2014, 2019) prepared by the DNR to address forest and tree health, sustainable supply of tree products through sound timber harvest management, biodiversity, and carbon sequestration. In addition to the Forest Stewardship Plans, Stronghold, Incorporated has engaged in other notable forestry initiatives over the years, including:

- A pine plantation established in 1966.
- Riparian forest buffer plantings through the Conservation Reserve Enhancement Program (CREP).
- Experimental chestnut tree plantings.
- Timber harvest demonstration areas, where five methods have been employed to evaluate and study forest recovery over time.
- Control of gypsy moth, oak spanworm, and other invasive species.

Gordon Strong, a patent attorney and conservationist, visited Sugarloaf in 1902 and was immediately charmed with its breathtaking beauty and serenity. Over the next several decades, he slowly acquired the tracts of land that comprise most of today's Sugarloaf Mountain. Gradually, the property was improved with roadways, landscaping, and buildings, including his own residence, a Georgian Revival mansion. Strong envisioned Sugarloaf Mountain as a place that everyone could enjoy and opened the more picturesque portions of the mountain to the public in 1926. Upon Strong's death in 1954, he bequeathed most of his fortune to an irrevocable trust, and all of the land he acquired to Stronghold, Incorporated. Gordon Strong's desire to open his mountain to the public was based on his belief that "those who appreciate natural beauty will be better people, people who will treat others with respect."

(From Sugarloaf Mountain: The Promise of Private Parkland by Daniel T. Oliver, May 2000)

Standing Strong for Sugarloaf

Two Men and Their Competing Visions for the Mountain

For a brief moment in the 1920's, America's pre-eminent architect of the period focused his efforts on the development of a grand structure to occupy the crest of Sugarloaf Mountain. It was never built.


Frank Lloyd Wright, the charismatic and influential architect whose work in the Chicago area earlier in the century piqued the interest of Gordon Strong, was beginning a period of exploration utilizing new geometric forms in his designs for buildings such as the National Life Insurance Building (Chicago, IL 1924), the San Marcos-in-the-Desert Resort (Chandler, AZ 1928), and a structure that would be known as the Gordon Strong Automobile Objective, to be constructed atop Sugarloaf Mountain, south of Frederick, Maryland. While none of these projects would come to fruition, the ideas born during their development provided Wright with design elements that he would use throughout the remainder of his long career.



Frank Lloyd Wright and his wife, Olgivanna, in their 1937 A.C. Roadster at Wright's Taliesin West studio complex in Scottsdale, Arizona (Photo Credit: Dr. Joe Rorke)

In the Summer of 1924, Strong met with Wright to discuss possible designs for "a structure on the summit of Sugar Loaf Mountain" that would "serve as an objective for short motor trips" emanating from Baltimore and Washington, D.C. Seeking to create a destination that would enhance visitors' enjoyment of the views from the top of the mountain, Strong indicated that he wanted the architect to incorporate the "element of thrill, as well as the element of beauty" further stipulating that the destination's appearance be "striking, impressive...enduring, so that the structure will constitute a permanent and credible monument."

Wright's initial schemes varied, incorporating various uses for the structure as well as various vertical tower elements, perhaps to be used for radio transmissions or as a mooring post for dirigibles. Strong's original concept for a dance hall became a theater in an initial scheme of Wright's. In its final iteration, developed in the Summer of 1925, the Automobile Objective would include a domed planetarium, natural history exhibits, restaurants, and even accommodations for overnight stays. But despite the changing program, Wright's designs all centered around the simple and elegant idea of the spiral. The circular ziggurat-style provided the perfect form — and a practical mechanism — for bringing automobiles onto the structure in such a way as to allow passengers unobstructed panoramic views of the surrounding countryside. With a domed structure serving as a solid armature, the intertwined vehicle ramps could be cantilevered and articulated to encase the dome in an organic wrapper of concrete and glass block. Visitors would be able to park their vehicles and enjoy similar views of the surrounding landscapes from an additional layer of cantilevered structure circling the dome.




Design drawings of Automobile Objective
Images copyright of the Frank Lloyd Wright Foundation, obtained from the Library of Congress.

Working from detailed topographic mapping provided by Strong, Wright designed a building that made good use of the existing landforms. Promenades linked visitors to adjoining natural features, including a second summit, allowing an array of outdoor activities to complement those provided inside of the building. Furthermore, Wright's design evolved between 1924 and 1925 in a way that attempted to enhance and complete the natural features of the existing mountain rather than to compete with those elements of the terrain that defined Sugarloaf.

Despite the architect's efforts, Gordon Strong ultimately rejected Wright's design believing that the plan did not allocate space appropriately and violated the integrity of the mountaintop.

Wright's response to the criticism revealed his feeling of personal rejection as well as the financial difficulties he had begun to experience during this period: "I have given you a noble 'archaic' sculptured summit for your mountain. I should have diddled it away with platforms and seats and spittoons for... expectorating businessmen and the flappers that beset them." (Letter from Wright to Gordon Strong, Oct. 20, 1925)



Rendering by David Romero, architect and 3dD visual artist, www.hookedonthepast.com

In the years following the Sugarloaf design work, Frank Lloyd Wright continued to find ways to exploit his understanding of the spiral form in other projects including his V.C. Morris Gift Shop (San Francisco, CA 1948), the Point Park Civic Center (Pittsburgh, PA 1947/unbuilt), and the Baghdad Cultural Center (Baghdad, Iraq 1957/unbuilt). However, it is in one of his most notable works that contemporary lovers of architecture see most clearly the DNA of the Gordon Strong Automobile Objective once planned for Sugarloaf Mountain: New York City's Solomon R. Guggenheim Museum (1943-1959). It is in The Guggenheim that Wright's vision for an architectural spiral of movement takes form as an inverted ziggurat. Instead of automobiles looking outward over a landscape, the program accommodates strolling art lovers — on foot this time — observing and enjoying the creative output of painters, printers, and sculptors.


Would a monumental structure designed by Frank Lloyd Wright sitting atop Sugarloaf Mountain have altered the history of the Stronghold properties? Would its existence have reshaped our perception and appreciation of the surrounding landscapes, or the mountain itself? One thing remains absolutely clear to the many thousands of people who visit the mountain or live in its midst...in rejecting a design by one of American architecture's most powerful and driven personalities, Gordon Strong did indeed stand strong for the mountain and for those who wake up in its shadow each day. And for those visiting the Stronghold property, there is no doubt that their "objective" is the mountain itself.

To see a circular ziggurat, there is always the Guggenheim, a mere 250 miles to the north.



Guggenheim Museum in New York City

1909 plat showing Gordon Strong's parcel acquisition.




Initiative 3A Work with Stronghold, Incorporated, the State of Maryland, and Frederick County Tourism to clarify Sugarloaf Mountain's status as a privately-owned and operated park.

Initiative 3B Collaborate with Stronghold, Incorporated and DNR to explore the desire and feasibility of extending and connecting the Monocacy Natural Resource Management Area's Rustic Trail Network to the Sugarloaf Mountain trail network to create a longer and linked trail system.

Stronghold's stewardship mission, including free access to the mountain, reflects significant elements of the "public trust doctrine," whereby Sugarloaf exists, essentially, as a resource held in custodianship

Aerial photograph overlaid on 1909 Gordon Strong plat. The mansion and overlook lanes are visible.




— or trust — by the Stronghold Board of Directors for the benefit of the public. In cooperation with Stronghold, private and public sector entities can help perpetuate this arrangement to ensure continued public access to the mountain, wildlife protection, and sustainable management of the mountain's environmental and cultural resources with no diminution in size, environmental function, or resource integrity.

Initiative 3C Partner with Stronghold, Incorporated to establish mechanisms to ensure long-term public access to Sugarloaf Mountain and identify ways in which the Frederick County community (residents, government, private organizations) can assist in these endeavors.

The Maryland State Highway Administration promotes Sugarloaf Mountain as a regional resource by grouping the privately-owned Sugarloaf Mountain with federal, state, and local public parks and public recreational lands on roadway signage with identical coloring, lettering, and formatting for all facilities. Identical signage for the private Sugarloaf Mountain and the public parks in the region has created confusion among users related to the differences in operational management between the public and private recreational resources.

Initiative 3D Initiate inter-governmental communication with the Maryland State Highway Administration to request a revised signage palette along I-270 and Comus Road for Sugarloaf Mountain that contains variations in color, style, and type design to distinguish the privately-owned mountain from publicly-owned parkland.



The Sugarloaf post office mural in its original (and current) location within a Rockville, Maryland police substation that formally was a post office



Postcard view of the U.S. post office in Rockville, Maryland where Sugarloaf mural was installed in 1940.

2019




ROCKVILLE, MD

POST OFFICE MURALS / ~~FOREVER~~ / USA



Sugarloaf Mountain appeared on a U.S. postage stamp in 2019 as part of a series celebrating the post office murals of the 1930's and 1940's

Photo of Judson Smith (1880-1962), the American painter who painted the Sugarloaf mural (courtesy Peter A. Juley & Son Collection, Smithsonian American Art Museum, J0070621)



From its inception in 1946, the Stronghold Trust was created to exist for 100 years. The Trust's sunset in 2046 should not presage the end of Gordon Strong's foresighted protection of the natural resources, forestlands, and wildlife habitats of Sugarloaf Mountain. Will Stronghold's future operational status and management continue to realize Gordon Strong's vision of Sugarloaf Mountain as memorialized in Stronghold, Incorporated's mission — environmental protection, education, and appreciation of natural beauty? Will the lands be managed to ensure continued abundance of wildlife and preservation of the habitats on which they rely? Will opportunities for enjoyment of these wildlands be provided in perpetuity for all people in future generations?

The enduring preservation of the geologic uniqueness and ecological significance of Sugarloaf Mountain — and all of the Stronghold lands — is critically important for our environmental heritage and legacy. Momentum gained over the past century sparked by Gordon Strong's conservation ethic calls for modern approaches to ensure that the Stronghold lands and their environmental health, ecological resilience, and biodiversity will be permanently protected.

Initiative 3E Support the preservation of Stronghold, Incorporated's 3,400 acres through a conservation easement device to ensure permanence and protection of all of its resources — cultural, environmental, historic — with no reduction in size, integrity, or ecological function.



Mountain view from Greenfield Road

View of Sugarloaf Mountain from Dixon Road





Land Use

The Livable Frederick Master Plan's (LFMP) Thematic Plan — a key component of the LFMP Development Framework — broadly reflects a comprehensive vision for Frederick County's future land uses. The Thematic Plan graphically depicts the preferred pattern and geographic distribution of new development in our community growth areas, organized as Primary and Secondary Growth Sectors. The Thematic Plan also illustrates a visionary framework for protecting our natural resource base through the identification of a Green Infrastructure Sector and an Agricultural Infrastructure Sector.

The Green Infrastructure Sector of the LFMP is identified to support the conservation of natural resources and environmentally sensitive areas, to direct urban/suburban growth away from green infrastructure and sensitive areas, and to ensure the protection and integration of green infrastructure within areas targeted for growth. Sugarloaf Mountain and its environs are components of this Green Infrastructure Sector within the LFMP, described as the Sugarloaf Rural Heritage Landscape.

The LFMP's Development Framework includes targeted planning initiatives, such as the creation of large area plans, where the focus is directed upon broad and contiguous areas of the County. The Sugarloaf Treasured Landscape Management Plan is such a Plan.

The Planning Area

The Sugarloaf Planning Area is 17,140 acres in size. Physical proximity and visual relationships to Sugarloaf Mountain, as well as overall landscape-related associations with the prominent landscape feature determined the Planning Area boundary, which is bordered generally by MD 80 (Fingerboard Road) and the historic Hope Hill community to the north, and Thurston Road, Bennett Creek, and Interstate 270 to the east. The western boundary includes the Monocacy River, Greenfield Road, and a portion of MD 28, Tuscarora Road. The Planning Area extends to Frederick County's southern border with Montgomery County.

Two, small historic communities — Flint Hill and Hope Hill — are located in the northern portion of the Planning Area and are designated "Rural Community" on the Comprehensive Plan Map to reflect these older crossroad settlements. A 14-acre surface mining operation on MD 80 in the northwest portion of the Planning Area has approval from the Maryland Department of the Environment's Mining Program for the extraction of shale. This sedimentary rock is used to make bricks and tile and is also used for pottery and in the production of cement.

Land Use Tools

The scale and location of development, and the extent of various land uses in the Sugarloaf Planning Area, are established in County plans and through the County's Zoning Ordinance and Subdivision Regulations. Land use planning, subdivision regulation, and zoning jurisdiction are components of the constitutionally-recognized authority of local governments in the U.S. in order to advance and protect the health, safety, welfare, and morals of a community. The Zoning Ordinance permits over 60 land uses and activities on land in the Agricultural and Resource Conservation Zoning Districts, which comprise 94% of the Sugarloaf Planning Area. Uses permitted in these zoning districts can vary widely in the level of impact on the surrounding community in terms of intensity, occupancy, noise, traffic generation, and environmental footprint. Some of these activities require public review, such as site development plan approval from the Planning Commission, Board of Zoning Appeals approval for a Special Exception or Variance, or simply a building permit or zoning certificate that requires no formal public review process prior to approval by County staff.



Dixon Road

Land Use in the Sugarloaf Planning Area

In addition to residential development, thirteen commercial operations, private institutional centers, and agricultural-related facilities are located within the Planning Area, including golf courses, residential retreat centers, equestrian facilities, and an environmental education center/camp. These are principal permitted uses or uses allowed by special exception in the Agricultural and Resource Conservation zoning districts.

The existing, very low-density development pattern in the Sugarloaf Planning Area, consisting primarily of large-lot, single-family residential dwellings, is suitable for a rural area with significant and sensitive environmental resources. A constrained and limited transportation network, sensitive forested watersheds with high-quality waters, and the surrounding open space and low density, rural characteristics of the Sugarloaf Planning Area warrant further evaluation and scrutiny of new large-scale commercial and institutional land uses or additional residential growth.

Replacement of forests or fields with impervious surfaces, and development of residential, large-scale institutional, or commercial land uses have the potential to disrupt and degrade the rural landscape setting in the Sugarloaf area. Noise from land uses with high occupancy or attendance can disturb the area's tranquility. Localized air quality is negatively impacted by additional traffic-generating land uses.

Policy 4.1 **Limit forest loss, forest fragmentation, and increased impervious cover through modifications to land use designations, zoning classifications, and development densities.**

Sugarloaf Mountain Road



Policy 4.2

Assess future land use changes in the context of the rural character of the Sugarloaf Planning Area.

Septic Systems, Groundwater, and Land Use

All development in the Sugarloaf Planning Area relies on private groundwater wells and on-site sewage disposal systems, commonly referred to as septic systems. The provision of public water and sewer service to the Sugarloaf Area has not been evaluated or planned due to the area's 60+ year history of land use planning for rural, very low-density uses, agriculture, and conservation.

Large institutional and commercial uses have higher effluent generation potential than would be expected for an average, or even a substantially larger-than-average, single-family dwelling. For example, a typical 4-bedroom house would have a septic system designed for a maximum capacity of approximately 600 gallons per day. The volume of effluent and flow rates for institutional uses can be four or five times that of single-family residences. Subsequent nitrogen concentrations entering the ground water can be significant. Large facilities and their considerable septic system needs have the potential for substantial effects on the surrounding environment.

Reducing nitrogen pollution from septic systems is beneficial from a water quality viewpoint and a public health/safety perspective, as well as meeting Clean Water Act requirements. Public health protection has ancillary benefits for aquatic environments.

Policy 4.3


Minimize the growth of new residential development that utilizes wells and septic systems by prohibiting the expansion of the Rural Residential Land Use Designation into Agricultural and Natural Resource areas.

Frederick County is part of the Chesapeake Bay Watershed. All of the County's streams and rivers eventually flow into the Potomac River, which empties into the Chesapeake Bay. In 2009, Executive Order 13508, Chesapeake Bay Protection and Restoration,¹ was issued, declaring the Chesapeake Bay a "national treasure constituting the largest estuary in the United States and one of the most biologically productive estuaries in the world."

The U.S. Environmental Protection Agency (EPA) established the Chesapeake Bay Total Maximum Daily Load (TMDL) on December 29, 2010.² The TMDL and its subsequent Watershed Implementation Plans (WIPs) established maximum pollutant (nitrogen, phosphorus, sediment) levels that can enter the Chesapeake Bay, as well as the actions needed to reduce the sources of these pollutants in our waterways: agricultural land uses, stormwater runoff from developed lands, wastewater treatment plants, and on-site waste water disposal systems.

While not the largest source of nutrients to the Chesapeake Bay, septic systems do contribute approximately 8 million pounds of nitrogen to the Bay annually, representing approximately 4% of the overall load to the Bay.³

Nitrogen concentrations of influent to septic systems will vary, but typically average about 60 mg/L, with concentrations from some institutional uses (schools) as high as 72 mg/L nitrogen.⁴ The Chesapeake Bay Program Watershed Model uses a nitrogen concentration figure of 39 mg/L in the effluent leaving a drainfield from a single-family dwelling. Traditional septic systems discharge approximately 9 pounds (lb)/person/year of nitrogen from the drainfield into groundwater, which over time flows into one of the thousands of streams on the landscape, following partial attenuation in the soil. Alternative treatment components can be added to a traditional septic system, often between the septic tank and the drainfield, which can reduce this nitrogen load by 50%.⁵



Sole Source Aquifer

A portion of the Sugarloaf Planning Area lies within the Piedmont Sole Source Aquifer (SSA), which also includes portions of Green Valley in Frederick County and large parts of upper Montgomery County, Maryland. Drainage basins in Frederick County within the SSA include portions of the Bennett Creek Watershed and the Little Bennett Creek Watershed, as shown on Map 4-1 at the end of this chapter. Designated by the U.S. EPA in 1980 (45 FR57165, 08/27/80), the SSA is defined as a sole or principle source aquifer that supplies at least 50% of the drinking water consumed in the area overlying the aquifer. These areas may have no alternative drinking water source(s). Impacts to the aquifer could physically, legally, and economically affect all those who depend on it for drinking water.

The EPA's SSA program provides federal oversight of federally-funded projects within the designated area. According to the federal Safe Drinking Water Act, once SSA designation is obtained, projects that could contaminate the aquifer may not receive federal financial assistance. Although this may not stop a project, it will put it within the purview of the EPA, which will seek to mitigate any adverse consequences. Projects and land uses that are not federally-funded are not subject to federal oversight under the SSA program.

Whenever feasible, the EPA coordinates review of proposed projects with other federal, state, or local agencies that have a responsibility for groundwater quality protection. This coordination helps the EPA understand local hydro-geologic conditions and specific project design concerns, and ensures that the SSA protection measures enhance and support existing groundwater protection efforts.

As the entire Sugarloaf Planning Area relies on private wells, simple groundwater analysis is a planning tool that can identify groundwater pollution risk and potential problem areas. Selective well testing combined with analysis of physical features that affect groundwater conditions, such as soil type and infiltration capabilities, slope, and depth to the water table, can identify characteristics of GUDI — groundwater under direct influence of surface water. This in turn helps determine the source of any identified groundwater contamination.

Initiative 4A **Expand the County's stream survey program to include monitoring of local groundwater conditions and aquifer recharge areas, with a focus on the northeast portions of the Sugarloaf Planning Area adjacent to lands with existing or planned higher density development, in order to study land use impacts to groundwater resources. The Sugarloaf Planning Area relies solely on groundwater wells and contains a portion of the Piedmont Sole Source Aquifer.**

Sensitive landscape areas where GUDI occurs include wetlands and spring/seep/sink areas where water moves between surface and subsurface conditions. The most well-known sources of groundwater pollution include improperly protected well heads or abandoned wells, poorly designed or functioning septic leach fields, or leaking storage tanks containing petroleum products or other hazardous substances or aquatic pollutants. Environmentally sensitive areas where surface water, including stormwater runoff, can mix with groundwater require vigilant protection.

Initiative 4B **To assure that nitrogen inputs to ground and surface waters are minimized, and to help safeguard the Piedmont Sole Source Aquifer, consider, in consultation with the Health Department, the requirement for all non-residential land uses in the Sugarloaf Planning Area to utilize Best Available Technology (BAT) for new or replacement on-site sewage disposal systems.**

Initiative 4C **Evaluate the need for coordinating the staffing, training, and equipment at the Urbana Volunteer Fire and Rescue Company and the Hyattstown Volunteer Fire Department in order to respond to a hazardous material spill within the Piedmont Sole Source Aquifer along I-270 and local roadways in both Montgomery and Frederick Counties.**

Livable Frederick Master Plan, Thematic Plan Diagram, and Comprehensive Plan Map

The Sugarloaf Planning Area land use designations depicted on the County Comprehensive Plan Land Use Map are shown on Map 4-2 and described in the 2010 County Comprehensive Plan as follows:

Natural Resource. This designation identifies significant natural resource features and provides guidance for the application of the Resource Conservation zoning district and other protection strategies. The primary environmental features with this designation include mountain areas, contiguous forestlands, major stream systems, and the State's Green Infrastructure elements.

Agriculture/Rural. Applied to lands outside of the Community Growth Areas, the Agricultural/Rural designation may include active farmlands, fallow lands, and residential lots and subdivisions that have been developed under the Agricultural Zoning District.

Rural Community. This designation recognizes existing rural communities that have historically developed as cross road communities with an identifiable concentration of residences and, in some cases, commercial uses.

Public Parkland/Open Space. Applied to lands primarily under public ownership for local, state, or federal parklands, this designation is also applied to watersheds that protect public water supplies. Additionally, it may also be applied to large land holdings under private ownership which may have some degree of protection from land development.

Rural Residential. The intent of the Rural Residential designation is to recognize areas of existing major residential subdivision that utilize private wells and individual septic systems, and are located outside of Community Growth Areas. Rural Residential areas are not intended to be served by public water and sewer and should not be expanded into surrounding agricultural or resource lands.

Mineral Mining. Applied to areas under active mining operations and more recently has been applied to areas where future mining and associated activities may occur. The corresponding zoning district is Mineral Mining (MM), which is a floating zone that can only be applied through a piecemeal rezoning process. The MM zoning district also permits associated processing uses related to mining such as asphalt plants and concrete block manufacturing.

The current land use plan designation of "Public Parkland/Open Space" is applied to the lands owned by Stronghold, Incorporated as well as the State of Maryland. A new land use plan designation for the Stronghold lands is recommended in order to better describe, signify, and distinguish these properties from lands owned by the U.S. Government, the State of Maryland, or Frederick County. The unique Comprehensive Land Use Plan designation proposed for the lands owned by Stronghold, Incorporated and Charles Oland is "Treasured Landscape-Sugarloaf." This designation is defined below and shown on Map 4-3 at the end of this chapter.

Treasured Landscape-Sugarloaf. This designation identifies significant forestlands, cultural and historic resources, wildlife habitats, and a unique geologic feature — a monadnock — and its scenic attributes in the form of ridge lines and steep topographical gradients that comprise Sugarloaf Mountain.

Initiative 4D Establish and apply the land use plan designation of "Treasured Landscape-Sugarloaf" in the Sugarloaf Planning Area.

Many portions of the Sugarloaf Planning Area that contain sensitive resources, such as contiguous woodlands, floodplain, steep forested gradients, wetlands, and stream systems, are not fully and accurately depicted with the land use plan designation and zoning classification appropriate for such resources, as described in the Livable Frederick Master Plan and the zoning ordinance. Maps 4-6 through 4-13 reflect the proposed alignment of the Natural Resource land use designation and the Resource Conservation zoning district with the location and extent of environmental resources within the Sugarloaf Planning Area.

Table 1A. Existing Comprehensive Plan Designations within Sugarloaf Planning Area

Comprehensive Plan Designation	Acreage*	Land Area
Natural Resource	4,236	24.7%
Agriculture/Rural	6,799	39.6%
Rural Community	232	1.3%
Rural Residential	568	3.3%
Public Parkland/Open Space	4,722	27.5%
Mineral Mining	18	<1%

*Roadways and their rights-of-way and the Monocacy River comprise the remainder of the acreage within the Planning Area

Table 1B. Proposed Changes to Comprehensive Plan Designations within Sugarloaf Planning Area, July 2021

Comprehensive Plan Designation	Existing	Proposed	Differential
Natural Resource	4,236	4,995	+759
Agriculture/Rural	6,799	5,824	-975
Rural Community	232	232	0
Rural Residential	568	526	-42
Public Parkland/Open Space	4,722	1,797	-2,925
Mineral Mining	18	18	0
Treasured Landscape-Sugarloaf	0	3,183	+3,183

Zoning

The Resource Conservation (RC) zoning district is the primary classification in the Sugarloaf Planning Area, defined below as contained in § 1-19-5.210 of the Zoning Ordinance:

The purpose of the Resource Conservation Zoning District is to allow low intensity uses and activities which are compatible with the goal of resource conservation to be located within mountain and rural wooded areas. Areas within this district include mountain areas, rural woodlands, and cultural, scenic, and recreation resource areas. Environmentally sensitive areas within the Resource Conservation zone, including FEMA floodplain, steep slopes, wetlands, and the habitats of threatened and endangered species, will be protected from development. Current zoning in the Sugarloaf Planning Area is shown on Map 4-4.

§ 1-19-5.220 defines the Agricultural Zoning District: The purpose of the Agricultural District is to preserve productive agricultural land and the character and quality of the rural environment and to prevent urbanization where roads and other public facilities are scaled to meet only rural needs.

All of the lands owned by Stronghold, Incorporated and the State of Maryland within the Sugarloaf Planning Area are zoned RC, as they contain forestlands, environmentally-sensitive lands, aquatic systems, steep topographical gradients, and the distinctive landform — the monadnock — that is Sugarloaf Mountain.

Table 1C. Existing Zoning Districts within Sugarloaf Planning Area

Zoning Districts	Acreage*	Land Area
Resource Conservation	9,225	53.7%
Agricultural	6,931	40.4%
R-1 Residential	672	3.9%
Mineral Mining	18	< 1%
Village Commercial	0.29	<1%

*Roadways and their rights-of-way and the Monocacy River comprise the remainder of the acreage within the Planning Area

Table 1D. Proposed Changes to Zoning Districts within Sugarloaf Planning Area, July 2021

Zoning Districts	Existing	Proposed	Differential
Resource Conservation	9,225	10,244	+1,019
Agricultural	6,931	5,908	-1,023
R-1 Residential	672	676	+4
Mineral Mining	18	18	-
Village Commercial	0.29	0.29	-

Initiative 4E Evaluate the extent and location of natural resources that currently lack the Natural Resource (NR) Land Use Plan designation and Resource Conservation (RC) Zoning, and apply the NR Plan designation and RC Zoning to those resource features, as shown on Maps 4-6 through 4-13.

Land Subdivision

The northern portion of the Planning Area (generally north of Peters Road) is dominated by residential land uses. From the early 1960's to 2020, the exercise of land subdivision within the Planning Area has created 715 residential lots (see Map 4-5 for the location of subdivision lots). Development on these lots is nearly complete, with nearly 90% of the 715 lots containing a dwelling as of December 2020 (Frederick County GIS). In addition to the lots constituted through the subdivision process, the Planning Area also contains many land parcels. With the exception of the majority of Stronghold, Incorporated lands and the DNR holdings, most of the parcels are developed, bringing the total number of dwellings in the Sugarloaf Planning Area, as of December 2020, to 846. An analysis of data from the 2010 U.S. Census shows the area's population to be 2,200.

The RC zoning district, as with most zoning districts, provides the opportunity for property owners to subdivide land parcels to create new lots for purposes of development and establishment of land uses or activities permitted by the Zoning Ordinance. The minimum lot size for new subdivision lots in the RC zone is 10 acres; thus, a 50-acre parcel could, theoretically, create five new residential lots through the current zoning and subdivision regulations.

As previously stated, within the Sugarloaf Planning Area, 715 residential lots of varying sizes have been created through the subdivision process and recorded in the land records. This figure includes remainder parcels within a subdivision, which are counted as lots. The breakdown of lots within each zoning district is shown below:

Table 2. Subdivision Activity by Zoning District within the Sugarloaf Planning Area through 2020

Zoning District	Acreage within Planning Area*	Number of Subdivision Lots	Average Lot Size (ac.)
R-1 Residential	672	339	1.98
Agricultural	6,931	314	22.0
Resource Conservation	9,225	62	148.7

*The remaining zoning districts within the planning area include Mineral Mining, and Village Center, which with road rights-of-way and the Monocacy River constitute the Planning Area's total size of 17,140 acres

Sugarloaf Rural Heritage Overlay Zoning District

The lands owned by Stronghold, Incorporated are some of the most environmentally sensitive areas in the entire Sugarloaf Planning Area. Notwithstanding Stronghold's acquisition and conservation practices, pressure to develop the lands that comprise Sugarloaf Mountain can be expected, simply because of their natural beauty, proximity to the greater Washington-Baltimore region, and general population growth in Frederick County.

Establishment of high-impact, incompatible land uses in one of the most significant natural areas in the County — and State — has the potential to threaten and degrade the natural resources, environments, and character-defining features of the Sugarloaf area. Land development activities can increase impervious cover, traffic, and noise and negatively impact overall ecosystem health. The Sugarloaf Treasured Landscape Management Plan contains policies and initiatives for the protection of the Planning Area's natural resources and the long-term health and integrity of the rural landscape.

For these reasons, and to help achieve the Plan's Vision, the creation of a Sugarloaf Rural Heritage Overlay Zoning District is proposed for the entire Planning Area, as indicated on Map 4-14. The proposed ordinance for the Sugarloaf Rural Heritage Overlay Zoning District, including a statement of purpose and intent, can be found in the Appendix (pp. A-19 through A-26). The objectives and goals of the Sugarloaf Rural Heritage Overlay include the following:

- To address the scale and visual impact of land uses and development that can degrade rural qualities, excessively burden the transportation network, and overwhelm the scenic and rural nature of the Sugarloaf Planning Area
- To minimize adverse impacts of land development activities on forestlands and natural habitats
- To regulate the amount of impervious surfaces to control the volume of stormwater runoff and stream bank erosion, maintain levels of groundwater infiltration, and retain as many of the functions provided by natural land as possible

Initiative 4F Adopt and apply the Sugarloaf Rural Heritage Overlay Zoning District and its ordinance to achieve the goals and vision articulated in the Sugarloaf Treasured Landscape Management Plan.

Urbana Community Growth Area

For nearly 50 years, Frederick County's Comprehensive Plans have identified the development potential along the I-270 Corridor as a major component of the County's future growth. The Urbana community itself has, since the late 1960's, presented a focal point around which could be built a larger community of homes, employment opportunities, and local retail shops and services. The Livable Frederick Master Plan and its Thematic Plan continue to support these related visions for southern Frederick County, providing policy guidance for the maturation of this planning approach.

The Urbana Community Growth Area (CGA) embodies the characteristics of a typical CGA in Frederick County by establishing a finite geographical area within which the County promotes and encourages continued population and employment growth through the provision of critical public infrastructure such as public water and sewer service, public schools, parks, a safe and functional transportation network, and other systems and services necessary to support strong and resilient neighborhoods. In the context of Livable Frederick, a CGA identifies a preferential location for land use conversion and intensification to accommodate future growth that is consistent with County policies and initiatives, as well as with specific community goals.

The I-270 Corridor, long established as a convenient location for existing and planned employment, mixed-use, and industrial uses, incorporates the lands along I-270 and MD 355 from the border with Montgomery County northward to Park Mills Road, just north of the existing Urbana community. The lands in this corridor have served as a thematic extension of Montgomery County's "Technology Corridor" identified in that jurisdiction's planning documents as spanning I-270 from Bethesda to Clarksburg. While much of Frederick County's portion of the interstate corridor remains sparsely developed, areas on the east side of I-270 in the southern fringe of Urbana have developed successfully in the last 15 years bringing over 1,000 jobs (and counting) to our community.

Neither the Urbana Community Growth Area nor the I-270 Corridor has been comprehensively studied or evaluated since the late 1990's. Recognizing this, the Livable Frederick Master Plan Implementation Program (October 2019) in its Planning Area Catalogue described an Elective Plan for a larger, thematically-conceived *Urbana Corridor* that would include one or more plans for the South Frederick Triangle, I-270 Corridor TODs, and the Urbana Community Growth Area. The South Frederick Triangle has now been incorporated into the South Frederick Corridors Plan.

The Sugarloaf Treasured Landscape Management Plan acknowledges the County's need to examine the Urbana Corridor through a new and coordinated planning effort that will address the current growth and development issues in southern Frederick County. Future evaluation of the area outside of, but adjacent to, the Sugarloaf Planning Area is warranted in anticipation of transportation enhancements along I-270 and the subsequent possibilities for mobility and land use options, including the growing sectors of biological sciences and technology services in the I-270 corridor.

The transportation potential of I-270, despite its current limitations for quick and convenient travel by area drivers, is a critical infrastructure investment that has allowed the County to grow and prosper in the years following World War II. As improvements to the transportation function of I-270 are completed in future years, the County cannot afford to summarily dispense with limited growth opportunities on the western side of the highway right-of-way in the vicinity of the MD 80 interchange. These future public and private investments in our mobility may encourage the placement of multi-modal transit centers, compact transit-oriented villages, or growth of Urbana's existing biological and information technology hub along the I-270 corridor.

Policy 4.4 Future planning efforts in the Urbana Corridor (Urbana CGA and the I-270 TOD Corridor) shall include visually attractive and high-quality design elements, enhanced mitigation of negative environmental impacts, and significant improvements to the localized road networks.

Land Conservation

Land conservation has many forms and styles with different functional attributes. Structuring tools for the perpetual management and protection of significant environmental assets requires strategic designs and tactical methods. The goals of the stakeholders influence the structure and function of the conservation instrument. Three major approaches to protect and steward land resources are described below.

Acquisition

A straight-forward preservation technique involves the purchase of land in order to obtain fee simple ownership from a willing seller to protect or conserve the land. The purchaser can be either a public-sector entity (e.g., a county or state), a non-profit or non-governmental organization, or — as in the case of Sugarloaf — a private individual who buys property to preserve in its current state or to improve the land environmentally via tree planting, wetland creation, or other habitat enhancement. Properties are sometimes donated to public or private sector entities for protection purposes. Gordon Strong's foresight and vision created one of the largest areas in the entire mid-Atlantic region of privately-owned, publicly-accessible lands for environmental conservation, education, and appreciation of the natural world's beauty.

Conservation Easements

A more commonly-used device for land protection is a conservation easement. With this approach, the property owner agrees to some use limitation (e.g., subdivision development), protection of existing resources (e.g., forest retention), or landscape enhancement (e.g., new tree plantings or wildlife habitat improvements) in exchange for a payment by a public sector entity or a private organization. Conservation easements can be structured to create tax benefits for the landowner. Conservation easements are legal encumbrances on a property made voluntarily and are normally perpetual, even in the event of a change in property ownership.

Land Use Regulation

Land use regulation through zoning codes and subdivision ordinances is the prescription of specific standards to land uses, physical design, and development densities and scale to achieve a health and safety purpose or environmental, cultural, or historic preservation goals as articulated in a land use

plan. Conservation goals can sometimes be achieved, at least in part, through comprehensive land use plan policies and regulations. If employed to advance conservation goals, zoning — an exercise of a local government's constitutional power — must be used fairly and judiciously, with a direct correlation between the regulatory effects on land owners and the goals to be achieved.

Conservation management of the large and rich landscapes on and around Sugarloaf Mountain have bestowed innumerable benefits to society and the environment. These ecosystem services protect us and our human-constructed systems. Monetary equivalents have even been established for their function and overall societal benefit. Some of these benefits include:

- Protecting air quality through retention of vast forestlands and active forest management for maximum carbon sequestration.
- Maintaining high quality waters through retention of forestlands around aquatic systems.
- Natural filtering of sediments and chemicals in stormwater runoff and better flood control.
- Providing habitat for fish and wildlife, including pollinators and rare, threatened, and endangered species.
- Providing opportunities for educational, scientific, and nature immersion activities.
- Enhancing overall biodiversity, environmental resilience, and quality of life.

The simple formula that Gordon Strong employed to acquire and steward thousands of acres of land is more rare today than common. Current methods for land conservation acknowledge modern-day economic realities and generally involve monetary compensation or tax benefits, or both. Essentially, there is a price for the environmental services that natural lands provide and a price to prevent future alteration or degradation of a landscape and those services.

The following is a listing and short description of various federal, state, and local programs for land preservation that could be engaged in order to foster conservation in the Sugarloaf Planning Area.

Frederick County

Frederick County Installment Purchase Program

In 2002, Frederick County began the Installment Purchase Program for purchasing easements on agricultural land through the use of Installment Purchase Agreements. Agricultural land owners receive tax-free, interest-only payments over a period of 10 to 20 years and a balloon lump sum principle payment at the end of the term.

State of Maryland

Rural Legacy

This preservation program was created as part of the state's Smart Growth initiatives to target properties within large contiguous areas of agricultural and ecological significance. The program promotes natural resource-based industries, preserves critical habitats for native plant and wildlife species, provides greenbelts, and protects riparian forests and wetlands. (See the following paragraphs for more details about the Rural Legacy Program in southern Frederick County).

Conservation Reserve Enhancement Program

The Conservation Reserve Enhancement Program (CREP) is a cooperative program between the State of Maryland and the U.S. Department of Agriculture. CREP pays land owners to plant poorly productive agricultural field edges and borders in an approved practice that protects water quality and enhances wildlife habitat, while continuing to allow farming or grazing on the most productive land. Frederick County administers a CREP easement program, sponsored by the Maryland Department of Natural Resources.

Program Open Space, Stateside Program

Program Open Space (POS) funding is used to preserve sensitive natural areas, wildlife habitats, and areas with high ecological value through either a conservation easement or a fee-simple purchase. Lands encumbered by a POS Stateside Easement remain in private ownership; fee simple purchases through the POS Stateside Program are managed by the Department of Natural Resources as State Parks, Forests, or Wildlife and Fisheries Management Areas.

Maryland Environmental Trust

The Maryland Environmental Trust works with landowners, local communities, and land trusts to protect Maryland's most treasured landscapes and natural resources as a legacy for future generations through the acquisition of donated conservation easements.

Maryland Agricultural Land Preservation Foundation

The Maryland Agricultural Land Preservation Foundation Program (MALPF) is a state land preservation program aimed at conserving prime farmland for food and fiber production by paying farmers to extinguish their development rights through the use of conservation easements. Frederick County also provides funding to this program.

Federal

Forest Legacy

Administered by the Maryland Department of Natural Resources, the Forest Legacy Program targets lands identified in the State's Forest Legacy Areas that have high value to Maryland's wildlife, water quality, and landscapes. The program is designed to protect environmentally important forests through the use of permanent conservation easements, where at least 75% of the land under easement is forested and the remaining 25% is a compatible land use such as agriculture.

NRCS Agricultural Conservation Easement Program

The Natural Resource Conservation Service (NRCS) helps landowners to protect working cropland, pasture, grasslands, rangeland, and forests associated with an agricultural operation through the use of conservation easements of varying term lengths.

Healthy Forests Reserve Program

The goal of this USDA conservation program is to protect and enhance private forest ecosystems to: promote the recovery of endangered and threatened species, improve plant and animal biodiversity, and enhance carbon sequestration. Conservation easements may be permanent or for 10-year or 30-year terms, with a share of costs paid to implement conservation practices.

Wetland Reserve Easements

This USDA program targets wetlands that have been altered for agricultural purposes that can be successfully and cost-effectively restored. Program goals include improving water quality and protecting and enhancing habitat for migratory birds and other wildlife. Easements may be permanent or for 30-year or shorter terms. Property owners are paid to implement restoration and conservation practices.

Maryland's Rural Legacy Program

Rural Legacy's mission is to protect areas rich in agricultural, forestry, natural, and cultural resources that, if conserved, will promote resource-based economies, protect greenbelts and greenways, and maintain the fabric of rural life. Protection is provided through the acquisition of easements and fee estates from willing landowners, and the supporting activities of Rural Legacy sponsors and local governments.

There are two Rural Legacy Areas in Frederick County: the Mid-Maryland/Frederick Rural Legacy Area and the Carrollton Manor Rural Legacy Area. The Mid-Maryland Area is in the western portion of the County along South Mountain. The Carrollton Manor Area, established in 2003, is in the southern part of the County east of the Catoctin Mountains to Mt. Ephraim Road, within the Sugarloaf Planning Area.

In 2015, the County combined the two Rural Legacy Areas in the application process with the State so awarded grants could be allocated in either Rural Legacy Area. To date, the State has awarded over \$28 million in grant funding to purchase easements in the County's Rural Legacy Areas.

The Carrollton Manor Rural Legacy area extends into the western portion of the Sugarloaf Planning Area, comprising 7,262 acres or 41% of the Planning Area. Mt. Ephraim Road, a portion of Park Mills Road, and Flint Hill Road are the eastern boundaries of the current Carrollton Manor Rural Legacy Area within the Sugarloaf Planning Area. This current boundary excludes Sugarloaf Mountain, significant areas of forestlands, and some large agricultural areas within the Planning Area. To advance the options and opportunities for property owners to preserve sensitive natural resource lands, unique environments, and working landscapes in the Sugarloaf Planning Area, the Plan recommends an expansion of the Carrollton Manor Rural Legacy boundary by 8,935 acres, as shown on Map 4-15. State approval of the proposed expansion will be required.

Policy 4.5 **Maintain agriculture as a significant land use in the Sugarloaf Planning Area through easements, incentives, policies, and regulation.**

Initiative 4G **Pursue the proposed expansion of the Carrollton Manor Rural Legacy Area to include all of Stronghold, Incorporated's holdings, adjacent forestlands, and agricultural lands within the Sugarloaf Planning Area.**

Policy 4.6 **Support an evolving agricultural industry and farming at many scales that contributes to a local food supply and conservation of agricultural land, rural open space, and environmental resources in the Sugarloaf Planning Area.**

Policy 4.7 **Promote local agricultural growers and producers in the Sugarloaf Planning Area and assist with reaching residents through on-farm, wholesale, regional grocery, and culinary outlets.**

Policy 4.8 **Support innovative and high-tech farmers and agricultural practices that enhance the competitiveness of local farms in the Sugarloaf Planning Area.**

Piedmont Sole Source Aquifer

Piedmont Sole Source Aquifer

Map 4-1



Sugarloaf Study Area

5

Rural Roads

Sugarloaf Study Area


5


110 of 110

1

This map displays the Sugarloaf Study Area in Montgomery County, MD, overlaid on an aerial photograph. The area is bounded by a dashed white line. The map includes several labeled roads and streams:

- Roads:** FINGERBOARD RD, DIXON RD, DOCTOR BERRY RD, LINTHICUM RD, SUNNEDOOR RD, GOLDE RD, SUGARLOAF MOUNTAIN RD, COMUS RD, BANNER RD, DICKERSON RD, PARKMILLS RD, ED SEARS RD, DELLARD RD, MONOGA BOTTOM RD, MOUNT PRIM RD, and FEATHER RD.
- Streams:** Flint Hill Branch, Middle Patuxent River, and various unnamed streams.
- Land Use:** The area is divided into urban (grey) and rural (green) zones. A large agricultural reserve is located in the lower right. A legend in the top right corner identifies "Rural Roads" with a yellow line icon and "Sugarloaf Study Area" with a dashed white box icon.






Map 4-3

Land Use Plan Designations with Proposed "Treasured Landscape - Sugarloaf"

Map 4-3 illustrates the Land Use Plan Designations with Proposed "Treasured Landscape - Sugarloaf" for the Sugarloaf Study Area. The map shows a mix of rural and urban areas, with various land use categories and designations. The Sugarloaf Study Area is outlined by a dashed white line. Rural Roads are marked with a yellow wavy line. The Agricultural Reserve, Montgomery County, MD is outlined by a black dashed line. The map includes a legend on the right side defining the land use categories and symbols used in the map.




Zoning Districts

A - Agricultural	R3 - Low Density Residential	GI - General Industrial	R16 - High Density Residential
RC - Resource Conservation	RS - Middle Density Residential	LI - Limited Industrial	PUD - Planned Unit Development
OSR - Open Space Recreation	R8 - Middle Density Residential	ORI - Office/Research/Industrial	VC - Village Center
RL - Low Density Residential	R12 - High Density Residential	GI - General Commercial	MX - Mixed Use
RM - Municipality	MM - Mineral Mining	MI - Institutional	MUN - Municipality




Map 4-5



Subdivisions

Subdivision Lots





Map 4-7

1


Comprehensive Plan - Proposed Land Use Plan Designation Changes

See "Treasured Landscape - Sugarloaf" map for additional Land Use Plan Designation changes

Agricultural / Rural

Natural Resource

Rural Residential





Map 4-8


Comprehensive Plan - Proposed Land Use Plan Designation Changes 2

Agricultural / Rural

Rural Residential

Natural Resource

See "Treasured Landscape - Sugarloaf" map for additional Land Use Plan Designation changes







Map 4-9

3

Comprehensive Plan - Proposed Land Use Plan Designation Changes

See "Treasured Landscape - Sugarloaf" map for additional Land Use Plan Designation changes







Map 4-11



Zoning Districts - Proposed Zoning Changes 1


A - Agriculture

R1 - Residential

RC - Resource Conservation



Map 4-12



Zoning Districts - Proposed Zoning Changes 2


RC - Resource Conservation

A - Agriculture

R1 - Residential



Map 4-13



Zoning Districts - Proposed Zoning Changes 3

RC - Resource Conservation







Map 4-14

Sugarloaf Rural Heritage Overlay District

Rural Heritage Overlay District





Map 4-15

■ Carrollton Manor Rural Legacy Area ■ Proposed Addition



Transportation Network

Commonplace throughout the U.S., most new “roads” in the 18th and 19th centuries began as Native American foot trails or wildlife migration paths that were cleared, widened, and leveled to facilitate commerce and population growth. Within the Sugarloaf Planning Area, the transport of supplies and products to and from lumbermills, flourmills, and early industrial uses such as stone quarries, blacksmiths, wheelwrights, and cobblers helped to shape the area’s historical road network. Some of these early roads were constructed along routes that follow high points or minor ridge tops to aid in drainage and avoid low areas closer to waterways. Examples include Roderick Road, Park Mills Road, and Fingerboard Road (MD 80). These roads also define watershed boundaries; for example, Roderick Road and the northern sections of Park Mills Road demarcate the Urbana Branch and North Branch subwatersheds. Today, the road network in the Sugarloaf Planning Area is remarkably similar to that depicted on the 1873 Titus Map.

The early roads that carried infrequent and slow-moving, horse-drawn freight wagons and carts now carry thousands of vehicles each day for access to hundreds of dwellings and large commercial and institutional facilities. In addition, many roads in the Planning Area function as alternative commuter routes, as the network parallels the north/south routes of I-270 and MD 355 that funnel travelers into Montgomery County and points further south. Park Mills Road, Thurston Road, Slate Quarry Road, Sugarloaf Mountain Road, and Comus Road have the highest number of daily trips of all roads in the Planning Area according to the Frederick County DPW, Office of Transportation Engineering.

Reflective of the geographic and topographic constraints from the period of initial roadway establishment, the Sugarloaf Planning Area’s roadway network of today can be analyzed and evaluated through basic properties of roadway geometry, including:

- Alignment — the straight sections and horizontal curves on a road.
- Profile — the hills and valleys on a road, formally called crest curves (top of hill) and sag curves (bottom of hill).
- Cross-section — the width of the travel lanes, their cross-slope (roadway banking), and associated drainage features.

A road’s characteristics — its geometric profile — affect its safety performance and ultimately the accommodation of development and increased traffic volumes. Second only to human error, a road’s design is a contributing factor to accidents. Road geometry affects sight distance — the driver’s line of sight on a roadway. Insufficient sight distance can adversely affect the safety and operation of a roadway or intersection. Sudden or hidden curves, narrow-width roadways with hills, or adjacent and obstructing vegetation impact a driver’s reaction time (stopping sight distance), avoidance-maneuver time (decision sight distance), and sight lines needed to safely proceed through an intersection (intersection sight distance). Additionally, steep road grades have high velocity flows after storm events, contributing to road-side erosion and direct flow of run-off into streams.

Increased vehicular trips on a transportation network with many roadway alignment challenges (curves and hills), intersections with poor sight distance, and constrained travel lanes (widths, adjacent vegetation) can impact efficient and safe vehicular mobility. Numerous intersections and road segments in the Sugarloaf Area have sight distance constraints, and can pose extra challenges to maneuvering and movement by the motoring public. The County has not programmed the redesign of intersections or the rebuilding of roadways in the Sugarloaf Planning Area primarily due to the impacts to sensitive environmental lands and relatively low traffic volumes. Increased development densities or high trip-generating land uses would strain an already challenged transportation network in much of the Sugarloaf Planning Area.

There are no roadway-adjacent sidewalks in the Sugarloaf Planning Area except for a very small portion along Comus Road near the entrance to Sugarloaf Mountain. Many of the roadways are frequently used by bicyclists and walkers. Due to the relatively low traffic volumes on many of the roads and the inherent speed-calming characteristics of some of the roadways, many residents and visitors perceive a level of safety and security in utilizing the roads in the Sugarloaf Planning Area for recreational activities — walking, bicycling, running, and horse-crossing.

According to the Frederick County Sheriff's Office, just two roadways — Thurston Road and Park Mills Road — comprised 59% of the reported crash incidents in the entire Sugarloaf Planning Area from 2015-2019. These two roads generate the most complaints about speeding and requests for speeding enforcement in the Sugarloaf Planning Area. The characteristics and geometry of Thurston Road and Park Mills Road present challenges not just for safe travel, but also for traffic enforcement to monitor and stop motorists. Map 5-1 illustrates locations of reported car accidents from 2015 through 2019 in the Sugarloaf Planning Area.



Thurston Road, north of Doctor Perry Road



Thurston Road



Slate Quarry and Old Hundred Road intersection



Thurston Road and Peters Road intersection

Initiative 5A **With the Sheriff's Office and the Division of Public Works, explore the application of speed calming techniques to deter motorists who exceed the speed limit on Thurston Road and Park Mills Road.**

Maryland Interstate Highway System Projects

To address the impacts of population growth, land development, and their demands on the interstate highway network in the greater Washington, D.C., region, the State of Maryland has three major projects underway or under study:

- The I-495 (Capital Beltway) and I-270 Managed Lanes Study
- I-270 Innovative Traffic Congestion Management Projects
- I-270 Transit Enhancements

The I-495 and I-270 Managed Lanes Study

This project proposes to improve roadway capacity and will, according to the Maryland Department of Transportation State Highway Administration (MDOT-SHA), “address the need to accommodate existing and long-term traffic growth, enhance trip reliability, expand travel options, accommodate homeland security, and improve the movement of goods and services.” The project is, essentially, a travel demand-management solution that addresses congestion and will enhance existing and planned multi-modal mobility and connection.

The I-495 and I-270 Managed Lanes Study has experienced numerous adjustments to the scope and phasing during the planning and evaluation process. Phase I of the Study is now identified as the section from the George Washington Parkway in Virginia to I-270, including the replacement of the American Legion Bridge (ALB) and I-270 from I-495 to I-70. Phase I was further split into two phases: Phase I North is I-270 from I-370 to I-70 and Phase I South is from the GW Parkway across the ALB to west of MD 5, and on I-270 from I-495 to north of I-370. At this time there will be no action on I-495 east of Old Georgetown Road, including the I-270 eastern spur from I-495, and the remaining approximately 40 miles of I-495. This section is referenced as “future phases” and any further consideration of that area will require a new National Environmental Policy Act (NEPA) Study.

On February 18, 2021, the Maryland Department of Transportation (MDOT), MDOT State Highway Administration (MDOT-SHA), and the Maryland Transportation Authority (MDTA) announced the selection of Accelerate Maryland Partners, LLC (AMP) to become the Phase Developer responsible for overseeing the predevelopment work on Phase I of the project (North and South). AMP is led by toll operating company Transurban and banking company Macquarie Capital. The team has worked on approximately 90 public-private partnerships globally, including the Express Lanes network in Virginia on interstates I-95, I-395, and I-495.

The predevelopment work will advance and allow MDOT and MDTA to work with the Phase Developer and all stakeholders on the best ways to advance the preliminary design to further avoid and minimize impacts to environmental resources, communities, properties, utilities, and other features by working with the affected counties, municipalities, state and federal agencies, property owners, utilities, and citizens.

A variety of road and transit options are being considered as part of the Phase I improvements. The construction of HOT lanes will provide free travel to transit vehicles allowing for the potential advancement of a bus rapid transit (BRT) within the corridor. The expectation by the State of Maryland is that the project improvements would at least include new managed lanes with a robust transit service that would maximize use, while at the same time producing enough return on investment to make a viable P3 project. The new American Legion Bridge will have two HOT lanes along with added space for bicycles and pedestrians to cross. Currently no such pedestrian or bicycle routes exist on the bridge.

In Frederick County, the added lanes would be in the median and outside of or adjacent to the existing roadway. No significant right-of-way acquisition is required for the majority of the segments, though some land acquisition is expected in the vicinity of the MD 80 interchange in Urbana, the interchange at

MD 109 (Old Hundred Road) in Hyattstown, and adjacent to the Monocacy River in the Monocacy National Battlefield. It is anticipated that the proposed transit improvements will focus on the needs identified in the Transit Service Coordination Report, dated May 2020. The report identifies transit infrastructure improvements needs at the Frederick and Monocacy MARC stations and park & ride improvements at Monocacy, Urbana (North and South), and Hyattstown. Additionally, the report identified potential managed lane access points in Monocacy, Urbana, and Hyattstown.

An Environmental Impact Statement (EIS) is being developed for the Managed Lanes Study, as required under the National Environmental Policy Act (NEPA)² of 1969. According to the MDOT-SHA, an EIS is the most detailed and rigorous level of NEPA study and concludes with a Record of Decision (ROD) for the project. In late 2021, the Federal Highway Administration and the MDOT-SHA will issue a supplemental Draft EIS for Alternate 9, which is the new Phase I-South study area for the I-495/I-270 Managed Lanes Project.

Components of the EIS for the project include formal descriptions of Purpose and Need, Existing Conditions, and Alternatives Identification. Creation of the EIS and NEPA compliance for the Managed Lanes Project will include analysis of: air quality, noise, Section 4(f)³, cultural resources, natural resources, hazardous materials, community effects, environmental justice, visual quality and aesthetics, and indirect and cumulative effects.

Interstate 270 extends along a portion of the eastern boundary of the Sugarloaf Planning Area. While the I-270 right-of-way may be sufficiently wide along this portion of the Sugarloaf Planning Area to accommodate the future I-270 project, it is primarily in a wooded condition. The future loss of trees in this area will reduce carbon sequestering capabilities, allow highway noise to penetrate deeper into the rural landscape, and increase stormwater runoff. Whichever alternative that is ultimately chosen will have impacts on natural resources, not just within the Sugarloaf Planning Area, but the entire I-270 and I-495 corridors. Frederick County should critically evaluate the magnitude of property and natural resource impacts, as well as the location and extent of wetland and forest mitigation from the Managed Lanes Project.

On June 16, 2021, the Washington Metropolitan Council of Governments' National Capital Region Transportation Planning Board (TPB), the federally designated metropolitan planning organization (MPO) for metropolitan Washington, voted to remove the proposed I-270/I-495 express toll lanes and American Legion Bridge project from an air quality analysis that the TPB is legally required to undertake as it updates the region's long-range transportation plan, called Visualize 2045. Inclusion in the MPO's long-range plan affirms that projects collectively meet federal air quality standards and have financing in place to build, operate, and maintain the regional transportation system. The Visualize 2045 Plan is anticipated for adoption in 2022; as of June 2021, it is unknown what actions the Maryland Department of Transportation will take to reassess or revise the I-270/I-495 Managed Lanes Project and the American Legion Bridge project.

Policy 5.1 **Maintain coordination and collaboration with the Maryland Department of Transportation-State Highway Administration in all aspects of the I-270/I-495 Managed Lanes Study and I-270 Transit Enhancement Project.**

Initiative 5B **Work with Maryland Department of Transportation-State Highway Administration to support localized mitigation of forest and wetland impacts from the I-270/I-495 Managed Lanes Project as it moves through the Sugarloaf Planning Area.**

Initiative 5C Coordinate with Maryland Department of Transportation-State Highway Administration and Montgomery County to retain full operational movements at the MD 109/I-270 interchange for efficient access to the southern Sugarloaf area once the MD 75/I-270 interchange is constructed.

I-270 Innovative Congestion Management Project

This project proposes to improve multiple bottlenecks, add new lane miles, add real-time traffic communication signs, and add intelligent signals that work together to deliver dynamic traffic management along the entire I-270 corridor. In Frederick County, the improvements include on-ramp improvements involving acceleration lane lengthening and placement of ramp signals designed to meter the flow onto the interstate highway. These ramp signals will be placed at the MD 80 and MD 85 interchanges along with the MD 109 interchange in Montgomery County. These improvements are intended to appreciably reduce severity of delays at current choke points and reduce the duration of peak period congestion.

I-270 Transit Enhancements

Generally, transit is considered a system of shared transportation and mobility that is accessible to the public. Examples include:

- Bus Rapid Transit – Runs on dedicated lanes that have physical separation from normal traffic lanes. Some BRT systems like Montgomery County's new FLASH BRT on Rt. 29 between Burtonsville and Silver Spring use a combination of dedicated lanes and normal travel lanes.
- Express Bus – Fewer stops than a local bus, normally serving large employment hubs, such as Maryland Transit Administration's (MTA) Commuter Bus Routes 515 and 204 that stop at the Urbana park-and-ride lot.
- Heavy Rail – The Washington, D.C., area Metrorail system, Baltimore's Metro Subway, and the Maryland Area Regional Commuter Rail (MARC) trains.
- Light Rail – The Baltimore Light RailLink system and the Purple Line under construction in Montgomery and Prince George's Counties.
- Monorail – Rail cars on an elevated fixed guideway like in Seattle and many Asian cities like Kuala Lumpur and Mumbai.
- Local Bus – Fixed routes mixed in normal travel lanes, such as Frederick County's TransIT Services and Montgomery County's Ride-On system.

The proposed managed lanes along I-270 and I-495 offer an opportunity to implement a contemporary transit network that moves more people more quickly and efficiently, thus helping to reduce greenhouse gas emissions by lowering "emissions per passenger" compared to single-occupant vehicles. Transit use can be an effective tool in reducing traffic congestion and, for those commuting outside of the immediate area, can be a more viable and affordable alternative to commuting by car.

Suburban counties in the greater Washington metropolitan region including Frederick, Charles, Anne Arundel, and Howard are in need of need all-day bus services connecting to the Washington, D.C., Metrorail system. The proposed addition of managed lanes between Tyson's Corner, Virginia and Maryland will enable time-competitive transit across the American Legion Bridge. Several transit routes using the managed lanes are being evaluated. The Maryland Department of Transportation projects that over 10,000 new weekday transit trips would be achieved. The State's expectation for service would be 7-day-per-week, bi-directional, and hourly Bus Rapid Transit (BRT) running between the City of Frederick and the Shady Grove Metro Station, with single point transfers to other locations such as College Park, North Bethesda, and Tyson's Corner, Virginia. The completion of the I-495/I-270 Managed Lanes Project and I-270 Transit Enhancements is probably 10-15 years away or longer, depending on the negotiations and contract issues related to the public-private partnership the State of Maryland is pursuing for the project.

In Frederick County, future, expanded transit along the I-270 corridor is designed primarily to reduce single-occupant vehicle travel by expanding mobility choices for travel to job centers in Montgomery County, Washington, D.C., and Northern Virginia. The MTA's Express Bus operates in this fashion along the I-270 corridor, with stops at the 300+ space park-and-ride lot in Urbana on the routes to College Park, Rockville, and Bethesda.

New transit centers and additional park-and-ride facilities will be needed to support the new transit services in Frederick County. A new park-and-ride lot is planned at the proposed I-270/relocated MD 75 interchange; existing lots in the I-270 corridor at Urbana and the Monocacy MARC Station will be expanded.

Policy 5.2 Future transit centers, park-and-ride facilities, and transit-oriented development projects associated with the future MD 75/Mott Road/Dr. Perry Road interchange with I-270 should be thoroughly evaluated in order to serve the existing southern Urbana Community Growth Area, as well as critical focal points along the I-270 Corridor supporting compact employment and mixed-use development.

In anticipation of transportation enhancements along I-270, including mobility options with transit, the MD 80/I-270 interchange area warrants further study of future land use scenarios in this highly-visible and accessible area along the I-270 technology corridor. Subsequent planning initiatives, such as an Urbana Community Plan or I-270 Corridor Plan, will evaluate possible types, densities, scales, and timing of land uses on the west side of I-270 in the general area of the MD 80 interchange (see previous discussion on pages 40-41). Because this area is adjacent to the Sugarloaf Planning Area, future analysis and planning for the MD 80 interchange area must include:

- An extensive level of water quality mitigation from development and impervious cover impacts to the mainstem and tributaries of Bennett Creek and the sensitive headwater areas in Urbana Branch Watershed.
- Protection and enhancement of the FEMA floodplain associated with Urbana Branch.
- Investigation of the road network's characteristics and geometries and needed safety enhancements and physical modifications.
- Analysis of sewer system conveyance and treatment capacities.
- High quality design elements that do not overwhelm surrounding natural open space, existing low density residential development, and rural landscapes.

Scenic Roads

Roadways act as thresholds or entryways to specific areas, places, or even regions. Sugarloaf Mountain stands as a visible gateway beacon welcoming both residents and visitors to Frederick County. The roads in the Sugarloaf Area have significant visual elements, such as majestic roadside trees, wooded landscapes, bucolic fields, historic buildings and structures, interesting topographic gradients, and other natural features. These scenic and cultural resources are part of the area's heritage and should be retained.

Several roads within the Planning Area are designated Rural Roads in the County's Rural Roads Program. The Frederick County Rural Roads Program was created to protect the scenic and historic qualities of roads in the rural areas of the County and to provide for continued maintenance of the road surface. The Rural Roads in the Planning Area include all or portions of Sugarloaf Mountain Road, Comus Road,



Slate Quarry Road

Freshwater Salinization Syndrome

University of Maryland researchers have reported that streams and rivers across the U.S. have become saltier and more alkaline (higher pH) over the past 50 years due to increased use of road deicers (e.g. sodium chloride and calcium chloride), fertilizers, and other salty compounds that we indirectly release into waterways. The scientists also studied Paint Branch in Prince George's County Maryland and Rock Creek in Washington, D.C., and found elevated salt concentrations in these local waterways after snow and ice weather events.

High salinity levels in streams are toxic to the entire aquatic food chain from tiny zooplankton to macroinvertebrates (mayflies, stoneflies) to fish like brook trout. Road salt runoff can also harm plants, wildlife, and drinking water supplies. Elevated chloride levels in the Flint River, together with chemical treatments, contributed to the leaching of lead from water pipes in Michigan.

The University of Maryland scientists also found that salty, alkaline freshwater can release a variety of chemicals, including toxic metals and harmful nitrogen-containing compounds from streambeds and soils in watersheds where salt is applied on roadways. Many of the chemicals — copper, zinc, cadmium, manganese — form 'chemical cocktails' and can severely harm ecosystems and drinking water supplies more than individual pollutants alone.

Given the pristine water quality in many of the streams in the Sugarloaf Planning Area that support brook trout and other sensitive aquatic organisms, a reduction in road salt usage should be implemented for the Sugarloaf Planning Area.

Sources:

Novel 'Chemical Cocktails' in Inland Waters are a Consequence of the Freshwater Salinization Syndrome
Sujay S. Kaushal, Gene E. Likens, Michael L. Pace, Shahan Haq, Kelsey L. Wood, Joseph G. Galella, Carol Morel, Thomas R. Doody, Barret Wessel, Pirkko Kortelainen, Antti Räike, Valerie Skinner, Ryan Utz and Norbert Jaworski
Philosophical Transactions of the Royal Society B.

Published: 03 December 2018 <https://doi.org/10.1098/rstb.2018.0017>

Freshwater Salinization Syndrome

Sujay S. Kaushal, Gene E. Likens, Michael L. Pace, Ryan M. Utz, Shahan Haq, Julia Gorman, Melissa Grese. Proceedings of the National Academy of Sciences Jan 2018, 115 (4) E574-E583; DOI: 10.1073/pnas.1711234115

Dixon Road one-lane bridge over Little Bennett Creek



Banner Road, Peters Road, Roderick Road, Mount Ephraim Road, Greenfield Road, Monocacy Bottom Road, and Page Road. These rural roads are not only characterized by their road surface, but also by their geometric profiles, natural features, vistas, recreational value, and historic significance.

Policy 5.3 Support and perpetuate the Sugarloaf Area's rural character and unique elements in the forthcoming redesign of the County's Rural Roads Program.

Some roads within the Sugarloaf Planning Area have scenic attributes but are not currently included in the Rural Roads Program. These roads could be designated as County Scenic Roads in an expanded Rural Roads Program to preserve and maintain their scenic, natural, and cultural attributes and qualities. Scenic Roads could have the following characteristics:

- Contribute to an area's unique and iconic qualities and characteristics.
- Abut significant cultural landmarks, native vegetation, notable stands of trees, or other significant natural features along the majority of their length.
- Afford vistas of exceptional rural or natural landscapes or geologic features, such as Sugarloaf Mountain, agricultural fields, or historic buildings.
- Have wider road widths than a Rural Road.
- Have higher posted speed limits than a Rural Road.
- Have a variety of travel surfaces, such as gravel, tar and chip, and asphalt.

Initiative 5D Establish a new "Scenic Road" designation to augment and compliment the County's Rural Roads Program, as shown below in Table 3.


Table 3. Sugarloaf Plan Scenic Road Recommendations

Road Name	Limits	Scenic Characteristics
Stewart Hill Road	Mt. Ephraim to terminus	Extensively wooded, adjacent to Stronghold, Incorporated lands
Slate Quarry Road	Thurston Road to County boundary	Dense forested landscape present along virtually entire length
Dixon Road	Doctor Perry Road to Thurston Road	Dramatic east view of Sugarloaf Mountain and one-lane historic bridge
Ed Sears Road	Park Mills Road to terminus	Parallels Monocacy River, just west of a DNR "critically significant" landscape of old growth Oak/Heath Forest
Ira Sears Road	Park Mills Road to terminus	Surrounded by picturesque agricultural fields at the forested foothills of Sugarloaf Mountain
Doctor Perry Road	I-270 to Thurston Road	Prominent view of Sugarloaf Mountain
Della Road	Ed Sears Road to terminus	Historic African-American village adjacent to the Monocacy River



Map 5-1

Reported Vehicle Crash Incidents (2015 - 2019)






Watershed Water Quality

The Sugarloaf Planning Area is located primarily within the Bennett Creek Watershed, with small portions in the Monocacy Direct Watershed and the Little Monocacy River Watershed (see Map 6-1). The vast majority of the Sugarloaf Planning Area is situated within the larger Lower Monocacy River Watershed, a 169,100-acre watershed. The Lower Monocacy River Watershed is “nested” in the even-larger Middle Potomac River Basin. This entire area’s drainage is part of the Chesapeake Bay Watershed.


Through the Maryland Biological Stream Survey, Frederick County and the State of Maryland have monitored the Bennett Creek Watershed, analyzing nutrients in waterways, stream system structure and habitat, and fish and stream insect (benthic macroinvertebrates) populations to determine the overall health of the streams in the watershed.



Freshwater streams are highly sensitive and valued natural ecosystems. Aquatic ecosystems provide the critically important services of storing water in floodplains and wetlands, supporting fisheries, providing recreation, and linking the terrestrial landscape. Land cover (e.g., forests, fields, development) and land use management are the primary determinants of the overall condition of waterways, which is defined and measured by the following features of aquatic systems: physical (instream and riparian habitat, flow levels), chemical (nutrients, toxins), and biological (fish and other aquatic organisms). The Sugarloaf Planning Area contains significant and valuable natural and aquatic resources.

Policy 6.1

Foster increased awareness and appreciation of environmental resources in the Sugarloaf Planning Area and their relationship to man-made systems, and support management actions to sustain and protect resource function, resilience, and quality.



Maryland's Designated Use Classes for Surface Waters (COMAR 26.08.02)

The State of Maryland is the owner of waters that occur in or flow through the State either above or below ground. As the guardian of these waters, the State of Maryland has adopted policies and regulations regarding the use and protection of water.

In Maryland, each body of water has been classified according to the most critical use for which it must be protected. Specific numeric criteria for the water quality standards (e.g., temperature, pH, turbidity, dissolved oxygen, bacteria, etc.) are found in COMAR 26.08.02.03. The "P" designation indicates that these streams, like most in the County, ultimately drain to a source of the public raw water supply (e.g., Potomac and Monocacy Rivers). See Appendix for a listing of all streams in Frederick County and their Use Classes. See Map 6-6 for Designated Use Classes for Surface Waters in the Sugarloaf Planning Area.

Use Class I: Water Contact Recreation and Aquatic Life

Waters suitable for water sports and leisure activities where the human body may come in direct contact with the surface water, and suitable for the growth and propagation of fish (other than trout), other aquatic life, and wildlife.

Use Class II: Shellfish Harvesting (none in Frederick County)

Waters where shellfish are propagated, stored, or gathered for marketing purposes including actual or potential areas for harvesting of oysters, soft-shell clams, hard-shell clams, and brackish water clams.

Use Class III: Non-tidal Cold Water ('Natural Trout Waters')

Waters suitable for the growth and propagation of trout, and which are capable of supporting natural trout populations and their associated food organisms.

Use Class IV: Recreational Trout Waters

Waters capable of holding or supporting adult trout for put-and-take fishing, and which are managed as a special fishery by periodic stocking and seasonal catching.

The Frederick County Stream Survey (FCSS) is a program designed to monitor and assess the status and health of County streams in terms of water quality and biological and habitat conditions. Since its inception in 2008, the FCSS has sampled over 400 stream locations. For each of the sampling years, 50 randomly selected sites were monitored, stratified across 20 watersheds in the entire County. Data were collected and analyzed on water quality (nutrients), physical habitat (stream bank erosion, riparian forest), and biological communities (benthic macroinvertebrates) at each of the stream sites. Of the 22 sites monitored within the Bennett Creek Watershed during Round 1 (2008-2011)¹ and Round 2 (2013-2016)² of the FCSS, 14 total sites are located within the Sugarloaf Planning Area. In 2007, a Pilot Study for the FCSS was launched in the Catoctin Creek Watershed (15 sites) and the Bennett Creek Watershed (9 sites) to help develop, test, and refine the design and sampling protocols for the full FCSS. See Map 6-3 for the FCSS sites in the Planning Area.

Stream Habitat

Stream health, as characterized by the condition of biological communities, is often directly correlated to the quality of physical habitat within a stream. Habitat loss and degradation have been identified as critical factors affecting biological diversity in streams worldwide. Habitat degradation can result from a variety of impacts occurring within the stream itself or in the surrounding watershed. Typical instream impacts include sedimentation, stream channelization, and bank erosion. Land development, timber harvesting, agriculture, livestock grazing, and the draining or filling of wetlands are well-known examples of human activities affecting stream habitat at the watershed scale. These human activities may cause changes in vegetative cover, sediment loads, and hydrology, and influence stream habitat quality.³

The FCSS collects data on many aspects of physical stream habitat, including the extent and type of vegetated riparian buffer, the severity of bank erosion observed, and other metrics than can be combined and used as an overall indicator of habitat quality called the Physical Habitat Index (PHI). The PHI for Maryland streams was developed using data from the Maryland Biological Stream Survey (MBSS). This index combines several measures of physical habitat characteristics into one value that is then compared to minimally impacted sites throughout the state, which are referred to as reference streams and conditions.⁴

Table 4. Maryland Physical Habitat Index – Condition Class Thresholds

Physical Habitat Index (PHI) Score Range (Paul et al. 2002)	Condition Class or Rating	Description (Roth et al. 1999)
81-100	Good/Marginally Degraded	Comparable to reference streams considered to be minimally impacted
66-80	Fair/Partially Degraded	Comparable to reference conditions, but some aspects of biological integrity may not resemble the qualities of minimally impacted streams
51-65	Poor/Degraded	Significant deviation from reference conditions, with many aspects of biological integrity not resembling the qualities of minimally impacted streams
0-50	Very Poor/Severely Degraded	Strong deviation from reference conditions, with most aspects of biological integrity not resembling the qualities of minimally impacted streams

The FCSS sites within the Sugarloaf Planning Area showed a variety of physical stream habitat conditions, from severely degraded (1 site) to degraded (2 sites), partially degraded (3 sites), and marginally degraded (8 sites) during both rounds of monitoring (2008-2011, 2013-2016). As previously mentioned,

Maryland Biological Stream Survey

The Maryland Biological Stream Survey provides the best possible information for ensuring the protection and restoration of Maryland's stream ecological resources by:

- Assessing the current condition of ecological resources in Maryland's streams and rivers.
- Identifying the impacts of acidic deposition, climate change, and other stressors on ecological resources in Maryland's streams and rivers.
- Providing an inventory of biodiversity in Maryland's streams.
- Assessing the efficacy of stream restoration and conservation efforts to stream ecological resources.
- Continuing to build a long-term database and document changes over time in Maryland's stream ecological condition and biodiversity status.
- Communicating results to the scientific community, the public, and policy makers.

<https://dnr.maryland.gov/streams/Pages/mbss.aspx>

Maryland's Stream Waders Program

Maryland's Stream Waders program is a volunteer-based, "citizen-science" program sponsored by the Maryland Department of Natural Resources' Monitoring and Non-Tidal Assessment Division, and is an integral part of the DNR's professional stream monitoring program, the Maryland Biological Stream Survey. Goals of the Stream Waders Program are:

- To increase the density of sampling sites for use in stream quality assessments.
- To educate the local community about the relationship between land use and stream quality.
- To provide quality assured information on stream quality to state, local, and federal agencies, environmental organizations, and others.
- To improve stream stewardship ethics and encourage local action to improve watershed management.

<https://dnr.maryland.gov/streams/Pages/streamWaders.aspx>

conditions at these specific sites can be caused by activities in the immediate site area (e.g., livestock access to a stream without a riparian buffer), or influenced by land uses and management upstream in the watershed. See Map 6-3 for PHI scores in the Planning Area.

Water Quality

Nutrients, such as nitrogen and phosphorus, are important for life in all aquatic systems. In the absence of human influence, streams contain low background levels of nutrients that are essential for aquatic plant and animal survival. However, since European settlement, concentrations of nitrogen and phosphorus in many North American streams have increased. Anthropocentric activities such as agriculture and urbanization result in nutrient-rich runoff from fertilization, wastewater discharge, and storm water flow into streams.⁵

Elevated nitrogen and phosphorus concentrations are major contributors to nutrient over-enrichment in Frederick County streams—and all streams in Maryland. Excessive nutrient loading in aquatic systems can cause eutrophication, or excessive plant growth, and facilitate low dissolved oxygen conditions, particularly in downstream waterways and estuaries like the Potomac River and Chesapeake Bay. For example, eutrophication can cause algal blooms that lead to decreased concentrations of dissolved oxygen. After prolonged exposure, this can asphyxiate fish, shellfish, and other animals.⁶

Nitrogen concentrations measured at the monitoring sites in the Planning Area within the Bennett Creek Watershed showed low (8 sites) to moderate (6 sites) levels of total nitrogen during both rounds of monitoring. Two monitoring locations in the northern section of the Planning Area had high total nitrogen readings. Total phosphorus levels in the streams within the Planning Area during both rounds of monitoring were 94% low and 6% moderate.

High nitrogen levels were found in eight locations in the Bennett Creek Watershed during a 2003 nutrient synoptic survey conducted for the watershed characterization component of the Lower Monocacy River Watershed Restoration Action Strategy⁷, a watershed management plan developed by the Maryland DNR, local governments, and a community-based workgroup.

All of these sites were located in the upper Bennett Creek Watershed, east of I-270, with the exception of one site just west of I-270 on the mainstem of Bennett Creek within the Sugarloaf Planning Area. In the area known as Green Valley, the Bennett Creek Watershed east of I-270 has very high concentrations of well and septic residential development. Sources of nutrients in this area include fertilizers being applied to lawns in the surrounding low-density residential development, fertilizers being applied to agricultural lands in the upstream catchment area, and septic systems.⁸

Biological Condition

Biological monitoring, or biomonitoring, is the use of living organisms or their responses to determine the quality of the aquatic environment. Freshwater benthic macroinvertebrates are bottom-dwelling aquatic insects that live in water during some stage of their lifecycle and dwell on rocks, logs, sediment, debris, and aquatic plants. Stream benthic macroinvertebrates includes crustaceans (crayfish), mollusks (clams and snails), aquatic worms, and immature forms of aquatic insects such as stoneflies and mayflies. Many fishes, amphibians, shorebirds, waterfowl, and other animals forage heavily on both the aquatic and terrestrial stage of aquatic insects, which are essential to their survival.

Benthic macroinvertebrates represent an extremely diverse group of aquatic animals, with over 600 taxa known to occur in Maryland.⁹ These insects have a wide range of recognized responses to stressors such as organic pollutants, sediments, and toxic chemicals and can serve as an early warning sign of declines in environmental quality. Benthic macroinvertebrates are relatively stationary and their migrations come largely from downstream drift, so they are less able to escape the effects of sediment and other

pollutants that diminish water quality and degrade habitat. Therefore, benthic macroinvertebrates can serve as reliable indicators of stream condition.¹⁰ Chemical water quality information was previously the main factor that was considered in water quality, but newer efforts have also been considering biological data for a more comprehensive understanding of water quality and overall stream health.¹¹

The Benthic Index of Biotic Integrity (BIBI) is a scientific measuring tool used to identify and classify stream health based on the characteristics of the stream insects and metrics, such as pollution tolerance/intolerance; composition (diversity, abundance of organisms); population attributes such as feeding (e.g., filter, collector) and habitat preference (e.g., burrower or clinger). The multi-metric approach compares what is found at a monitoring site to what is expected using a regional baseline condition that reflects little or no human impact.¹² Biological monitoring provides insight into a stream's overall condition and ability to provide habitat, food, and shelter for aquatic organisms. The condition and health of streams is directly influenced by land cover and land use in the surrounding watershed.

Maryland's BIBI was formulated according to specific regional conditions and uses a scale ranging from 1 to 5 to facilitate statewide comparisons and to be consistent with the State of Maryland's fish IBI scores. The development of the State of Maryland's Benthic Index of Biotic Integrity can be found at: https://dnr.maryland.gov/streams/Publications/1998_Benthic-IBI.pdf

Table 5. Maryland Benthic Index of Biotic Integrity – Condition Class Thresholds

Benthic Index of Biotic Integrity (BIBI) Score Range	Condition Class or Rating	Description (Roth et al. 1999)
4.0—5.0	Good/Marginally Degraded	Comparable to reference streams considered to be minimally impacted
3.0—3.9	Fair/Partially Degraded	Comparable to reference conditions, but some aspects of biological integrity may not resemble the qualities of minimally impacted streams
2.0—2.9	Poor/Degraded	Significant deviation from reference conditions, with many aspects of biological integrity not resembling the qualities of minimally impacted streams
1.0—1.9	Very Poor/Severely Degraded	Strong deviation from reference conditions, with most aspects of biological integrity not resembling the qualities of minimally impacted streams

In the Planning Area, results of the BIBI scores from the FCSS Round I and Round II ranged from poor (2 sites) to fair (6 sites) and good (6 sites), indicative of in-stream habitat and riparian conditions suitable for supporting a diverse population of stream insects. See Map 6-3 for BIBI scores in the Planning Area. Additional BIBI scores from the Maryland Biological Stream Survey (MBSS) in the Planning Area show fair and poor biological conditions. See Map 6-4 for MBSS sites.

Additionally, the FCSS results included a regression analysis to examine the relationship of land use, habitat, and water chemistry parameters to the biological health of the streams, using the BIBI scores for each site sampled in Round I and Round II of the countywide survey. While the relationship of the BIBI to land use in the catchments upstream of the sample sites was not very strong, BIBI scores did significantly decrease with increasing urban and agricultural land uses. BIBI scores showed a significant increase with increasing forested land use.

Policy 6.2

Enhance biological, physical, and chemical monitoring of streams, including evaluation of physical impediments that block brook trout movement and acute “hot spots” with degraded in-stream conditions that imperil survival of coldwater aquatic communities.

Impervious Surface

The features and functions of landscapes change when land is cleared of trees, graded, and developed. Removal of trees and their canopy, spongy topsoil and leaf litter, as well as grading and altering natural land depressions results in the loss of the land's natural capacity to absorb and store water runoff generated during rainfall and snowmelt. Compaction of soil and placement of impervious surfaces — such as roads, rooftops, parking lots, and driveways — results in the loss of the land's natural features that enable water to percolate into the soil. Impervious surfaces eliminate natural recharge areas for groundwater that feeds stream base flow. Since impervious surfaces cover natural recharge areas, more water from rainfall eventually enters the stream as surface water runoff and less as groundwater-derived base flow, which can alter stream flow and negatively impact springs, seeps, and wetlands. During the summer months, rain that falls on warm pavement is heated. This hot water can flow directly to streams via storm drains and be stressful or even fatal to stream inhabitants.

Impervious surfaces contribute to overall non-point source water pollution. Non-point source pollution originates from multiple and diffuse sources, not from a discernible or specific source of origin. For example, petroleum products or metals on roads or pesticides and fertilizers on a lawn that wash off and get carried in surface water runoff to a stream are non-point source pollutants. Compounds discharged into a stream or river from a wastewater treatment plant outfall pipe are point sources of pollution.

The location of impervious cover in a watershed is important in determining adverse impacts to a stream system. For example, paved surfaces located in the headwaters of a stream system can create greater adverse impacts on the system than paved surfaces situated farther down in the watershed of the stream system. Soil types, geology, topography, and the extent and location of vegetative cover in a watershed can also influence impervious cover impacts to waterways. As a rule, water quality decreases as impervious surface cover increases, leading to degraded stream conditions.

Current practices and regulations for stormwater runoff management utilize what is known as environmental site design. These practices are designed to achieve on-site water quality and quantity treatment and infiltration so less water from impervious surfaces run off the land. Conventional stormwater ponds are still used to manage stormwater, but to a lesser extent. The latest run-off controls use a combination of vegetation and structural practices and techniques, an approach called bioretention, in an attempt to recreate pre-development conditions and hydrology of a site. Ultimately, the replacement of forest and fields with impervious cover has multiple negative impacts to environmental systems.

Policy 6.3

Minimize parallel streamside roads and road crossings of streams in all future planning, subdivision and site plan approvals, and construction designs in the Sugarloaf Planning Area.

Initiative 6A

Establish non-residential and non-agricultural building size thresholds in the Sugarloaf Planning Area to reduce impervious surfaces, stormwater runoff, and degradation of aquatic resources.

BIBI Scores vs. Percent Forested Land Use




Figure 1. Relationship Between the BIBI and Forested Land Use

Regression relationship between the Benthic Index of Biotic Integrity (BIBI) and forested land use in upstream catchments, countywide, for Rounds I and II of the Frederick County Stream Survey (Versar 2017)

BIBI Scores vs. Percent Urban Land Use




Figure 2. Relationship Between the BIBI and Urban Land Use

Regression relationship between the Benthic Index of Biotic Integrity (BIBI) and urban land use in upstream catchments, countywide, for Rounds I and II of the Frederick County Stream Survey (Versar 2017)

Monitoring Water Quality Impacts from Impervious Cover and Land Use

As required by the Maryland Department of the Environment (MDE), Frederick County initiated a long-term water quality monitoring program in the Peter Pan Run Watershed in 1999. Peter Pan Run originates in Urbana and is a tributary to Bush Creek, which flows into the Monocacy River at the Monocacy National Battlefield. To assess the long-term water quality impacts associated with land development in the Urbana area, the County established baseline, pre-construction stream and water quality conditions in the Peter Pan Run Watershed. The program involved monitoring and evaluating stream flow volumes, water quality in streams and from the outfalls or discharges from stormwater management facilities, and biological communities in the main stem of Peter Pan Run and its tributaries. Specifically, the Peter Pan Run study examined sedimentation and stream bank erosion from an increase in impervious surfaces, heavy metals from road and parking lot runoff, nutrient loading caused by application of lawn fertilizers, and the illegal disposal of oil and chemicals via storm drains.

With water quality conditions in Peter Pan Run documented, the County identified 15 stormwater management structures for upgrades and retrofits in the Urbana area in 2017. These projects were completed in 2019. The pollution treatment efficiencies and subsequent improvements in stream and water quality between the State stormwater management regulations in effect during the years from 1999 to 2017 and today's stormwater laws can now be analyzed. The goals of monitoring and retrofit programs are to identify the impacts of urban development on a stream and study the benefits of restoration projects on overall watershed health.

For more information and links to the 2017 and 2019 Peter Pan Run Long Term Monitoring Reports, see <https://frederickcountymd.gov/7578/Water-Quality-Monitoring>

Policy 6.4

Support and adequately fund watershed restoration initiatives such as stormwater management system upgrades and retrofits, infrastructure repair, reforestation, and stream restoration projects that minimize riparian vegetation removal in the Sugarloaf Planning Area.

The following generalized Stressor Identification Index identifies how land uses can cause stress to the aquatic system, plus the chemical, physical, and biological response to such stressors. Human-induced impacts to the environment are increased when natural landscapes and land cover (e.g., forests, fields) are replaced with rooftops, roads, and parking lots. Impervious surfaces increase with development and urbanization, and can cause negative impacts on stream health, so it is important that actions be taken to combat these changes and minimize their effects, especially in the Sugarloaf Area where sensitive aquatic communities are found. Brook trout are very sensitive to landscape alterations in Maryland and disappear at low levels of impervious land cover. Locally, brook trout are rarely found in watersheds where impervious land cover exceeded 4%.¹³ For more information on brook trout watersheds, see https://dnr.maryland.gov/fisheries/Documents/LandUseCharacteristics_TROUTWatersheds.pdf

Coldwater Biological Resources in the Sugarloaf Planning Area

Water temperature is a key factor in the distribution of organisms in the aquatic environment. Coldwater streams are stream reaches that maintain year-round water temperatures that can support a coldwater aquatic community. Maximum stream temperatures of 20° C (68° F) are generally considered the thermal threshold for long-term trout survival (DNR). In Maryland, coldwater biological communities are identified by the presence of reproducing trout (brook, brown, and rainbow) and/or obligate coldwater benthic macroinvertebrate, such as the stonefly taxa, *Tallaperla* and *Sweltsa*.

These coldwater species have a narrow range of required environmental conditions and are more sensitive to alterations in temperature, stream flow, and water quality. Their presence in a stream indicates a watershed with minimal land use impacts and high water quality conditions. Forested

land cover within a catchment is the overall best landscape-scale predictor of brook trout occurrence at a given site, with measures of impervious land cover and urbanization also important predictors.¹⁴ Several watersheds in the Sugarloaf Planning Area currently support coldwater resources, based upon monitoring data from the Maryland DNR Freshwater Fisheries Program and the Frederick County Stream Survey. These streams support a combination of naturally reproducing brook trout populations and obligate coldwater benthic macroinvertebrates. See Map 6-2 for cold water resource monitoring.

Brook trout in Maryland are valuable for cultural, recreational, economic, and biological reasons. They represent the only native trout species in the State. Because of their habitat, brook trout are typically found in the more environmentally pristine areas of Maryland.¹⁵ Anthropogenic alterations to Maryland's environment over the last several centuries including clear cutting of forests, establishing large agricultural areas, and urbanization have resulted in the extirpation of brook trout from 62% of their historic habitat in Maryland.¹⁶

Silt-free, spring-fed streams that contain mixed gravels, cobbles, and sand with some deep-water areas characterize ideal brook trout habitat. Benthic macroinvertebrates need the space between and beneath gravel and cobble substrate on the stream bottom for attachment sites, feeding areas, and shelter from predation. Keeping sediment inputs to streams at low levels through fine-scale, protective buffering of flow paths and natural landscape drainage networks in the Sugarloaf Planning Area will help ensure that stream habitat areas are available for brook trout and benthic macroinvertebrates.


Stream Categories

Five categories of streams are defined based on how much impervious surface exists in their upstream catchment:

- Excellent – less than 4% impervious surface in the upstream catchment
- Sensitive – 4% to 10% impervious surface in the upstream catchment, are generally able to maintain their hydrologic function and support good to excellent aquatic diversity
- Impacted – 10% to 25% impervious surface in the upstream catchment, show clear signs of declining stream health
- Non-supporting – 25% to 60% impervious surface, no longer support their designated uses in terms of hydrology, channel stability, habitat, water quality, or biological diversity
- Urban drainage – greater than 60% impervious surface, functions basically as a conduit for rainfall or flooding events and consistently have poor habitat and biodiversity scores

Source: Shueler, T., L. Fraley-McNeal, and K. Cappiella. 2009. Is Impervious Cover Still Important? A Review of Recent Research. *Journal of Hydrologic Engineering*. April 2009

Figure 3. Stressor Identification Index (adapted from Tetra-Tech, 2008, Bennett Creek Watershed Assessment)



Across the Mid-Atlantic Region, the number streams that support coldwater biological communities has been greatly reduced due to an increase in water temperature and degraded water quality caused by development and land use changes. Habitat loss and local extinctions of fish and other aquatic species are projected from the combined effects of increased water withdrawal and climate change.¹⁷

Policy 6.5 Maintain high-quality watershed conditions to sustain coldwater biological communities.

Aquatic research has been employed to evaluate the status and condition of biological resources in waterways within the Sugarloaf Planning Area. The Sugarloaf Treasured Landscape Management Plan promotes a commitment to conserving and enhancing aquatic resources and biological communities in the Sugarloaf Area by identifying the following watersheds as Sugarloaf Resource Watersheds of Concern. Due to having the highest quality waters and extensive forest resources, the majority of the Resource Watersheds have high potential for degradation from the effects of various land uses, conversions, and

development activities. This designation will focus attention and actions to maintain a high-quality environment and the long-term sustainability of the Resource Watersheds and, concomitantly, the rural landscape and character of the community. See Map 6-5 for the Sugarloaf Resource Watersheds of Concern.

Table 6. Sugarloaf Resource Watersheds of Concern

Watershed	Size (ac.)	Forest Cover (ac.)	Forest Cover (%)	Impervious Surface (ac.)	Impervious Surface (%)
Bear Branch	865.5	787.4	90.9%	12.7	1.4%
Furnace Branch*	2,094.9	1,696.1	80.9%	24.3	1.1%
Little Bennett Creek Subwatershed	813.2	599.1	73.6%	9.4	1.1%
Bennett Creek Subwatershed 1	378.0	313.6	82.9%	2.0	0.553%
Bennett Creek Subwatershed 2	469.0	316.5	67.4%	7.1	1.5%
North Branch**	918.4	238.2	25.9%	49.9	5.4%
Urbana Branch**	1,280.0	367.3	28.6%	109.6	8.5%

*Extends into Montgomery County, Maryland

**A portion of this watershed is located outside of the Planning Area

Initiative 6B **Engage the Division of Public Works' Highway Operations Division in a critical examination of the need and use of road salt within the Sugarloaf Resource Watersheds of Concern in order to protect high quality waters that support brook trout and coldwater aquatic organisms from the threat of elevated chloride levels.**

Brook Trout Watersheds - Bear Branch and Furnace Branch

Bear Branch, the only pristine trout-bearing stream in all of the Lower Monocacy River Watershed, is located in the Sugarloaf Planning Area. Two watersheds with the Sugarloaf Planning Area (Furnace Branch and Bear Branch), are designed Use Class III-P, Natural Trout Waters and Public Water Supply. The remaining streams in the District are Use Class IV-P, Recreational Trout Waters. Based on biological monitoring and stream temperature data, additional streams in the Sugarloaf Planning Area are anticipated to be redesignated to Use Class III. This designation will afford additional in-stream habitat protections related to time-of-year prohibitions for stream crossings and construction activities.

Policy 6.6 **Protect sensitive aquatic resources, including brook trout populations, in Bear Branch Watershed.**

Policy 6.7 **Support efforts to achieve Tier III Use Class Status for additional streams in the Sugarloaf Planning Area and ensure that the unique high-quality features of these streams are maintained.**

Table 7. Brook Trout Populations, Bear Branch Watershed – Mt. Ephraim Road (Maryland DNR)

Year	Adult	Young	Total
1992	26	6	32
2001	7	0	7
2008	4	0	4
2010	8	9	17
2014	4	25	29
2018	17	25	42

Furnace Branch was stocked with wild brook trout by Maryland DNR in the late 1970s. These trout were able to survive for several years, but chronically elevated summer temperatures prevented their long-term survival. Subsequent monitoring surveys by the DNR in the last 15 years have not collected any brook trout from Furnace Branch. Automated stream temperature sampling data including over 6,000 samples in 2019 showed a greater percentage of samples exceeding the brook trout thermal threshold (20° C) in Furnace Branch compared to Bear Branch, which maintains a reproducing brook trout population. The monitoring data is evidence that watersheds with coldwater biological resources have fewer temperature readings over the critical level, which positively impacts the survival capacity of a local brook trout population.

Table 8. Brook Trout Temperature Exceedance for Furnace Branch and Bear Branch

Stream	Percentage >20°C (68°F)	Percentage >21°C (69.8°F)	Percentage >22°C (71.6°F)	Percentage >23°C (73.4°F)
Bear Branch	11.4%	1.7%	0%	0%
Furnace Branch	29.9%	11.2%	2.5%	0%

Data from 2019 monitoring period (June 1 –August 31). Values depict percentage of observations above specific temperature values. Remaining percentages represent temperatures below 20° C. (Maryland DNR)

Although the Furnace Branch is a large watershed with high forest cover (80.9%) and low impervious cover (24.3 acres or 1.1% of the entire watershed), and had good water quality as measured by the high BIBI scores and good physical habitat scores from the FCSS (see Map 6-3), brook trout have not remained viable within the streams in the watershed. Additional monitoring of streams and their structure in the Furnace Branch Watershed — plus the extent of forest buffering around streams and identified springs, seeps and wetlands, especially in agricultural headwater areas — is warranted. Through implementation of policies and initiatives contained in this Plan to improve water quality in the Sugarloaf Planning Area, the goal of returning a sustainable population of brook trout to the Furnace Branch Watershed can be achieved.

Policy 6.8 Improve and restore wildlife habitat and biological diversity, including brook trout populations, in the Furnace Branch Watershed.

Initiative 6C Continue engagement with and support of the Eastern Brook Trout Joint Venture, a unique partnership between state and federal agencies, regional and local governments, businesses, conservation organizations, academia, scientific societies, and private citizens working toward protecting, restoring, and enhancing brook trout populations and their habitats across their native range.

Headwater Stream

Water in streams comes from several sources including: water held in soil adjacent to stream banks and riparian areas, runoff from precipitation, and groundwater. Rivers, lakes, and streams originate from countless numbers of very small streams and wetlands, many of which are so small they do not appear on maps. This network of small streams and their associated complexes, whose waters join together above and below ground, flow down gradient, eventually growing larger and intersecting with rivers. Headwater streams, also called channel heads, rills, rivulets, drainage swales, depressions, flow paths, and seeps, act as the primary conduits of water, sediment, nutrients, and other materials to larger streams in a watershed during rainfall and snowmelt events. Regardless of discharge permanence, headwater channels dictate the delivery of sediments, nutrients, and pollutants to downstream waters. Knowledge of their location is critical to understanding watershed processes, and evaluating human and ecological values of stream channels (Meyer, et al.).

Headwaters comprise most of the total length of an entire stream system. Meyer, et al. (2003) reported that 20% or less of the actual stream network is shown on USGS maps, and that topographic maps commonly used as catalogues of stream networks are not detailed enough to serve as a basis for stream management and protection. Because of their prevalence on the land, headwater streams — and associated wetlands and springs — are connected with, and drain, large land areas. Thus, these small streams have much interaction and interface with the surrounding terrestrial landscape.

Headwater streams and their associated wetland and spring linkages:



- Capture, store, and hold rainwater, thus reducing flooding threats to people and property. Headwater wetland complexes recharge aquifers by slowly releasing water into streams and groundwater. This is critically important for households and businesses relying on wells for drinking water.
- Trap excess sediment. Healthy and intact headwater systems can modulate the amount of sediment transported to downstream ecosystems. Wetland areas associated with headwater streams — or wetlands without a surface connection to a nearby stream — are areas where rainwater and stormwater runoff slows, allowing for the settling of sediment and debris carried in the water.
- Modify and transform potential pollutants. Water volumes in small headwater streams have more “contact” with a stream channel and stream bed, where microorganisms, bacteria, and fungi live. These organisms consume, transform, and reduce nutrients. They also colonize leaf and limb litter, creating food sources for other larger stream organisms like mayflies, frogs, and fish.

Headwater streams convey water and nutrients to larger streams and, despite their relatively small dimensions, play a disproportionately large role in nitrogen transformations on the landscape (Peterson, et al. 2001). Restoration and preservation of small stream ecosystems should be a central focus of management strategies to ensure maximum nitrogen processing in watersheds, which in turn will improve the quality of water delivered to downstream lakes, estuaries, and oceans (Peterson, et.al 2001).

If connections between soil, surface waters, and groundwater are disrupted — as from impervious surfaces and land development — water levels in streams, rivers, and groundwater can be reduced, imperiling aquatic organisms. Impervious surfaces increase the amount of precipitation that runs off the ground and lessen the amount of rainfall that soaks into the soil, short-circuiting the groundwater recharge process.

The entire Sugarloaf Planning Area contains countless headwater streams that populate and drain the landscape, linking the terrestrial with the aquatic. Headwater protection will sustain critical environmental functions, such as base flow maintenance of these aquatic systems, wetland and groundwater recharge, efficient nutrient cycling, and aquatic habitat conservation. Through expanded buffering and protection measures for the Sugarloaf headwater system, increases in water pollution, stream erosion, and sedimentation will be minimized and prevented.

Sources: Control of Nitrogen Export from Watersheds by Headwater Streams, *Science* 06 Apr 2001: Vol. 292, Issue 5514, pp. 86-90 DOI: 10.1126/science.1056874 Meyer, J. L., L. A. Kaplan, J. D. Newbold, D. L. Strayer, C. J. Woltemade, J. B. Zedler, R. Beilfuss, Q. Carpenter, R. Semlitsch, M.C. Watzin, and P. H. Zedler (2003): Where rivers are born: The scientific imperative for defending small streams and wetlands. Sierra Club and American Rivers.



The Strahler Stream Order system. First-order streams (1), also called headwater streams, can join another first-order stream to become a second-order stream (2). Further merging results in additional stream orders with ascending numbers (3, 4, etc.). Credit: Steve Adams, Minnesota DNR

Urbana Branch Watershed

Population, development, and impervious cover within this watershed are the highest in the entire Sugarloaf Planning Area. Forest cover in this watershed is relatively low at 28.6%. In 2012, 74 acres within this watershed were rezoned from Agricultural to R-1 Residential, resulting in the creation and development of 32 residential lots. This development project added approximately 5.6 acres of impervious surface to the watershed based on recent GIS analysis using an impervious footprint of 4,500 square feet per lot that includes a house, parking area, driveway, plus impervious cover of 0.50 of subdivision street right-of-way. Planned high density development within the Urbana Community Growth Area and potential development areas around the MD 80/I-270 interchange, both within the headwaters of Urbana Branch, will further increase the levels of impervious cover within the most sensitive portion of the watershed in the future. For these reasons, Urbana Branch Watershed is designated a Resource Watershed of Concern.

Any future planning initiative for the MD 80 interchange area that advances the Livable Frederick Master Plan's goals to increase multi-modal accessibility and support the innovative bioscience and advanced technology sectors must include a high level of environmental protection for the Urbana Branch Watershed and the Bennett Creek Watershed, such as:

- Close examination of all aquatic system components, including zero and first-order streams, including field verification if necessary, to determine necessary protective or expanded riparian buffering.
- Utilization of stormwater best management practices for future development that include structures, devices, or designs that provide the highest level of stream channel and water quality protection, and reduce thermal impacts to receiving streams.
- Enhanced protection of the FEMA floodplain associated with the mainstem of Urbana Branch.

Three locations in Urbana Branch Watershed were evaluated in 2003 through the State's "Stream Waders" program, a volunteer monitoring effort used to supplement the larger Maryland Biological Stream Survey. DNR conducted monitoring in Urbana Branch Watershed in 2020 (see Map 6-2). Additional water quality monitoring is warranted to assess the health of Urbana Branch Watershed to: obtain baseline data of aquatic conditions in a watershed with current 8.5% impervious cover; track environmental changes in the streams over time; evaluate the general effectiveness of upstream stormwater management systems; and study the benefits of focused efforts to increase forest cover in the watershed.

Table 9. Urbana Branch Watershed – Stream Waders Biological Monitoring

Site No. (Maryland DNR)	Location	Benthic Index of Biotic Integrity (BIBI)
224-1-2003	West side Thurston Road, 0.60 miles north of Dixon Road	1.85 – Poor
224-2-2003	East of Virginia Lane	3.00 – Fair
224-4-2003	West side of Thurston Road, 0.60 miles north of Dixon Road	1.57 --Poor

Geographic Information Systems (GIS) analysis shows two watersheds in the northern portion of the Planning Area that have higher levels of impervious cover than the brook trout threshold of 4%: North Branch (5.4%) and Urbana Branch (8.5%). While still within the "sensitive" category based on Schueler, et al (2009), these two watersheds have the lowest proportional forest cover of any Resource Watershed in the Sugarloaf Planning Area. The Sugarloaf Treasured Landscape Management Plan promotes efforts to increase forest cover in all of its watersheds, with special focus on the Urbana Branch and North Branch watersheds through the incentive programs described within Chapter VII, Forestlands, Green Infrastructure, and Biodiversity.


Policy 6.9	Focus existing incentive programs in the Urbana Branch and North Branch Watersheds to expand and increase the amount of forest cover to address environmental and climate resilience and aid in water quality protection.
Policy 6.10	Critically examine quantities of groundwater requested for future withdrawals by large-scale commercial and institutional uses in order to maintain springs and seeps, and to ensure stream base flows needed for sensitive cold-water aquatic biota and protection of nearby private residential wells.

The sensitive coldwater biological resources in the Sugarloaf Area of southern Frederick County highlight the quality of these minimally impacted watersheds, where development densities and impervious cover are very low and forest cover is high. Heavily forested watersheds often represent areas with the least impacts from human development or that have had enough time to recover from historic disturbances. Many high-quality streams have evolved in response to the forest or native cover of their subwatersheds, and have unique habitat conditions that support trout or spawning anadromous fish.¹⁸


Establishing new forestlands and enhancing riparian buffers along all waterways in the Sugarloaf Planning Area will help ensure the continued presence of high-quality waters in the Planning Area. Buffering and protecting springs, seeps, and headwater stream areas will enable cold groundwater to keep downstream temperatures low during summer months, and help maintain and support coldwater biological resources. Riparian buffers provide additional environmental benefits such as bank stabilization, addition of woody debris and leaf matter to the stream for habitat and food, uptake of nutrients, and the provision of shade to modulate water temperatures.

Additionally, minimizing the overall loss of forest cover through land use management and refining the standards for timber harvesting to enhance preservation of high-quality waters and critical breeding areas for Forest Interior Dwelling Bird species will protect natural resources, maintain the area's rural landscapes, and improve overall environmental quality.

Initiative 6D	Preserve and enhance environmental functions, such as flood control, temperature modulation, and downstream water quality protection, by enhancing the buffering of aquatic systems, including headwater areas and mapped natural flow and drainage paths.
Initiative 6E	Establish a physical, chemical, and biological water quality monitoring program for the Urbana Branch Watershed to assess current conditions and evaluate the effects of land use change on stream quality.
Policy 6.11	Support conservation practices on all agricultural lands, including livestock exclusion from streams, wetland protection and enhancement, and regenerative agricultural practices to sequester carbon and increase soil and water health.



Map 6-1




Aquatic Monitoring Sites - Coldwater Resources


- Bear Branch Watershed**
- Bennett Creek Subwatershed 2**
- North Branch Watershed**
- Urbana Branch Watershed**
- Bennett Creek Subwatershed 1**
- Little Bennett Creek Subwatershed**

Source: Maryland Department of Natural Resources, Frederick County



Map 6-2






Aquatic Monitoring Sites - Maryland Biological Stream Survey (MBSS) - Maryland Department of Natural Resources

- Bear Branch Watershed
- Bennett Creek Subwatershed 1
- Bennett Creek Subwatershed 2
- Urbana Branch Watershed
- Little Bennett Creek Subwatershed
- North Branch Watershed
- Furnace Branch Watershed *

* extends into Montgomery County




Resource Watersheds of Concern

- Bear Branch Watershed
- Bennett Creek Subwatershed 1
- Bennett Creek Subwatershed 2
- Furnace Branch Watershed *
- Little Bennett Creek Subwatershed
- North Branch Watershed
- Urban Branch Watershed



Map 6-5





|Forestlands, Green Infrastructure, and Biodiversity|

Prior to European settlement, about 95% of Maryland's six million acres of land was covered in forest. Today, forest cover is around 40%. In Maryland's early post-colonial history, forest loss was due to primarily agricultural conversion. In the early part of the 20th century, many marginal farms were abandoned and reverted to forest. However, in the last half of the century, urban development replaced an estimated 7,200 acres of forestland per year (Maryland DNR). Between 2012 and 2019, Frederick County experienced a net loss of approximately 480 acres of forest.

Maryland's trees and forests are the foundation for native wildlife, recreation, and scenic beauty. Forests also support healthy streams, fish and wildlife habitat, and clean air. Forests provide renewable natural resources for rural economies, forest product companies, and wood manufacturing, as well as supplying wood for heat. Maryland faces many challenges in sustaining ecologically functional and economically viable forests in the face of rapid urban development and other threats, such as pests, disease, and wildfire.¹

Maryland's 2020 Forest Action Plan

Part I of the State's Forest Action Plan contains a forest assessment, designed to:

- Describe forest conditions on all ownerships in the state
- Identify forest-related benefits and services
- Highlight issues and trends of concern, and opportunities for positive action
- Delineate high priority forest landscapes

Part II of the State's Forest Action Plan lists the State's goals, objectives, strategies, and actions to address the wide variety of forestry issues identified in the forest assessment in Part I of the Plan. Following is a list of the State's goals from the Forest Action Plan.

Goal I: Grow Forests, Habitats, Markets, and Jobs

Goal II: Manage Forest Health and Fire

Goal III: Provide Clean Water

Goal IV: Create Healthy, Livable Communities with Trees and Forests

Goal V: Respond to Climate Change

The Sugarloaf Planning Area is 17,140 acres in size. Forest cover is 58.5% of this total, or 10,036 acres. See Map 7-4 for identification of the forest cover in the Sugarloaf Planning Area. The contiguous and unfragmented condition of the vast majority of these forestlands provides exceptional landscape quality and environmental benefits, such as watershed protection and wildlife habitat. Additionally, many stream valleys and other areas within the Sugarloaf Planning Area have large amounts of forest. Forest cover and growth on the landscape is generally shaped by soil type, climate, topography, disturbance frequency (pests, disease, fire), and human activity.²

The forested landscape in the Sugarloaf Planning Area is a living testament to its ecological history, scenic beauty, and natural resource significance. Evolutionary processes over millennia and decades of land management for the long-term health and sustainability of the forests by the largest landowners, Stronghold, Incorporated and Maryland DNR, have contributed to the rich landscapes and exceptional

habitat in the Sugarloaf Planning Area. The vast forestlands in the Sugarloaf Planning Area provide air and water quality protection, biodiversity, aesthetic inspiration, and physical sustenance. They have inherent worth and intrinsic value.

The Sugarloaf Planning Area contains part of the State's Green Infrastructure Network. Green Infrastructure describes an area's significant natural resource base — the mountains, forestlands, wetlands, and natural landscapes (hubs) — and the connections between them (corridors). The State's Green Infrastructure Hub within the Sugarloaf Planning Area contains approximately 5,600 acres, as shown on Map 7-5. These significant natural resource lands within the Sugarloaf Planning Area have county, state, and region-wide environmental, cultural, and historical significance.

The Conservation Fund describes Green Infrastructure as an interconnected network of natural areas and other open spaces that conserve natural ecosystem functions, sustain clean air and water, and provide a wide array of benefits to wildlife and people. Green Infrastructure areas are environmentally rich and valuable areas, providing multiple ecosystem benefits or "services," such as:

- Storing and cycling nutrients
- Filtering and cooling water in streams and aquifers
- Conserving and generating soils
- Pollinating crops and other plants
- Sequestering carbon and purifying the air
- Protecting property from storm and flood damage
- Providing wildlife habitat

Green Infrastructure is defined as more than just open space, agricultural land, parks, or land not yet developed. Green Infrastructure emphasizes the linkages and connections between natural resource features and promotes the ecological processes of the natural environment. Conservation Biology principles and their application to Green Infrastructure hubs and corridors emphasize that interconnected blocks of habitat are better than isolated blocks, and that larger forest patches are better than smaller patches. Protecting biodiversity and natural systems is the broader goal of Green Infrastructure.

Green Infrastructure hubs are large natural areas that provide habitat for animal and plant species, as well as other environmental processes. Many species require large, unbroken tracts of forest, offering deep interior forest conditions, to carry out some portion of their life cycle. These are called FIDS — Forest Interior Dwelling Species. For example, many songbirds depend on Maryland's interior forests. Some of them are neotropical migrants, whose summer habitat here and winter habitat in tropical areas are increasingly threatened. Many unique and rare plant and animal communities are also threatened by habitat fragmentation that can increase the risk of predation or the displacement of native species by invasive, exotic species.

Policy 7.1

Promote the creation of Forest Management Plans and Forest Stewardship Plans that address increasing species and landscape diversity over time, including the extent and quality of older forests and early successional habitat. Such plans should include methods to control invasive pests, destructive insects, and diseases to prevent widespread forest mortality and loss of native forest types.

The Maryland Department of Natural Resources has modeled, using GIS technology, the locations where FIDS habitat is most likely to occur in Maryland. Due to the significant amount of contiguous

forest cover, the Sugarloaf Planning Area contains thousands of acres of probable FIDS habitat. Refer to Map 7-3 for a depiction of FIDS habitat, as described in the chart below.

Table 10. Forest Interior Dwelling Species Criteria – Sugarloaf Planning Area (MD DNR)

Class	Name	Definition	Acreage
I	FIDS Core Area	A forest patch that contains over 200 hectares (approx. 500 acres) of forest interior habitat*	6,611
II	High Quality FIDS Habitat	A forest patch at least 40 hectares (approx. 100 acres) in size that contains either at least 25% of forest interior habitat or riparian forest that averages 200 meters (656 feet) in width and is a minimum of 300 meters (984 feet) long	3,363
III	Potential FIDS Habitat	A forest patch at least 20 hectares (approx. 50 acres) in size that contains either at least 4 hectares (approx. 10 acres) of forest interior habitat or riparian forest that averages at least 100 meters (328 feet) wide and is a minimum of 150 meters (492 feet) long	653

*Forest Interior Habitat is defined as the portion of a forest tract that is at least 100 meters (328 feet) from the nearest forest edge.

Policy 7.2	Ensure timber harvesting activities in the Sugarloaf Planning Area achieve: enhanced protection of all waterways and drainages; minimal risk of stream sedimentation; protection of forests during critical breeding seasons for FIDS; and no degradation or negative impacts to forest quality, resilience, and wildlife habitat.
Policy 7.3	Support efforts of landowners and organizations to improve deer herd management to reduce deer browsing of native trees.

Maryland's Green Infrastructure Hubs contain one or more of the following:

- Large blocks of contiguous interior forest, containing at least 250 acres
- Important plant and animal habitats of at least 100 acres, including rare, threatened, and endangered species locations
- Significant ecological communities and migratory bird habitats
- High-quality stream and river segments and their associated riparian forests, floodplains, and wetlands that support trout, mussels, and other sensitive aquatic organisms
- Large wetland complexes

Maryland's Green Infrastructure corridors or links are portions of the landscape — usually in a linear assemblage — such as wooded stream valleys, forest belts, or ridges that allow animals, plant seeds, pollen, and water to move from one area to another, linking hubs together. Corridors are normally 1,000 feet wide and have long been considered an effective means of linking isolated "islands" of wildlife habitat that have been fragmented by development, agriculture, or some other impediment.

As the amount of land developed has increased, natural areas have not only decreased in area, but have undergone a significant increase in fragmentation. As human population and development pressures grow, it becomes increasingly important to have a plan to maintain the integrity and functionality of Green Infrastructure.³

The Maryland Department of Natural Resources (DNR) prepared its first Green Infrastructure Atlas in 2000, followed by a Green Infrastructure Assessment to identify the statewide network of natural

resource lands. The Green Infrastructure Assessment, based on principles of landscape ecology and conservation biology, identified an ecological network using satellite imagery to characterize land cover, Geographic Information System (GIS) data on road, stream, wetland, and other natural resource features, and biological databases.

An important component of the State's Assessment is the identification of gaps in the links/corridors that create impediments to the ecological systems. Gaps are disturbed lands within the green infrastructure network that produce corridor breaks or reduce interior habitat. Green Infrastructure gaps are areas with potential for restoring forest cover and wetland and riparian buffers to strengthen the ecological network, improve water quality, and provide habitat benefits.

Initiative 7A *Initiate the development and creation of a functional Green Infrastructure Plan for the County that prioritizes areas for forest restoration and conservation across ownerships to increase natural landscape continuity and reduce forest fragmentation*

The Green Infrastructure Assessment identifies Targeted Ecological Areas, lands and watersheds of high ecological value that are priorities for conservation by DNR through easement purchase, fee-simple acquisition, or other mechanisms from willing sellers. Sugarloaf Mountain and surrounding lands are within a Targeted Ecological Area. For more information on the State's Green Infrastructure Assessment, see: <https://dnr.maryland.gov/land/Pages/Green-Infrastructure-Mapping.aspx> or <https://dnr.maryland.gov/land/Pages/ProgramOpenSpace/Program-Open-Space-Evaluation.aspx>

The key functions of Maryland's Green Infrastructure Assessment are to:

- Systematically identify and protect ecologically important lands
- Address problems of forest fragmentation, habitat degradation, and water quality
- Emphasize the role of a given place as part of a larger interconnected ecological system
- Consider natural resource and ecosystem integrity in the context of existing and potential human impacts to the landscape
- Maximize the effectiveness of public and private conservation investments
- Promote shared responsibilities for land conservation between public and private sectors

The State, through its Green Infrastructure Network and Targeted Ecological Areas, has identified the best remaining ecological lands in Maryland. As a first step towards protection, opportunities for restoration of natural ecosystems have also been identified. Through examination of the location, extent, and configuration of forest cover in the Sugarloaf Planning Area, opportunities to improve forest connectivity in the larger Sugarloaf Green Infrastructure Network are apparent. Protecting, connecting, and restoring these natural landscapes will also help to enhance water quality, improve stream stability and flood attenuation, offset CO₂ emissions, and improve wildlife habitat in the Planning Area. The Green Infrastructure hubs and corridors in the Sugarloaf Area can be strengthened, and connectivity between all natural areas can be increased through widening forest corridors, enhancing vegetative riparian buffers, filling corridor gaps, enlarging and connecting small forest patches, and broadening the core Sugarloaf Green Infrastructure hub with additional forest cover.

There are many forested stream valleys and wooded areas in the Sugarloaf Planning Area that didn't meet the State's criteria for inclusion in the GI Network. These areas are also important and sensitive environmental features. Expanding these natural areas will benefit aquatic systems, habitat, and functional landscape integrity. The Sugarloaf Treasured Landscape Management Plan recommends their enhancement and restoration through the programmatic opportunities listed in the following section.



Policy 7.4	Retain existing forestlands, promote sound forestry management, and expand tree planting, including riparian forest buffers and the conversion of lawn to forest in the Sugarloaf Planning Area, to help achieve climate change resilience.
Policy 7.5	Collaborate with stakeholders, agencies, and organizations to use forests and trees to improve watershed conditions, including the conservation of forests critical for protecting high quality waters.
Policy 7.6	Emphasize forest connectivity when Forest Resource Ordinance easements are proposed during the land development process.
Initiative 7B	Establish the Sugarloaf Area Forest Initiative, modeled after the Linganore Watershed Forest Program, to utilize the County's Forest Resource Ordinance mitigation funds to plant new forest on private lands.

Programmatic Opportunities for Reforestation

Sugarloaf Area Forest Initiative (Frederick County)

This proposed program is modeled after the Linganore Watershed Forest Program of 2011, whereby the County's Forest Conservation Act mitigation funds were used to plant new riparian forest and preserve existing riparian forest on private lands in the Linganore Watershed. The new application of this initiative will involve the planting of new trees on lands to address forest fragmentation and create connectivity in the Sugarloaf Planning Area. This program will provide monetary compensation, planting, and maintenance in exchange for a permanent conservation easement on the area planted.

Creek ReLeaf (Frederick County)

The Creek ReLeaf program is a reforestation program assisting with the County's stormwater treatment requirements that is designed to increase the total amount of forested area within Frederick County, including privately owned lands and public properties. The program provides private landowners with native trees and shrubs planted on their property, five years of maintenance to establish the forest stand, and payment for a permanent reforestation easement that will be placed on the planted parcel. After the initial five years, the property maintenance reverts to the landowner with County inspections every three years.

Healthy Forests, Healthy Waters Program (Maryland DNR, Alliance for Chesapeake Bay)

This program provides opportunities for private landowners to establish new woodland cover on their property. Personalized tree planting plans that match landowner goals and site conditions are developed by the DNR Forest Service, with two-year maintenance provided. There is no perpetual easement placed on the new plantings or payment provided to the landowner.

Backyard Buffers (Maryland DNR)

In cooperation with the Potomac Watershed Partnership, this program assists landowners who have a stream or other waterway on or adjacent to their property to create a streamside buffer of native trees and shrubs.

Marylanders Plant Trees (Maryland DNR)

This program encourages residents and organizations to plant new trees through a State coupon program that provides a discount on the purchase of a native tree at dozens of participating nurseries across the state.

Lawn to Woodland Program (Maryland DNR)

In partnership with the National Arbor Day Foundation, this program provides assistance to landowners with the planting of trees, shrubs, and native plants in order to convert portions of mowed lawn to forest.

Tree-Mendous Maryland (Maryland DNR)

This program provides funding and assistance to help residents restore tree cover on public lands, private lands, and community open space.

Conservation Reserve Enhancement Program (USDA)

The Conservation Reserve Enhancement Program (CREP) is a cooperative program between the State of Maryland and the U.S. Department of Agriculture. CREP pays landowners to plant poorly productive agricultural field edges and borders in an approved practice that protects water quality and enhances wildlife habitat while continuing to allow farming or grazing on the most productive land. Frederick County administers a CREP easement program, sponsored by the Maryland DNR.

Forest

A forest is a dynamic and complex community of different plants (primarily trees), animals, and soils. A forest has multiple layers that provide varied habitats for many types of animals. The canopy is the “roof” of the forest, dominated by the tallest trees and the outer layers of leaves. The forest canopy captures rainfall and protects the ground surface. When rainfall hits tree leaves, some water flows to the branches and down the trunk for slow release into the soil. Rainfall is also slowed by hitting and dripping off leaves to the ground. Groundwater, pumped from the soil by the tree roots, is released from the leaves through transpiration and contributes, along with sun shading, to a cooler climate within a forest. Trees absorb carbon dioxide, which help purify our air. Trees combine atmospheric carbon (CO₂ gas), sunlight, and water to created glucose and oxygen during photosynthesis. The CO₂ gas from the air is transformed into the tree’s components and its wood. Trees and forests are remarkably simple — and remarkably beneficial — in the way they reduce erosive impacts of storm events on the land surface and clean the air we breathe.

Just below the canopy is the understory, which is a layer of smaller trees and shrubs. Young trees grow here to eventually replace older ones as they die. The forest floor is the ground level and includes small plants and seeds, plus fallen leaves, downed limbs and trees that provide shelter for wildlife. The forest floor is highly absorbent and stores large amounts of nutrients and water. The soil is also considered a layer in the forest, containing microorganisms, worms, insects, with leaves and twigs and other items undergoing decay and recycling. Tree roots in the soil remove nutrients and filter pollutants from groundwater flowing beneath the surface on its way to a stream or river.

Healthy Forests Reserve Program (USDA)

The goal of this program is to protect and enhance private forest ecosystems; promote the recovery of endangered and threatened species; improve plant and animal biodiversity; and enhance carbon sequestration. Conservation easements in this program are designed for varying term lengths, or in perpetuity with a share of costs paid to implement conservation practices.

Initiative 7C **Through partnerships with natural resource professionals, provide technical and financial assistance to help private landowners practice sustainable forest resource management and to transition lawn to natural areas.**

Policy 7.7 **Support education and outreach efforts of the Maryland DNR Firewise Program to promote fire awareness and prevention in the wildland-urban interface in the Sugarloaf Planning Area.**

Initiative 7D **Ensure existing capacities (e.g., plans, personnel, equipment) of local fire departments and emergency response agencies are sufficiently adequate for effective wildfire response and suppression.**

Initiative 7E **Engage the services of the Maryland DNR Forest Service to prepare Community Wildfire Protection Plans for eligible areas in the Sugarloaf Planning Area.**

Biodiversity

Biodiversity is the overall variety of life on our planet. It describes the differences and variability in organisms or life forms, habitats, species, and genetic types. Biodiversity and ecosystems produce the rich abundance of life on earth and the ecosystem services on which we rely. Ecosystem services contribute to jobs, economic growth, health, and human well-being.⁴

Human activities are causing massive impacts on biodiversity at all levels, but the impacts are most apparent to the general public at the species level and above as people witness loss of habitat, species extinction, disrupted communities, and polluted or otherwise damaged ecosystems.⁵ The impact of human activities on genetic diversity within a species is least apparent and, hence, is often ignored.⁶ Genetic diversity is at the lowest hierarchy in this biodiversity sequence, which enhances — not diminishes — its importance.⁶ Without genetic diversity, a population cannot evolve and adapt to environmental change.⁶

A recent study documented a 29% reduction in hundreds of bird species in North America over the past 50 years, signaling an “overlooked biodiversity crisis.”⁷ Birds provide ecosystem services such as dispersing seeds, consuming harmful crop pests and insects, acting as pollinators, and playing a key role in predator/prey relationships. The Cornell Laboratory of Ornithology cites agriculture (intensification, pesticide use), habitat loss, light pollution, building crashes, and outdoor cats for the decline in North American bird populations. Habitat alterations in Central and South America and climate change are also contributing to the decline. Sustainable agricultural practices, including the incorporation of hedgerows, trees, and grassy margins with cultivation and grazing operations provide food, cover, and habitat that can help increase bird populations.⁷



Adult with poult, Comus Road

The Biodiversity Conservation Network (BioNet) is an ecological database and digital map that integrates the Maryland DNR's vast data and prioritizes areas for terrestrial and freshwater biodiversity conservation. It was developed by the DNR to use for proactive land conservation activities, such as targeting for acquisitions and easements, locating appropriate areas for project mitigation or habitat restoration, and planning for areas that require management to sustain dwindling species and habitats. In addition to focusing on vanishing species and habitats, and on high quality common habitats, the criteria used in BioNet also were designed to incorporate the large landscape required for migratory animals, population dispersal, and habitat shifts from climate change. In summary, BioNet includes and prioritizes:

Only known occurrences of species and habitats	Animal assemblages (e.g., forest interior species)
Globally rare species and habitats	Intact watersheds
Animals of Greatest Conservation Need	Wildlife corridors and concentration areas
Watch List plants and indicators of high-quality habitats	

These areas are prioritized into a five-tiered system based on a continuum of rarity, diversity, and quality with Tier I being the highest for biodiversity conservation, as shown on the BioNet Map for the Sugarloaf Planning Area (Map 7-1):

Tier 1: Critically Significant for Biodiversity Conservation	Tier 4: Moderately Significant for Biodiversity Conservation
Tier 2: Extremely Significant for Biodiversity Conservation	Tier 5: Significant for Biodiversity Conservation
Tier 3: Highly Significant for Biodiversity Conservation	

The DNR's five-tiered system was designed to capture and support the full array of biological diversity within Maryland — not just those places that are one-of-a-kind — but also the places that area needed to maintain viable populations of more common species. Keeping common species common is a goal that will provide enormous benefits to both our quality of life and our economy. Society cannot afford to wait until herculean efforts are necessary to save species from the brink of extinction; the costs of these efforts are staggering. Therefore, even Tier 5 BioNet Areas are still significant to conserve, both for the species they directly support and for maintenance of the larger fabric of our natural landscape (MD DNR).

Over 60% of the Sugarloaf Planning Area has biodiversity significance and conservation value. By focusing on the protection of the natural resource base and rural setting of the Sugarloaf Area, the Sugarloaf Treasured Landscape Management Plan strives to maintain landscapes and habitats, thus preserving biodiversity.

Table 11. Biological Conservation Network (BioNet) – Sugarloaf Planning Area (Maryland DNR)

BioNet Tier	Acres	Percentage of Sugarloaf Planning Area
Tier I – Critically Significant	185	1.04%
Tier II – Extremely Significant	3,218	18.2%
Tier III – Highly Significant	6,367	36.1%
Tier IV – Moderately Significant	40	<1%
Tier V – Significant	1,328	7.5%

Ecologically Significant Areas

The Sugarloaf Planning Area contains five State-designated Ecological Significant Areas (ESAs), attesting to the unique landscapes and species found there. This community of living organisms and the interactions they have with physical elements (air, soil, water, sunlight) is an ecosystem. ESAs are buffered habitats of rare, threatened, and endangered species, as well as significant or rare habitats and ecological systems. The plant and animal populations in four of the ESA areas in the Planning Area have a Maryland conservation status ranking of "Highly State Rare" or "State Rare," indicating the organism is at a high or very high risk of extinction or extirpation due to restricted or very restricted ranges, few or very few populations or occurrences, steep or very steep declines, severe or very severe threats, or other factors (MD DNR).

Table 12. Ecologically Significant Areas in the Sugarloaf Planning Area

ESA	Acres	Conservation Significance within Biodiversity Conservation Network (BioNet)	Elements of Biodiversity ¹
1) Bells Chapel Woods	185	Tier I – Critically Significant	1
2) LilyPons	313	Tier III – Highly Significant	5
3) Lower Monocacy River	123	Tier II – Extremely Significant	3
4) Potomac River-Monocacy	1,223 (57 ac. within Sugarloaf Area)	Tier III – Highly Significant	4
5) Sugarloaf Mountain	2,838	Tier II – Extremely Significant	5

(Maryland DNR, Wildlife and Heritage Service)

¹ Biodiversity elements include rare species, threatened species, endangered species, colonial-nesting waterbirds, or significant ecological communities.

Below are descriptions of each ESA as provided from the Maryland DNR, Wildlife and Heritage Service, with generalized depictions on Map 7-2:

- Bells Chapel Woods – A rare example of old-growth forest in Frederick County. This site is primarily on rocky slopes and relatively free of invasive plants. Canopy trees reaching over 80 feet in height are present, including chestnut oak, northern red oak, and tulip poplar, with some oaks reaching 35 inches in diameter. These large trees are over 250 years old. Understory and shrub layers include red maple, American beech, black gum, mountain laurel, and blueberry. Vertical structural diversity, downed woody debris, large snags, and canopy gaps caused by the mortality of old trees are additional characteristics of old growth forest in this natural area. Although there are a few stumps in the northern section, indicating some tree removal, multiple growth layers and older trees still occur throughout the natural area. The forest contains the highest quality or "core" habitat for forest interior dwelling species (FIDS), especially birds such as wood thrush and scarlet tanager, and for other species that benefit from old growth forest habitat characteristics.
- Lily Pons – The man-made freshwater ponds at LilyPons Water Gardens provide habitat for some rare breeding birds, as well as a total of 252 birds that have been reported from this general area. These rare wetland breeding birds are found in freshwater marshes in primarily coastal counties in Maryland. However, these ponds provide a wetland oasis along the Monocacy River that replicates natural freshwater marsh habitat that these species require for breeding. The ponds also provide stopover habitat during spring and fall migrations, as birds head north for the summer and then south for the winter after the summer breeding season.

Wildland Fire

Wildfire is a common occurrence in Maryland. In fact, the Maryland Forest Service responds to over 500 wildfires in an average year, which burn more than 4,000 acres of land. Fire departments respond to even more wildlife incidents, averaging over 5,000 per year. Compared to other counties in Maryland, Frederick County has a disproportionately high number of wildlife ignitions due to the abundance of people in close proximity to wildland fuels. This makes wildfire a very real threat in Frederick County, where in the past 35 years approximately 700 wildfires have burned over 1,000 acres of land.

The wildland-urban interface is a zone where houses and other structures intermingle with wildland fuels, and is an area where homes and lives are at high risk of the dangers associated with wildfires. This zone has been rapidly expanding in Maryland in recent years as more and more people build houses in or near the forest.

Wildfire is a very real threat in Maryland. Since humans cause 98% of the fires in Maryland, the wildland-urban interface is also an area where the risk of wildfire ignitions increases. In 2011 alone, 29 structures in Maryland were destroyed by wildfires, with an additional 15 structures damaged and 141 threatened. Maryland's leading cause of wildfires is improper debris or outdoor burning, which ignites about 29% of wildfires each year. Arson, the second leading cause, accounts for around 25% of ignitions. Other causes of wildfire include equipment use, children playing with fire, campfires, railroads, downed power lines, discarded woodstove or fireplace ashes, and fireworks.

For these reasons, the Firewise Maryland Program of the Maryland DNR Forest Service is promoting fire awareness and prevention through community outreach and education. This includes instructing homeowners on how to protect themselves from wildfire by changing how they landscape around their homes and maintain their yards. The Firewise Maryland Program will also prepare Community Wildfire Protection Plans for at-risk Wildland-Urban Interface communities.

- Lower Monocacy River – This area is a Montane-Piedmont floodplain terrace forest along the lower Monocacy River, located north of the confluence with the Potomac River. Sections of this area regularly flood, depositing rich organic matter into the soil. These alluvial soils support a floodplain forest composed mainly of silver maple, box elder, and American sycamore, with an understory dominated by spicebush. The area also contains a diverse herbaceous layer, which includes rare and endangered plants.
- Potomac River-Monocacy – This area extends for 5.2 miles along the Potomac River, beginning approximately 0.63 miles above the Monocacy River, south to Mason Island in Montgomery County, Maryland. Within the Sugarloaf Planning Area, this ESA covers 57 acres and extends 0.60 miles upstream on the Monocacy River from its confluence with the Potomac River. The area contains a species of dragonfly that is highly rare in Maryland.
- Sugarloaf Mountain - Wooded areas of the mountain provide habitat for abundant wildlife species. Oak trees, mostly red and white oaks, grow on drier, higher slopes and tulip poplars dominate lower, moister slopes and stream margins. Black oak, chestnut oak, black birch, eastern hemlock, dogwood, and sassafras are also common here. Vegetation grows thickly along main streams, while on the drier slopes, the herbaceous layer is sparse and composed of a few hardy species. The quartzite that forms Sugarloaf Mountain causes soils to be acidic in nature, supporting an array of plants that thrive in this soil type. The understory of the Sugarloaf Mountain forest is composed of mountain laurel, pinxter flower, flowering dogwood, wild hydrangea, and maple-leaved viburnum. Native wildflowers like pink lady's slipper, Canada mayflower, and rattlesnake weed are found in pockets of soil and rocky outcrops all over the mountain.

Along streams and in swampy areas, skunk cabbage dominates, associated with species including downy arrowwood, yellow corydalis, Canada mayflower, tall meadow-rue, and marsh blue violet. Blunt-lobe grapefern (*Sceptridium oneidense*, state-listed as Endangered) can be found in these swampy environments, and some showy, uncommon flower species find safe growing spaces in mucky, tangled thickets. Reflexed flatsedge (*Cyperus refractus*, state listed as Rare) occurs in seeps and ditches in the area.

The mountain and surrounding land provide habitat for many animals, including an array of forest-dwelling birds. These include larger birds such as the red-shouldered hawk, wild turkey, pileated woodpecker, and great horned owl, as well as smaller migratory birds like the scarlet tanager and black-and-white warbler.

The Maryland DNR Natural Heritage Program completed a State Wildlife Action Plan in 2015. The plan details key wildlife habitats, natural communities, and Species of Greatest Conservation Need statewide, and provides information on threats and conservation needs of Maryland's wildlife resources and supporting habitats. The Maryland Wildlife Action Plan can be accessed at http://dnr.maryland.gov/wildlife/Pages/plants_wildlife/SWAP/Submission.aspx


Policy 7.8

Foster increased awareness and appreciation of environmental resources and their relationship to man-made systems, and support for management action to sustain and protect resource function and quality.

Initiative 7F	<p>Collaborate with conservation groups, governmental entities, and willing landowners to establish a “Forest Management for Wildlife” demonstration area to showcase ecological forestry techniques to improve desired wildlife habitats, from managing towards mature forest conditions to designing early successional habitat to benefit declining shrubland species, such as American woodcock, bobwhite quail, and ruffed grouse.</p>
Initiative 7G	<p>To improve public safety and reduce the costs of property insurance for residents and businesses within the Planning Area, establish a network of water storage tanks to be owned and maintained by the County for rural fire suppression. Once piloted in the Sugarloaf Area, this initiative should be expanded to other rural parts of the County.</p>



Map 7-1




Biodiversity Conservation Network

- Tier 1
- Tier 2
- Tier 3
- Tier 4
- Tier 5



Map 7-2




Ecologically Significant Areas



Map 7-3

Forest Interior Dwelling Species (FIDS) Habitat Areas as Modeled by MD-DNR




Class I - Core Area

Class II - High Quality Habitat

Class III - Potential Habitat



Map 7-4



DNR Green Infrastructure


Hubs

Gaps

Corridors

Rural Roads





Climate Change

The accuracy of scientists' predictions that climate change would bring more severe storms, increased flooding, higher temperatures, more drought, and reduced agricultural yields is evident with each passing year. Our planet is experiencing melting glaciers and ice sheets that raise sea levels. Higher air temperatures are thawing permafrost, which releases more carbon dioxide and methane into the atmosphere. Marine heat waves, altered sea currents, and stronger hurricanes are all consequences of oceans absorbing the extra heat in the atmosphere. A "compound" or "cascading" disaster is the concept scientists apply to the massive forest fires in the western U.S. in 2020: record heat, droughts, extreme weather fronts from unstable jet stream air patterns creating intense storms with lightning strikes — all exacerbated by changes in our climate from increasing global greenhouse gas emissions. Climate change models predict that we will see meteorological extremes that produce catastrophic fires in unexpected places and outside of normal fire seasons.¹ In the east, for instance, an exceptional drought helped to produce a fatal wildfire in the Great Smokey Mountains of Tennessee in 2016. Blazes near Gatlinburg burned more than 10,000 acres and killed 14 people. To put the size of the 2016 Tennessee fire in perspective, the 10,000 acres that burned in the Great Smokey Mountains is equivalent to all the forestlands in the Sugarloaf Planning Area (10,036 acres).

Volume II of the Fourth National Climate Assessment (NCA4), released in November 2018 by the United States Global Change Research Program, reported that climate change is affecting the natural environment, agriculture, energy production and use, land and water resources, transportation, and human health and welfare across the U.S. and its territories.²

Over 11,000 scientists from a broad range of disciplines warned in a November 2019 report³ that planet Earth clearly and unequivocally faces a climate emergency and described six broad categories that must be addressed in order to avoid potential irreversible climate tipping points and nature's reinforcing feedbacks (atmospheric, terrestrial, marine) that could lead to catastrophic warming.

1. Energy: sources, efficiencies, conservation
2. Short-lived pollutants: methane, black carbon-soot, hydrofluorocarbons
3. Nature: restoration, carbon sequestration
4. Food: animal production
5. Economy: resource extraction and overexploitation
6. Population: fertility, consumption, waste

Local and State Action

Frederick County's 2020 Climate Emergency Resolution (No. 20-22, adopted July 21, 2020)⁴ strives to reach net zero greenhouse gas emissions, improve carbon sequestration, and implement measures to protect people and nature from the adverse consequences of climate change. The County acknowledges the effect temperature changes have had on ecological stability and safety, as evidenced by increased wildfires, floods, rising seas, climate refugees, diseases, droughts, and the ongoing mass extinction of species. The County also acknowledges that climate change adversely affects county infrastructure and emergency and social services, influences our access to food, water, and energy, and disrupts commerce and our quality of life.

Policy 8.1

Factor climate change into all land use and planning initiatives and processes to achieve a natural and built environment that is highly resilient and adaptive.



Initiative 8A Support County efforts to develop policies and plans that address climate change and sustainability in a coordinated and comprehensive manner.

Maryland's 2016 Greenhouse Gas Emission Reduction Act - Reauthorization requires the state to achieve a minimum of a 40% reduction in statewide greenhouse gas (GHG) emissions from 2006 levels by 2030, and to develop and adopt a statewide GHG Reduction Plan (2030 Greenhouse Gas Emission Reduction Act Plan, 2030 GGRA Plan). The State is required to demonstrate that the new reduction goal can be achieved in a way that has a net positive impact on Maryland's economy, protects existing manufacturing jobs, and creates significant new "green" jobs in Maryland.

The Maryland Department of the Environment (MDE) developed the 2030 GRRA Plan in coordination with other state agencies and stakeholders, including the bipartisan Maryland Commission on Climate Change. The 2030 GRRA Plan includes a comprehensive set of more than 100 measures to reduce greenhouse gas emissions, including investments in energy efficiency, clean and renewable energy solutions, widespread adoption of electric vehicles, and improved management of farms and forests. It also supports new industries and technologies by encouraging investment in the energy and transportation sectors. The MDE estimates as much as \$11.54 billion in increased economic output in the state by 2030, and the creation of more than 11,000 jobs as a result of these proposals.

The 2030 GRRA was submitted to the Governor and State Legislature on February 19, 2021.

Key elements of the 2030 GRRA include:

- Governor Hogan's proposed Clean and Renewable Energy Standard (CARES) and its requirement for 100% clean electricity by 2040 — one of the most ambitious goals in the nation.
- An increased emphasis on clean transportation through the Maryland Clean Cars program, expanded investment in public transit, upgrades of half of the state's transit buses to clean power, and, potentially, the regional Transportation and Climate Initiative's "carbon cap-and-invest" program.
- Continued participation and leadership in the geographically expanding Regional Greenhouse Gas Initiative (RGGI), the market-based program to reduce greenhouse gas emissions from power plants.
- Programs to phase out the use of hydrofluorocarbons (HFCs), greenhouse gases that are significantly more potent than carbon dioxide, and to better identify and reduce methane leaks in the energy sector.
- Enhanced healthy soil initiatives, through which farmers can make significant contributions to climate change goals by sequestering carbon.
- Increasing the energy efficiency of buildings through investments under the EmPOWER Maryland program, along with the implementation of Governor Hogan's executive order directing state buildings to reduce energy use by an additional 10%.

For more information on the State's Climate Change Program and the Greenhouse Gas Emissions Reduction Plan, see:

<https://mde.maryland.gov/programs/Air/ClimateChange/Pages/index.aspx>

[https://mde.maryland.gov/programs/Air/ClimateChange/Pages/Greenhouse-Gas-Emissions-Reduction-Act-\(GGRA\)-Plan.aspx](https://mde.maryland.gov/programs/Air/ClimateChange/Pages/Greenhouse-Gas-Emissions-Reduction-Act-(GGRA)-Plan.aspx)

The Carbon Cycle

The element carbon is present in the atmosphere, seawater, soils, rocks (such as coal and limestone), plants, and all living things. Carbon moves through these realms as part of the carbon cycle.

Carbon transfers and moves from:

The Atmosphere to Plants. In the air, carbon is affixed to oxygen in a gas (CO₂ — Carbon Dioxide). Plant photosynthesis involves pulling CO₂ from the air to produce food for plant's growth, becoming part of the plant, and stored as wood. Trees use or "sequester" significant amounts of CO₂ from the air.

Plants to Animals. Through food chains, the carbon in plants transfers to animals that eat plants.

Animals to the Atmosphere. Respiration (breathing) from living organisms puts CO₂ gas into the air.

Atmosphere to Oceans. Much carbon is absorbed by the oceans and other waterbodies throughout the world.

Plants and Animals to Soils. When animals and plants die, they decompose and decay, putting carbon into the ground and soil, eventually becoming fossil fuels over millions of years.

Fossil Fuels to the Atmosphere. When oil, coal, or biomass (wood and plant debris) is burned for power generation or automobiles, carbon enters the atmosphere as CO₂ gas. Each year, billions of tons of carbon are released by burning fossil fuels. Wood products made from harvested trees do not contribute to CO₂ emissions, but their removal from the natural environment ends additional carbon uptake. Most CO₂ stays in the atmosphere where it acts as a greenhouse gas, trapping heat in our atmosphere. Without CO₂ and other greenhouse gases (e.g., methane, nitrous oxides), the Earth would be frozen, but humans have released so much CO₂ into the atmosphere by burning enormous quantities of fossil fuels to power our human civilization that it is causing increased warming and changes to our climate.

In 2019, the Maryland Legislature passed the Clean Energy Jobs Act (HB 1158, SB 516), which requires Maryland's Renewable Portfolio Standards (RPS) to increase to 50% by 2030, including a goal for 100% clean, renewable electricity by 2040. The RPS requires electricity suppliers to have a minimum portion of their retail electricity sales from a variety of renewable energy sources, known as Tier I and Tier II renewable sources.

Policy 8.2 **Support alternative energy production and storage systems, while carefully evaluating their impact on forestlands, viewsheds, and the transportation network in the Sugarloaf Planning Area.**

Agriculture and Carbon Sequestration

Agricultural land comprises over 1/3 of the Sugarloaf Planning Area. Agriculture has a large and pivotal role in greenhouse gas emission reductions in Maryland. Regenerative agricultural practices, such as the use of cover crop diversity, deep-rooted crops, and no-till systems, help to "regenerate" soil biology by rebuilding and increasing soil organic matter and supporting the living ecosystems of beneficial soil microbes which, in turn, improves plant health and crop productivity. Healthier soils contain more organic matter and plant biomass that sequester carbon and retain water, which limits runoff, improves filtration, and helps crops to be more resilient in drought conditions and during heavy storms. Less fertilizer and energy usage are other beneficial results of regenerative agricultural systems.

Policy 8.3 **Support sustainable, regenerative agricultural practices in the Sugarloaf Planning Area that enhance soil productivity and carbon sequestration, and protect water quality, thus providing overall greater resilience to climate change.**

Initiative 8B **Explore the creation of a new County programmatic initiative to engage willing landowners to replace turf grass with conservation landscaping to: reduce greenhouse gas emission (from less mowing), enhance pollinator habitat, and increase vegetative diversity.**

Guidance is provided in the Chesapeake Conservation Landscaping Council's Conservation Landscaping Guidelines: https://chesapeakelandscape.org/wpcontent/uploads/2014/04/8_elements_2013.pdf

In 2020, the Maryland General Assembly passed HB 687/SB597 permitting the Maryland Agricultural Water Quality Cost-Share Program (MACS) funds to be utilized for "natural filter practices." These practices are defined as: planting of riparian buffers; planting of herbaceous cover, including cost share for multi-species cover crops equal to single species; tree plantings on agricultural lands and outside of riparian buffers; wetland restoration; and pasture management, including rotational grazing systems such as livestock fencing and watering systems implemented as part of conversion of cropland to pasture.

Initiative 8C **Establish, fund, and showcase a pilot program that engages a willing land owner/farm operator in the Sugarloaf Planning Area to convert or enhance an existing agricultural operation to a system that incorporates more regenerative practices and carbon sequestration.**

Initiative 8D **Partner with the USDA, MDA, the Frederick Soil Conservation District and other experts to supply technical design, installation, and adoption assistance to implement HB 687/SB 597, the Agricultural Cost Share Program-Fixed Natural Filter Practices in the Sugarloaf Planning Area.**

Forests and Carbon Sequestration

Trees and forests are sometimes described as “carbon sinks,” a condition where carbon dioxide is sequestered — absorbed or retained and stored by the organism or segment of the environment. When trees die, decompose, or are harvested or burned, some of this stored carbon is released back to the atmosphere. According to the U.S. Forest Service, trees can store substantial amounts of carbon — 1 acre of trees in the temperate zones (including Maryland) can sequester 40 tons of carbon annually.

Carbon storage by forestlands is valuable because carbon that would otherwise have been emitted into the atmosphere as CO₂, causing climate change, is instead trapped in living trees. Sequestration, therefore, helps reduce CO₂ concentrations, reducing the negative effects of climate change. The reduction of these negative effects on people and the planet provide the economic benefit of carbon stored by forests.⁵ Increased carbon storage on forest lands, or expansion of forest lands via afforestation, can also involve notable changes in other valued ecosystem services, including water quality, habitat for terrestrial and aquatic species, and provision of timber.⁶

From the onset of European settlement to the start of the last century, changes in U.S. forest cover due to expansion of agriculture, tree harvests, and settlements resulted in net emissions of carbon. More recently, with forests reoccupying land previously used for agriculture, technological advances in harvesting, and changes in forest management, U.S. forests and associated wood products now serve as a substantial carbon sink, capturing and storing more than 227.6 million tons of carbon per year.⁷ Forests and wood products store about 16% of all the CO₂ emitted annually by fossil fuel burning in the United States.⁸ Climate change and disturbance rates, combined with current societal trends regarding land use and forest management, are projected to reduce forest CO₂ uptake in the coming decades.⁹

Efforts in forestry to reduce atmospheric CO₂ levels have focused on forest management and forest product use. Forest management strategies include land-use change to increase forest area (afforestation), avoid deforestation, and optimize carbon management in existing forests. Carbon

Paris Climate Agreement

The Paris Agreement under The United Nations Framework Convention on Climate Change, also called Paris Climate Agreement or COP21, is a landmark environmental accord that was signed by 197 countries in 2015 to address climate change and its negative impacts. The Paris Agreement set out to improve upon and replace the Kyoto Protocol, an earlier international treaty designed to curb the release of greenhouse gases. The 2015 Agreement aims to substantially reduce global greenhouse gas emissions in an effort to limit the global temperature increase in this century to 2 degrees Celsius above pre-industrial levels, while pursuing means to limit the increase to 1.5 degrees. The agreement includes commitments from all major emitting countries to cut their climate-altering pollution and to strengthen those commitments over time. The pact provides a pathway for developed nations to assist developing nations in their climate mitigation and adaptation efforts. It creates a framework for the transparent monitoring, reporting, and strengthening countries’ individual and collective climate goals.

management in existing forests can include practices that increase forest growth, such as fertilization, irrigation, switching to fast-growing planting stock, shorter rotations, and weed, disease, and insect control. Increasing the interval between harvests, decreasing harvest intensity, and focused density/species management are also effective carbon management practices in existing forests.¹⁰ Forest product-use strategies include the use of wood wherever possible as a structural substitute for steel and concrete, which require more carbon emissions to produce. The carbon emissions offset from using wood rather than alternate materials for a range of applications can be two or more times the carbon content of the product.¹¹

Policy 8.4

Preserve vast forestlands in the Sugarloaf Planning Area that comprise an “ecological sanctuary” and acknowledge their importance in providing clean water, sequestering carbon, and mitigating climate change.

The amount of global carbon dioxide (CO₂) — a greenhouse gas — in the air reached a record of 417 parts per million (ppm) in May of 2020¹², even with the economic slowdown caused by the COVID-19 pandemic. The rate of increase of greenhouse gas emissions in the air is also accelerating, from an annual growth rate of 0.8ppm in the 1960's to 2.4 ppm per year in the last decade. A reduction in greenhouse gas emissions has occurred in 2020 but according to a Scripps Institute of Oceanography news release about the May 2020 record figure, CO₂ emissions reductions of 20% to 30% would need to be sustained for 6 to 12 months in order for the increase in atmospheric CO₂ to slow in a detectable way.

The National Oceanic and Atmospheric Administration (NOAA) and the National Aeronautics and Space Administration (NASA) reported that 2019 was the second hottest year on record, caused by human activity releasing tons of CO₂ into the atmosphere each year.¹³ Every decade since the 1960's has been warmer than the previous decade. Climate scientists around the world predict that limiting Earth's warming to no more than 2 degrees Celsius above pre-industrial levels is needed to prevent catastrophic environmental and social consequences.

Local Impacts and Solutions

Milder winters with less snowfall are occurring in Maryland more frequently. Maryland has experienced an increase in annual average temperature of 1.5 degrees Fahrenheit since the beginning of the 20th century.¹⁴ Maryland's annual mean precipitation has been above average for the past two decades.¹⁵ The climate in this region is generally expected to continue trending warmer and wetter over the next century, accompanied by an increase in extreme heat waves and precipitation events.¹⁶ Locally, severe flooding occurred in Frederick County in September 2015 and again in May 2018, damaging property and infrastructure. Increases in the frequency and magnitude of flooding events pose threats to transportation infrastructure and hazards to motorists in the Sugarloaf Area where the following roads closely parallel stream systems:

- Peters Road – Bennett Creek
- Mt. Ephraim Road – Bear Branch
- Thurston Road (southern section) – Little Bennett Creek

Additionally, multiple streams in the Sugarloaf Area flow under roads through culverts, which also have potential to cause roadway flooding since their original designs most often did not account for sizing to convey and accommodate more intense storm events. Increased runoff volumes from more rainfall, increased runoff velocities from the area's topography, and debris blockage in culverts can create hazards during flooding events.



Peters Road at Bennett Creek

Policy 8.5 All future repairs and upgrades of stream culverts in the Sugarloaf Planning Area should be designed to: ensure unimpeded upstream and downstream movement of aquatic organisms and other wildlife; minimize stream scour and erosion; and accommodate more intense storms and frequent flooding events.

Initiative 8E Explore options with the Department of Public Works and the Office of Sustainability and Environmental Resources to address the compromised stream bank stabilization structure and associated stream channel erosion located along a tributary to Little Bennett Creek, adjacent to Sugarloaf Mountain Road.

Changes in land use and land cover affect local, regional, and global climate processes such as urban heat islands, ozone pollution, and greenhouse gas concentrations.¹⁷ Choices about land use and land cover have affected and will continue to affect how vulnerable or resilient human communities and ecosystems are to the effects of climate change.¹⁸

Policy 8.6 **Expand the capacity of the Sugarloaf Planning Area to provide essential contributions to the County's efforts to reduce, mitigate, and adapt to climate change.**

Policy 8.7 **Endorse and support a variety of "green" principles and technologies and climate-sensitive methods in building and site design (e.g., energy efficient components and accessories, passive solar design) to help mitigate and adapt to climate change.**

Initiative 8F **Accelerate the promotion of the Commercial Property Assessed Clean Energy Loan (C-PACE) Program for investment in clean energy, conservation, and carbon drawdown activities, such as energy efficiency, renewable energy, water conservation projects, green infrastructure, grid resiliency, and energy management techniques.**

Incentive programs and management strategies to expand and retain forest cover in the Sugarloaf Planning Area will achieve greater carbon sequestration, and enhance wildlife habitat and natural landscape connectivity. Stewarding a healthy, vigorous forest through sound and sustainable management practices will help increase resilience to climate change-related environmental changes. Implementing regenerative agricultural practices in the Sugarloaf Planning Area can ensure a healthy, sustainable agricultural sector that helps to advance atmospheric carbon drawdown. Reducing the growth of impervious surfaces and high traffic-generating land uses will help protect water and air quality and maintain the rural characteristics of the Sugarloaf Planning Area. All of the aforementioned measures constitute "low carbon" land use strategies.

Policy 8.8 **Reduce greenhouse gas emissions by limiting the growth of high vehicle trip-generating land uses in the Sugarloaf Planning Area.**

The Sugarloaf Treasured Landscape Management Plan advances localized climate change adaptation and mitigation measures. Reflecting community values and priorities, the plan promotes actions and policies for stewardship of natural resources and to sustain **environmental** (ecosystem services, biodiversity), **social** (quality of life, sense of place), and **economic** (human activity, "experience" economy) benefits for future generations.



Citations and Footnotes

Chapter 3 Stronghold, Incorporated and Sugarloaf Mountain

1 <https://www.nps.gov/subjects/nlandmarks/index.htm>

Chapter 4 Land Use

1 <http://federalleadership.chesapeakebay.net/EO/file.axd?file=2009%2f8%2fChesapeake+Executive+Order.pdf>

2 <https://www.epa.gov/chesapeake-bay-tmdl>

3, 5 EPA, 2013. A Model Program for Onsite Management in the Chesapeake Bay Watershed. June 2013. U.S. Environmental Protection Agency, Office of Wastewater Management, Washington, DC. https://federalleadership.chesapeakebay.net/130627_ches_bay_tech_assist_manual.pdf

4 Lowe, K.S., N. Rothe, J. Tomaras, K. DeJong, M. Tucholke, J. Drewes, J. McCray, and J. Munakata-Marr (2007). Influent Constituent Characteristics of the Modern Waste Stream from Single Sources: Literature Review. Water Environment Research Foundation. 04-DEC-1. www.ndwrcdp.org/publications.

Chapter 5 Transportation

1 Managed lanes are an option to provide travelers a choice of single-occupant vehicle travel in specific areas of roadways

2 The National Environmental Policy Act of 1969 (NEPA) is a federal environmental law that established processes to evaluate the needs and benefits of a federal action and the potential environmental impacts arising from the action. The law requires development of a reasonable range of project alternatives that can accomplish the purpose and need, and consideration of potential impacts to socioeconomic, cultural, and natural resources from the alternatives being considered. Key to this process is coordination among federal, state, and local agencies, and communication with the public, and other project stakeholders.

3 Section 4(f) refers to the section of the 1966 Transportation Act that requires “consideration of park and recreational lands, wildlife and waterfowl refuges, and historic sites during transportation project development.”

Chapter 6 Watershed Water Quality

1 https://www.frederickcountymd.gov/DocumentCenter/View/291410/FCSS_2008-2011-County-Wide-Results?bidId

2 <https://www.frederickcountymd.gov/DocumentCenter/View/304884/FINAL-Frederick-County-Stream-Survey-2013-2016-Countywide-Results>

3, 4 Paul, M.J., J.B. Stribling, R.J. Klauda, P.F. Kayzak, M.T. Southerland, and N.E. Roth. 2002. A Physical Habitat Index for Freshwater Wadeable Streams in Maryland. Prepared by Tetra Tech Inc., Owings Mills, MD; Versar, Inc., Columbia, MD; and Maryland Department of Natural Resources, Monitoring and Non-Tidal Assessment Division

5,6 Versar, Inc. 2017. Frederick County Stream Survey 2013-2016 Four Year Report. Prepared by Versar, Inc., Columbia, MD for Frederick County Office of Sustainability and Environmental Resources.

7, 11 <https://dnr.maryland.gov/waters/Pages/Watershed-Action-Strategy.aspx>

8 Maryland Department of Natural Resources (MDDNR), Watershed Services, Landscape and Watershed Analysis, Management Studies. 2003b. Report on Nutrient Synoptic Survey in the Lower Monocacy River Watershed Restoration Action Strategy, Frederick County, Maryland, April 2003 as part of the Watershed Restoration Action Strategy. Maryland Department of Natural Resources, Annapolis, MD in Tetra Tech, Inc. 2008. Bennett Creek Watershed Assessment. Prepared by Tetra Tech, Incorporated for the Frederick County Division of Public Works.

9 Jessup, B.K., A. Markowitz, J.B. Stribling, E. Friedman, K. Labelle, N. Dziepak. 2003. Family-level Key to the Stream Invertebrates of Maryland and Surrounding Areas, 3rd edition. Maryland Department of Natural Resources, Chesapeake Bay and Watershed Programs, Monitoring and Non-Tidal Assessment Division. CBWP-MANTA-EA-99-2.

10 Roth, N.E., M.T. Southerland, G. Mercurio, J.C. Chaillou, P.F. Kazyak, S.S. Stranko, A.T. Prochaska, D.G. Heimbuch, and J.C. Seibel. 1999. State of the Streams: 1995-1997 Maryland Biological Stream Survey Results. Prepared by Versar, Inc., Columbia, MD and Post, Buckley, Schuh, and Jernigan, Inc., Bowie, MD for the Maryland Department of Natural Resources, Monitoring and Non-Tidal Assessment Division

12 Karr, J.R. 1996b. Rivers as Sentinels: Using the biology of rivers to guide landscape management in R.J. Naiman and R.E. Bilby, eds. The Ecology and Management of Streams and Rivers in the Pacific Northwest Coastal Ecoregion. Springer-Verlag, New York.

13 Stranko, S.A., R.H. Hilderbrand, R.P. Morgan, M.W. Staley, A.J. Becker, A. Roseberry-Lincoln, E.S. Perry, and P.T. Jacobson. 2008. Brook Trout Declines with Land Cover and Temperature Changes in Maryland. *North American Journal of Fisheries Management*. 28: 1223-1232.

14, 15 Maryland Department of Natural Resources, Inland Fisheries Management Division. 2006 Maryland Brook Trout Fisheries Management Plan, A. Heft (eds.), Annapolis, Maryland

16 Spooner, D.E., M.A. Xenopoulos, C. Schneider, and D.A. Woolnough, 2011: Coextirpation of host-affiliated relationships in rivers: The role of climate change, water withdrawal, and host-specificity. *Global Change Biology*, 17, 1720-1732, doi: 10.1111/j.1365-2486.2010.02372.x.

17 Chesapeake Stormwater Network. 2011. Technical Bulletin No. 3, Implications of the Impervious Cover Model: Stream Classification, Urban Subwatershed Management and Permitting.

Chapter 7 Forestlands, Green Infrastructure and Biodiversity

1 Maryland Department of Natural Resources. 2020. Forest Action Plan 2020-2050. Part I: Forest Resource Assessment, Part II: Strategy

2 Joyce, L.A., S.W. Running, D.D. Breshears, V.H. Dale, R.W. Malmesheimer, R.N. Sampson, B. Sohngen, and C.W. Woodall, 2014: Ch. 7: Forests. Climate Change Impacts in the United States: The Third National Climate Assessment, J.M. Melillo, T.C. Richmond, and G.W. Yohe, Eds., U.S. Global Change Research Program, 175-194.

3 Benedict, Mark A., Edward T. McMahon. 2006. Green Infrastructure: Linking Landscapes and Communities. Washington, D.C.: The Conservation Fund/Island Press.

4 Groffman, P.M. P. Kareiva, S. Carter, N.B. Grimm, J. Lawler, M. Mack, V. Matzek, and H. Tallis. 2014: Ch. 8: Ecosystems, Biodiversity, and Ecosystem Services. Climate Change Impacts in the United States: The Third National Climate Assessment, J.M. Melillo, T.C. Richmond, and G. W. Yohe, Eds. U.S. Global Change Research Program, 195-219. Doi: 10.7930/JOTD9V7H.

5 Millennium Ecosystem Assessment, 2005: Ecosystems and Human Well-Being. Health Synthesis. Island Press.

6 Disrupting evolutionary processes: The effect of habitat fragmentation on collared lizards in the Missouri Ozarks Alan R. Templeton, Robert J. Robertson, Jennifer Brisson, Jared Strasburg *Proceedings of the National Academy of Sciences* May 2001, 98 (10) 5426-5432; DOI: 10.1073/pnas.091093098

7 Kenneth V. Rosenberg, Adriaan M. Dokter, Peter J. Blancher, John R. Sauer, Adam C. Smith, Paul A. Smith, Jessica C. Stanton, Arvind Panjabi, Laura Helft, Michael Parr, Peter P. Marra, Decline of the North American Avifauna, *Science*, Vol. 366, Issue 6461, 04 Oct 2019, pp. 120-124, DOI: 10.1126/science. aaw1313

Chapter 8 Climate Change

1 https://www.washingtonpost.com/outlook/wildfires-climate-change/2020/09/17/d590d9b8-f886-11ea-a275-1a2c2d36e1f1_story.html

2 <https://nca2018.globalchange.gov>

3 William J Ripple, Christopher Wolf, Thomas M Newsome, Phoebe Barnard, William R Moomaw, World Scientists'Warning of a Climate Emergency, *BioScience*, Volume 70, Issue 1, January 2020, Pages 8–12, <https://doi.org/10.1093/biosci/biz088>

4 <https://www.frederickcountymd.gov/ArchiveCenter/ViewFile/Item/11819>

5 Bluffstone, R., J. Coulston, R.G. Haight, J. Kline, S. Polasky, D.N. Wear, and K. Zook. 2017. Chapter 3: Estimated Values of Carbon Sequestration Resulting from Forest Management Scenarios. The Council on Food, Agriculture, and Resource Economics (C-FARE) Report No. 0114-301c, Washington, DC.

6 Englin, J. and J.M. Callaway. 1995. "Environmental Impacts of Sequestering Carbon Through Forestation." *Climate Change* 31:67-78.

7, 8, 9, 10, 11 Joyce, L.A., S.W. Running, D.D. Breshears, V.H. Dale, R.W. Malmesheimer, R.N. Sampson, B. Sohngen, and C.W. Woodall, 2014: Ch. 7: Forests. Climate Change Impacts in the United States: The Third National Climate Assessment, J.M. Melillo, T.C. Richmond, and G.W. Yohe, Eds., U.S. Global Change Research Program, 175-194.

12 <https://research.noaa.gov/article/ArtMID/587/ArticleID/2636/Rise-of-carbon-dioxide-unabated>

13 <https://climate.nasa.gov/news/2945/nasa-noaa-analyses-reveal-2019-second-warmest-year-on-record/>

14, 16 J. Runkel, K. Kunkel, D. Easterling, B. Stewart, S. Champion, R. Frankson and W. Sweet, "Maryland State Summary," National Oceanic and Atmospheric Administration, 2017.

15 K. E. Kunkel, L. E. Stevens, L. Sun, E. Janssen, D. Wuebbles, J. Rennells, A. DeGaetano and J. G. Dobson, "Regional Climate Trends and Scenarios for the U.S. National Climate Assessment: Part 1. Climate of the Northeast U.S.," National Oceanic and Atmospheric Administration, 2013.

17, 18 Brown, D.G., C. Polksky, P. Bolstad, S.D. Brody, D. Hulse, R. Kroh, T.R. Loveland, and A. Thomson, 2014: Ch. 13: Land Use and Land Cover Change. Climate Change Impacts in the United States: The Third National Climate Assessment, J.M. Melillo, Terese (T.C.) Richmond, and G.W. Yohe, Eds., U.S. Global Change Research Program, 318-332. Doi:10.7930/J05Q4T1Q.



Appendix

Sugarloaf Rural District Plan Study Area Historic Resources Inventory

Below is a list of historic sites that are listed either on the National Park Service's National Register (NR) of Historic Places, or on the Maryland Historical Trust's Maryland Inventory of Historic Properties (MIHP). An eight-digit NPS Reference number identifies resources listed on the NR. Properties listed with the State are assigned an inventory number that begins with the one digit county abbreviation (F), followed by a hyphen and an Arabic numeral representing the planning area (from 1-8) and followed by a second hyphen and a sequential number.

Resource Number	Resource Name	Location	Description
NR 00001053	Bloomsbury	Thurston Road	The Roger Johnson property, known as Bloomsbury, is a farmstead consisting of a two-part sandstone house dating from the 1780s with an early 19th century addition; a log barn and frame wagon shed; and remnants of log slave quarters located immediately behind the main house.
NR 66000036	Chesapeake and Ohio Canal National Park		Built between 1828 and 1850, the canal ran 184.5 miles from Georgetown, D.C. to Cumberland, Maryland. Operators used the canal primarily for hauling coal from western Maryland to the port of Georgetown in Washington, D.C. Hundreds of original structures, including locks, lock houses, and aqueducts, serve as reminders of the canal's role as a transportation system during the Canal Era.
NR 73000919	Amelung House and Glassworks	Park Mills Road	Johann Friedrich Amelung came to Maryland in 1784 and built the Glassworks in Frederick County along with a c. 1785 late-Georgian two-story brick home. The home is six bays wide with two interior chimneys. Today, there are no longer any aboveground remains of the factory.
NR 75000151	Monocacy Site		The Monocacy Archeological Site is the deepest known stratified site in Maryland. The Marcey Creek component of the Monocacy site represents the earliest (950±95 B.C.) dated manifestation of pottery in the Potomac River valley and is one of the earliest dated appearances of pottery anywhere in the east.
F-1-28	Greenfield Mills	Greenfield Road	Site of a former town known as Greenfield Mills. The mill was described as a four-story stone structure with four pairs of six-foot burrs. The 1886 General Directory of Frederick City listed farmers, a shoemaker, blacksmith, wheelwright,

Sugarloaf Historic Resources Inventory

			general store owner, and grist and sawmill owner at Greenfield Mills.
F-1-92	Monocacy Aqueduct		The Monocacy Aqueduct crosses the Monocacy River on the C&O Canal. It is a five arch coursed sandstone aqueduct completed in 1833.
F-1-127	Amrine Farmhouse	Park Mills Road	The Amrine Farmhouse also known as the Baxter Farm is an ell shaped, two story, brick dwelling. The rear section dates to the 18 th century or early 19 th century whereas the main front block was built in the mid or late 19 th century. A brick and frame outbuilding, frame bank barn, windmill, and wagon shed are also located on the property.
F-1-132	Bridge 10029, Furnace Ford Bridge	MD 28 over Monocacy River	Bridge 10029 is a three span, Camelback truss measuring 446 feet in total length. The bridge was built in 1931 and was not altered since its construction.
F-1-134	Carrollton Manor Rural Historic District	MD Rt 28 to Tuscarora Creek to Fountain Run and to Monocacy River	A portion of the Carrollton Manor Rural Historic District (CMRHD) overlaps the Sugarloaf Rural District Area. CMRHD is associated with the historic land patent known as "Carrollton Manor" that has variously been reported as containing 10,000 to 12,000 acres. The entire district retains a substantial number of landscape elements that illustrate the history of agriculture in Frederick County from ca. 1800-1940.
F-1-174	Forest Grove U.M. Church	Dickerson Road	The Forest Grove United Methodist Church is a one-story church with German siding, wood buttresses, and a rusticated concrete block foundation, which was originally built prior to 1874 in Washington, DC. In 1874, the Methodist Episcopal congregation acquired it, disassembled, and transported to Frederick County by C&O canal boat.
F-2-11	C&O Canal National Historical Park		See National Register info in chart above.
F-7-1-3	Cosgrave-Naylor Log House	Comus Road	This is a two-story log house with two blocks: a main block of three bays in length and one in depth and a one story shed kitchen that was added to the rear. It is unclear if the structure is still standing. Further research is needed.
F-7-1-4	Bene and Barbara Hallman House, site	Mount Ephraim Road	The Bene and Barbara Hallman House site was the location of a two-story log house built in the early 1880s and owned by an African-American landowning quarry worker.

F-7-1-5	James and Malinda Hallman House, site	Mt. Ephraim Road	This site was the home of one of the grandchildren of a principal founder of the African-American community in Mt. Ephraim. It resembled other log houses in the area.
F-7-1-6	Moses Hallman Log House, site	Banner Park Road	This log house site resembled the homes of other families of moderate means in the Mt. Ephraim community.
F-7-1-7	Hannah and William Hallman House	Mount Ephraim Road	This was the site of a two-story log house that was the home of John Beall one of the principal founders of the African American community in Mt. Ephraim.
F-7-1-8	Frank Nichols Log House	Banner Park Road	This house is no longer standing. It was a two-story log house built as the residence of a white land-owning family of moderate means.
F-7-1-9	Morris and Agnes Posey Log House, site	Banner Park Road	This site was the location of Morris and Agnes Posey's log house in the Mt. Ephraim community. It had two stories with two rooms down and two up built c. 1875-1895.
F-7-1-10	Charles and Laura Proctor Log House, site	Banner Park Road	This log house site resembled the other two-story log dwellings with two rooms down and two up in the Mt. Ephraim community.
F-7-1-11	David and Sally Proctor Log House, site	Mount Ephraim Road	This site was where David and Sally Proctor built their two-story log cabin. It stood on property that had been owned by direct descendants of that family since 1814 and 1833 who were freed African-Americans.
F-7-1-12	Frank and Maggie Proctor Log House, site	Banner Park Road	This site was the location of a two-story log house with two rooms and was the home of an African-American landowning family built by community labor in the last quarter of the 19 th century.
F-7-1-13	Linwood Proctor Log House	Banner Park Road	This one and a half story log house was the home of an antebellum free African-American family, who had owned the property on which the house stands since 1814. The house has three bays on the façade with the door centrally located.
F-7-1-14	William and Mary Proctor House, site	Banner Park Road	This two-story log house site was the home of the matriarch and patriarch of nearby African-American families associated with the Mt. Ephraim community. This house stood at the middle of the circle at the end of Banner Park Road.
F-7-1-15	William and Rachel Proctor Log House	Banner Park Road	The William and Rachel Proctor log house appears still to be standing. It has been reduced from its two-story height to its original one and a half stories. The structure is three bays wide on the west elevation with a porch across the east elevation.

F-7-1-16	Wood-Bowie Log House	Comus Road	No Records.
F-7-2	Rock Hall	Doctor Belt Road	A two-story, Federal style stone house built in 1812 by Roger Johnson. The façade is three bays wide with a transom over the entrance door. A later two-story stone addition was added to the north end of the principal block covered by a two-story porch. A small log cabin was added to the wing addition about 1825-40.
F-7-4	Koontz Chapel	Park Mills Road	The Koontz Chapel built in 1893, is a one-story frame church with Gothic arched windows and door transom. A cemetery associated with the church is located to the north.
F-7-5	Kohlenberg Glassworks Site	Bear Branch Road	This site is the location of the former Kohlenberg Glassworks. John Amelung and his small group of artisans settled in the area and began manufacturing in two glasshouses in the late 1780s and early 1790s. After Amelung went bankrupt in 1799, the property was transferred to Kohlenberg and existed until c. 1808.
F-7-9	Johnson Furnace, site	Dickerson Road	A slagheap and charcoal pits are all that remained on the site of the Johnson Furnace at the time of the 1978 survey. Traces of roads, which led from the furnace to the forge, are evident. The Johnson brothers built the Johnson Furnace, Thomas becoming the first governor of Maryland.
F-7-11	Thurston Road Bridge 68, site	Thurston Road over Little Bennett Creek	Pony truss bridge that no longer exists.
F-7-12	Samuel T. Simmons House	Linthicum Road	The Samuel T. Simmons House, built c. 1825, is a two-story stone dwelling with a two-story open porch with a scroll-sawn balustrade on the second level and a stucco-covered north elevation. A one-story brick addition adjoins the west gable end.
F-7-13	Dixon Road Steel Truss Bridge (07-09)	Dixon Road over Bennett Creek	The Dixon Road Steel Truss bridge, constructed in 1904, is a single-span, Warren pony truss measuring 44 feet in total length. The bridge was rehabilitated in 1994.
F-7-16	Richard Johnson House	Dixon Road	The Richard Johnson House is a two-story stone dwelling built in probably three sections between 1780 and 1808. A circa 1800 stone smokehouse as well as a late 19 th century wagon shed/corn crib, and a circa 1900 frame bank barn are also located on the property.
F-7-18	Bloomsbury	Thurston Road	See National Register info in chart above.
F-7-19	Mullican Log House	Thurston Road	The Mullican Log House was built about 1855 as a two-story log dwelling with German siding and a

			center entrance with a one-story porch. A log smokehouse associated with the house is no longer standing.
F-7-22	The Little House (Orrison Farm)	Peters Road	The Little House is a two and a half story frame over log building with three bays across the façade and one room deep built in the 18 th century. A one-story kitchen addition was added to the west elevation in the 1800s and a more modern one-story addition was added in the 1960's.
F-7-23	Bloomsbury Forge	Peters Road	The stone dwelling built between 1774 and 1787 is the principal structure remaining at the site of the Bloomsbury Forge, an iron finishing manufactory established by the Johnson brothers. The house is a simple two-room, two-story structure with a 1940's addition to the side wing and a 1980's addition to the rear.
F-7-25	Comstock School	Mount Ephraim Road	The Comstock School is a one-story frame rural school built about 1910 with an elaborate Classical Revival door surround with a half dome and flanking columns. Gordon Strong built the school for the African-American children near his Sugarloaf Mountain estate.
F-7-26	Park Mills Survey District	Mt. Ephraim and Bear Branch Roads	Park Mills Survey District includes an area of about 5 acres centered at the intersection of Mt. Ephraim and Bear Branch Roads. The district has six contributing structures which include a circa 1810-1820 stone dwelling with two sections, three other much-altered dwellings with some log structure in each which date from about 1820-1840, and two unoccupied frame stores of the period about 1850-1870. The district is moderately significant for its association with several demolished rural industrial sites in the vicinity, including the Amelung Glassworks, the Kohlenberg Glassworks, and the Fleecy Dale Woolen Factory.
F-7-27	Bell's Chapel Methodist Episcopal Church	Mt. Ephraim Road	Bell's Chapel M.E. Church was built between 1918 and 1925, replacing a circa 1874-log building. The present structure is frame with a stone foundation and wood shiplap siding. A small bell cupola over the east end of the gable ridge has plywood panels enclosing the originally open chamber.
F-7-28	St. Paul's African Methodist Episcopal Church	Ed Sears Road	St. Paul's A.M.E. Church was built in 1916 on a foundation laid in 1908 when the lot was purchased. The church is a one-story frame building on a rusticated concrete block foundation with a gable façade and projecting foyer. The exterior is covered with German siding. Stained

Sugarloaf Historic Resources Inventory

			glass windows have segmental arched frames. A cemetery is located east of the church.
F-7-29	Hope Hill Methodist Episcopal Church	Fingerboard Road	Hope Hill M.E. Church was built in 1910 to replace the original church located on Park Mills Road about one mile east of the present building. The cemetery associated with the earlier church is still actively used. The church is the typical design of rural churches with a projecting bell tower on the north gable end and a double-doored entrance.
F-7-30	Flint Hill Methodist Church and Cemetery	Park Mills Road	Flint Hill Methodist Church is a one and a half story frame structure with an extension tower with belfry located on the second bay on the east side. Double hung gothic windows are located on all four elevations of the building. A cemetery associated with the church is located northwest of the church.
F-7-32	Stronghold Survey District	Sugarloaf Mountain Road at Comus Road	The Stronghold Survey District, covering about 400 acres including the southern slopes and the summit of Sugarloaf Mountain, contains the principal buildings associated with Henry Gordon Strong. He developed a private enclave with two large Georgian Revival mansions and a network of trails, overlooks, and formal gardens for the benefit of his family and the education of underprivileged children from Chicago. Most structures within the district date from the period from about 1910-1930 with a few surviving buildings of the last quarter of the 19 th century and a 1954 stone mausoleum.
F-7-37	Hope Hill Colored School	Fingerboard Road	The Hope Hill Colored School is a frame, two-room schoolhouse with an entrance foyer and folding doors separating two classrooms. Built c. 1890 for the Hopeland community the school is much deteriorated.
F-7-40	Bear Branch School	Flint Hill Road	Built in 1839, the Bear Branch School is a one and a half story rectangular log structure and three bays wide. Originally, the building was located on the west side of Bear Branch Road. The school is in a state of disrepair.
F-7-44	Simmons-Ordeman House	Park Mills Road	The James H Simmons House was built about 1840. It is a two-story stone house with three bays on the façade and a centrally located door. A two-story rear wing has been altered with an extended and enclosed two-story porch. A frame smokehouse, frame granary, and a small barn of the English type are associated with the property.

F-7-45	George J.H. Kanode Farmstead	Roderick Road	The George J.H. Kanode Farmstead was established in 1912 with the buildings erected during the period 1912-1920. A Four Square dwelling is located on the property with a porch that has been extended around two additional elevations. Outbuildings include a frame and concrete block bank barn, a smoke house, and a well house.
F-7-46	Boyer-Yingling House	Lily Pons Road	They Boyer-Yingling House was built c. 1847 to 1854 and is a two-story brick dwelling with a 1 ½-story rear wing. The main block is three bays wide with a one-story entry porch over the door.
F-7-48	Green Valley School	Park Mills Road	The Green Valley School was built in 1889 with a gable entrance façade. In 1930, the building was sold when the school was consolidated with Urbana and is currently a residence.
F-7-50	Amelung House & Glassworks	Park Mills Road	See National Register info in chart above.
F-7-56	Samuel Schwartz Farmstead	Roderick Road	The Samuel Schwartz Farmstead is centered on a circa 1883, frame dwelling with exterior details in the Queen Anne style. A couple frame agricultural outbuildings remain, a bank barn and a wagon shed/corn crib, however several outbuildings have been lost since the 1993 including a hog barn, a tool shed, and a dairy barn and milk house.
F-7-62	Murdock-Lawson Farmstead	Roderick Road	The Murdock-Lawson Farmstead is centered on a circa 1825 brick dwelling with a side hall plan and a one-story porch, with a one-story addition on the northwest corner. Other agricultural buildings include a bank barn, wagon shed/corn crib, and smokehouse. The property is now the Bar-T Mountaintop Summer Camp.
F-7-69	Matthias Geigis House	Thurston Road	The Matthias Geigis House, built circa 1860, is a two-story structure with a three-bay façade and interior end chimneys. Outbuildings associated with this dwelling include a smokehouse / meat house, wagon shed/corn crib, and stone cooling shed.
F-7-72	Abraham R. Simmons House	Thurston Road	The Abraham Simmons House is a two-story exposed log dwelling, built c. 1850, with a modern two-story addition on the northwest corner. The façade is three bays in length with a central entrance.
F-7-74	Simmons Store and Residence	Thurston Road	The Simmons Store and Residence was built about 1865-1870, a two-story frame dwelling with a one-story porch on its façade. The store is a one-story extension on the north end of the building with a

			projecting polygonal display window. A separate porch associated with the store was removed after 2012.
F-7-81	John F. Simmons Farmstead	Thurston Road	The John F. Simmons Farmstead is centered on a two-story brick dwelling erected in about 1835. The house has a three bay façade with a side hall entrance and an entry porch built in 1978 to replace a deteriorated full-width porch. There is a 1 ½-story brick wing on the north gable end. The only remaining contributing outbuildings are a frame bank barn and a wagon shed/corn crib.
F-7-82	George E. House Farmstead	Thurston Road	The George E. House Farmstead is a two-story stone dwelling dated 1856 with a four-bay façade with double entrances. A two-story rear wing was added between 1856 and 1868. Modern additions have been added to the dwelling since 1993. A stone springhouse, built about 1845, and bank barn built circa 1890-1900 are still on the property. A dairy barn is also located on the property and while considered not contributing in the 1993 survey, the dairy barn may now be contributing. Further research would be required.
F-7-83	Simmons-Royer-Ordeman Farmstead	Park Mills Road	The Simmons-Royer-Ordeman Farmstead is a stone two-story dwelling built about 1820 with a two-story enclosed porch covering most of the façade and a one-story rear addition. A lower-height two-story wing adjoins the house on the south. A log smokehouse and stone springhouse, both built about the same time as the dwelling, are also in the domestic group. A dairy barn and wagon shed/corn crib across the road complete the eligible structures on the farmstead.
F-7-105	Riverside Tenant House	Fingerboard Road	The Riverside Tenant House is a two-story frame dwelling built about 1880-1890 with a two room plan and a central chimney with a one-story rear wing.
F-7-108	George W. Horman House & Outbuildings	Roderick Road	The George W. Horman House is a two-story frame dwelling with Queen Anne style influences built about 1901 and possibly altered later in the first or second quarter of the 20 th century. Outbuildings located on the opposite side of Roderick Road include a concrete block dairy barn, milk house, silo, and brick dairy, dating from about 1925 to 1935. The brick dairy was used as the processing and bottling plant for the Tip Top Dairy and has a stepped parapet with a three-bay main

			elevation. A 1901 stone garage associated with the house has been torn down.
F-7-116	Leona Pollack House	Fingerboard Road	The Leona Pollack House is a two-story saltbox roofed frame over log house that is five bays wide with the rear elevation only one story. The building was moved approximately one-quarter mile in 1948 to facilitate the building of I-270.
F-7-118	Keto Log House	Ed Sears Road	This log house is no longer standing. It was a two-story log house built in two parts with three bays wide and a steeply pitched gable roof.
F-7-119	Stonemetz Log House	Stewart Hill Road	No longer standing. This was the location of a two-section log house, the first probably dating to the middle of the 19 th century and the second added shortly thereafter. The log house was one and a half stories, 12 to 13 logs high.
F-7-120	Sugarloaf Mountain Historic District		The Sugarloaf Mountain Historic District is an irregularly shaped area of land principally located in the southwest section of Frederick County and extending south into northwestern Montgomery County. It is a cohesive region of cultural landscapes and natural areas oriented around the monadnock Sugarloaf Mountain. Influence of early German settlement in this area and distinct regional characteristics (especially before 1830) are apparent, however, a variety of building materials and styles is also evident. Despite the variety of building materials, all of the dwellings relate to one another in their overall architectural styling and detail – including symmetrical facades, interior end chimneys, and two-story main block with a two-story wing.
F-7-123	Mackintosh Farmhouse	Ed Sears Road	The Mackintosh Farmhouse is a compound of two structures, one frame and one log positioned at right angles built c. 1900 and c. 1850. These sections are united at the east gable end of the frame structure by a combined extension of the frame section gable roof horizontally and the log section gable roof vertically to create a truncated hip roof at the east end of the structure. A few agricultural outbuildings from the early 1900s remain on the property; however, the bank barn is in ruins.
F-7-141	Monocacy Natural Resources Management Area		This area occupies 2,011 acres located in southeastern Frederick and western Montgomery counties. The area is predominately rural, comprising farmland, rolling and rocky wooded hills, and single-family homes. Rock Hall and sites

			associated with the Johnson Furnace are the historic centerpieces of the district. The built resources constructed prior to 1960 and contained within the boundaries are associated with the regional industrial development of the 18 th and 19 th centuries, and with regional agriculture between the 19 th and mid-20 th centuries.
--	--	--	---

The following sites were recorded during the County's 1993-1995 survey of the Urbana area, which included Sugarloaf Mountain. These properties are noted in the County's Urbana Survey Field Notes as having potential for architectural significance. The resources are identified with a one digit area abbreviation (U) followed by a hyphen and a sequential number.

Resource Number	Location	Description
U-13	Ephraim Road	It is a two-story frame dwelling with a cross-gabled roof and a full-length one-story porch on the façade. The property was built c. 1910.
U-24	Park Mills Road	The dwelling is a two-story frame dwelling that is three bays wide with a one-story rear addition. The exterior is covered with German siding.
U-27	Ira Sears Road	The dwelling is a two-story frame, dwelling of the Foursquare style built c. 1910. It has a hipped roof with a center dormer and a full-width front porch covering the façade. The main block of the dwelling is three bays wide. An addition has been added. A frame bank barn is located on the property.
U-28	Ira Sears Road	This site is a cemetery. The dates able to be reviewed on the stones were 1887 and 1905.
U-29	Park Mills Road	The dwelling is 1 ½ stories with a one story porch across the façade. A frame bank barn and wagon shed are also located on the property as well as other agricultural outbuildings.
U-31	Park Mills Road	The frame dwelling is two stories, with a cross gable built c. 1900. A one-story porch is located on the façade. A frame bank barn is also located on the property and other outbuildings on the property may date to c. 1900.
U-33	Della Road	One and a half story bungalow built c. 1930 with clapboard siding, shed dormers, and a one-story porch.
U-36	Della Road	A one and a half story frame gable façade dwelling with a one-story porch the width of the façade.
U-39	Ed Sears Road	Property was not clearly visible from the road however it was noted to possibly have weatherboard siding and some brick alterations. The property is the site of B.S. & C. Smith House of 1873.
U-43	Fingerboard Road	A two-story frame dwelling, three bays across and interior end chimneys. It appears as though a front porch may have been enclosed on the façade. A bank barn and dairy barn are located on the property.

U-45	Flint Hill Road	The dwelling is two stories, frame construction, with a one-story porch and interior end chimneys.
U-46	Flint Hill Road	A two-story dwelling with five bays and a one-story porch across the façade. Interior chimneys are located on each gable end. A few agricultural outbuildings are associated with the property but are in a deteriorated state.
U-73	Park Mills Road	Hope Hill Cemetery original site of Hope Hill Methodist Chapel.
U-74	Park Mills Road	A two-story, 3 bay framed dwelling with a cross gable. A one story bracketed porch covers the façade and the roof has a standing seam metal covering. A few agricultural outbuildings, including a bank barn are associated with the property.
U-75	Hope Mills Lane	The frame dwelling is two stories in height with double cross gables and a one-story porch. The property has an addition on the south elevation. A rear wing is on the east elevation with an exterior chimney. A bank barn, wagon shed/corn crib and a few other frame outbuildings are located on the property.
U-76	Peters Road	A two-story frame/log dwelling in a deteriorated state with what appears to be German siding. The building has a one-story porch that appears to be collapsed and a two-story rear wing. A frame bank barn and wagon shed are also located on the property.
U-78	Thurston Road	A two-story frame/log dwelling with a cross gable in the roof and a two story rear wing. A one-story porch is located across the façade.
U-79 & U-80	Thurston Road	A two-story stone/brick with stucco exterior dwelling that originally was five bays across. Windows are 6 over 6. An addition has been added to the west elevation. A frame bank barn with arched louvered vents and cupolas is located to the northeast of the dwelling.
U-85	Roderick Road	A two-story brick four-square dwelling with a hipped roof and dormers.
U-90	Fingerboard Road	A two-story, two-section log dwelling with a two-story porch on the north elevation. Several additions have been added to the dwelling and is now used as a clubhouse for a golf course. Wagon shed/corn crib and bank barn are located on the property and appear to be utilized by the golf course.
U-91	Fingerboard Road	A two-story frame dwelling three bays wide with six over six windows. A one-story porch with turned columns is located on the façade. A two-story wing is located on the rear of the building.
U-98	Thurston Road	A two-story cross gable dwelling with a modern two-story porch across the façade. Exterior brick chimneys are located on the gable ends. The property also contains a stone foundation smokehouse and two frame outbuildings.
U-103	Thurston Road	A two-story brick dwelling, five bays wide, with a two-story rear wing. A frame bank barn and wagon shed/corn crib are located on the property.
U-105	Sugarloaf Mt Road	A two-story frame/log dwelling three bays wide with a one-story porch across the façade.

Sugarloaf Rural District Plan Study Area

Historic Resources Inventory

Below is a list of historic sites that are listed either on the National Park Service's National Register (NR) of Historic Places, or on the Maryland Historical Trust's Maryland Inventory of Historic Properties (MIHP). An eight-digit NPS Reference number identifies resources listed on the NR. Properties listed with the State are assigned an inventory number that begins with the one digit county abbreviation (F), followed by a hyphen and an Arabic numeral representing the planning area (from 1-8) and followed by a second hyphen and a sequential number.

Resource Number	Resource Name	Location	Description
NR 00001053	Bloomsbury	Thurston Road	The Roger Johnson property, known as Bloomsbury, is a farmstead consisting of a two-part sandstone house dating from the 1780s with an early 19th century addition; a log barn and frame wagon shed; and remnants of log slave quarters located immediately behind the main house.
NR 66000036	Chesapeake and Ohio Canal National Park		Built between 1828 and 1850, the canal ran 184.5 miles from Georgetown, D.C. to Cumberland, Maryland. Operators used the canal primarily for hauling coal from western Maryland to the port of Georgetown in Washington, D.C. Hundreds of original structures, including locks, lock houses, and aqueducts, serve as reminders of the canal's role as a transportation system during the Canal Era.
			Johann Friedrich Amelung came to Maryland in 1781 and established a farm in the area.

Sugarloaf Area Planning History, 1959-2012

SUGARLOAF AREA PLANNING HISTORY

The significance of Sugarloaf Mountain and the protection of natural resource areas is well established in Frederick County's planning history.



1959 Land Use Plan

Frederick County's first Land Use Plan was approved in January 1959, and identified Sugarloaf Mountain proper, as 'Recreation,' with some of the surrounding woodland environment designated 'Conservation.' Based on the 1959 Land Use Plan map, the zoning classification of C-1 Conservation was subsequently applied to Sugarloaf Mountain and the Furnace Branch stream valley. The purpose and intent of the land use districts was described in a March 1964 report by the Frederick County Planning Commission, which defined the C-1 Conservation District in the following manner: *"This district is created to protect watersheds and to provide permanent open space that will help organize and direct development and provide space for recreational use. It is to conserve geologic features, forest cover and historical sites for public educational purposes, and as an economic and recreational resource for the general welfare of the County."*


A series of planning reports about the County's transportation network, parkland, open space, housing, and land use followed in the late 1960's, leading to the 1972 Comprehensive Plan. One of these background reports from 1970 (the "Parks and Open Space Plan"), provided early policy guidance on environmental conservation and natural resource-based land use planning. A section, entitled Natural Resources, within this 1970 report states, *"Encroaching urbanization, inevitable though it is, must be shaped and controlled, so as to provide for the preservation of the County's natural resources. In addition to conservation of natural resources, it is imperative that outstanding scenic, historic, and natural beauty areas are protected so that future generations may enjoy them in an unspoiled and well-maintained state."* Describing the Urbana Region and Sugarloaf Mountain in particular, the 1970 report listed Sugarloaf Mountain as one of the 8 "most critical areas that should be preserved and for the most part this can be accomplished by appropriate zoning and through the use of other similar land use controls." Finally, the Parks and Open Space Plan from 1970 states, *"It is imperative that fairly large amounts of the Urbana Region remain open in order to conserve the natural resources and guide urbanization in this prime development area."*

FIGURE OS-34
MAJOR NATURAL FEATURES INVENTORY

Reference*	Identification	Location	Comments
A	Appalachian Trail	South Mountain	This 2,010 mile long trail stretches from Maine to Georgia (37 miles of it in Maryland) and is soon to be purchased by the State.
B	Big Hunting Creek Little Hunting Creek Owens Creek	Hunting Creek Valley	These are three outstanding mountain trout streams that are partially protected by State and Federal parks areas.
C	Buzzard Flats	Catoctin Mountain near Thurmont	A rugged forest area surrounding an unusual plateau.
D	Frederick Municipal Water-shed	Catoctin Mountain	A rugged mountain area permanently preserved as a water catchment area by the City of Frederick.
E	"The Cascade"	Highland School Road	Little Catoctin Creek cuts through very rugged terrain forming several beautiful pools and waterfalls.
F	Point of Rocks	Catoctin Mountain	This is the southernmost point of the Catoctin Mountain in Frederick County and is an outstanding geologic anticline.
G	Sugarloaf Mountain "Stronghold"	Sugarloaf Mountain	Sugarloaf is a quartzite monadnock some 1,280 feet high and is part of a private trust that will keep some 2,700 acres permanently open.
H	Weverton Cliffs	Brunswick	The southernmost extension of South Mountain is an outstanding cliff complex overlooking the Potomac.


*Refers to Figure OS-

1970 Parks and Open Space Plan




1972 Comprehensive Plan

The 1972 Countywide Comprehensive Plan continued to depict Sugarloaf and its close environs as Conservation on the land use map, but included a large area for future low-density residential growth and development in close proximity to the mountain, from Peters Road to I-270; this 1972 residential growth area included a new roadway parallel to I-270, plus one of the first depictions of the Corridor Cities Transitway, planned from Gaithersburg to Frederick. Surrounding the identified Conservation and Residential areas on the 1972 Plan were large areas with a 'Rural Reserve' designation (shown in white) which included scattered residential development as well as forestlands and aquatic systems. The Rural Reserve land use plan designation was subsequently changed to the Agricultural/Rural designation in the 1984 Plan, and has been in use since that time.




1978 Urbana Region Plan

In 1978 the first *Urbana Region Plan* was adopted, which identified a Sugarloaf Mountain Environmental Area as an area of “critical state concern” per the legislation passed in 1974 by the Maryland General Assembly that required all comprehensive plans to include such an element. The 1978 *Urbana Region Plan* applied the Conservation land use plan designation to the “Sugarloaf Mountain Environmental Area,” and contained very brief descriptions of its characteristics, a mapped delineation, plus current and future management techniques. Some of these techniques included the pursuit of scenic easements, and the acquisition of sensitive lands by governmental agencies and other organizations. A notable feature of this 1978 Region Plan was the depiction of a new southern alignment for MD 80 (Fingerboard Road) from Park Mills Road to the Monocacy River. The presence of environmental features such as steep forested topographical gradients, multiple stream system, plus an overhead powerline prompted the removal of this road from future plans.



1984 Urbana Region Plan

Beginning with the 1984 *Urbana Region Plan*, and continuing to the 2004 *Urbana Region Plan* and the 2010/2012 Countywide Comprehensive Plan updates, the Conservation land use plan designation in the Sugarloaf District was expanded through the use of aerial photographic analysis, and later, GIS technology, to more accurately depict the extent and location of the far-reaching forestlands and other resources in the area beyond the lands owned by Stronghold and the Maryland Department of Natural Resources. The 1984 Plan reflected the residential development that had occurred in the District through application of the 'Rural Subdivision' designation and the 'Rural Community' designation (applied to Flint Hill and Hope Hill). The Rural Subdivision designation was replaced with 'Rural Residential' in the 2010 Countywide Comprehensive Plan.



2012 County Comprehensive Plan

The 2004 *Urbana Region Plan* added a “Public/Quasi-Public Park or Open Space” land use plan designation to distinguish natural resource areas, including lands with steep slopes and large forested tracts, from local, state, or federally owned parkland. This designation also included lands comprising Sugarloaf Mountain; these lands are shown in dark green on the 2012 land use plan map. Areas in light green are designated “Natural Resource,” which replaced “Conservation” in 2010.

Sugarloaf Rural Heritage Overlay Zoning District Regulations

SUGARLOAF RURAL HERITAGE OVERLAY ZONING DISTRICT - Proposed Regulatory Framework

Chapter 1-19 (Zoning)

Article VII: Supplementary District Regulations

New Division 7 (Sugarloaf District) within Article 7 in Zoning Ordinance. New Section 1-19-7.700
Sugarloaf Rural Heritage Overlay District

Purpose/Intent

The Sugarloaf Planning Area has high quality natural resources and unique features that support a vast, diverse, and healthy environment. Special protection measures are needed where land use changes could threaten those resources, environments, and features. It is the intent of the County, in creating this District, to ensure the long-term sustainability, health, and integrity of natural environmental systems, and maintain and protect the ecological function and rural qualities of the landscapes that comprise the Sugarloaf Planning Area. The District establishes criteria, standards, and review procedures for land development activities to minimize or eliminate adverse impacts to water quality, forest resources, wildlife habitats, and scenic and rural landscape elements.

Regulatory Components for Overlay Zone

Non-residential buildings, with the *Exception noted below, constructed on a lot or parcel (after effective date) shall not exceed a gross building area of 15,000 square feet. An expansion or enlargement of an existing non-residential building shall not increase the non-residential building beyond 15,000 square feet. A request to exceed the maximum gross building area of 15,000 square feet for new non-residential buildings or expansions/enlargements may be granted by the body or entity with specific approval authority upon review of a justification statement from the applicant/owner that addresses and describes, in detail, the following:

- The unique needs of the proposed activity or use that warrant a non-residential building larger than 15,000 square feet; and
- The site design elements and building design features, such as enhanced energy efficiency, water conservation (e.g., re-use, consumption reductions), and stormwater runoff controls, or other measures that will be utilized to minimize negative impacts to natural resources and surrounding properties that may result from the overall development proposal and increased building square footage.

For permitted uses (marked P in the Use Table), the approval authority will be County staff. For uses that require Board of Appeals approval (marked E in the Use Table), the approval authority will be the Board of Appeals. For uses that require site plan approval (marked PS in the Use Table), the approval authority will be the Planning Commission or their authorized representatives.

***Exception:** The 15,000 square foot gross building area limit does not apply to new or expanded non-residential structures used only for agricultural activities, as defined in 1-19-11.100, and the following uses.

Natural Resource Uses (listed in Section 1-19-5.310)

- Apiary

Sugarloaf Rural Heritage Overlay Zoning District Regulations

- Agricultural value added processing
- Agritourism enterprises
- Nursery, retail
- Nursery, wholesale
- Farm distillery
- Farm distillery tasting room
- Farm winery
- Farm winery tasting room
- Limited farm alcoholic beverages tasting room
- Farm brewery
- Farm brewery tasting room
- Limited roadside stand
- Commercial roadside stand

Commercial Use – Retail (listed in Section 1-19-5.310)

- Feed and grain mill

Wholesaling and Processing Use (listed in Section 1-19-5.310)

- Agricultural products processing

Design Standards

All new non-residential development within the Sugarloaf Rural Heritage Overlay Zoning District shall incorporate the following design standards in addition to all other applicable requirements of the Zoning Ordinance:

Non-residential building design shall include architectural elements at entrances and where visible from a road or public right-of-way including, but not limited to: changes in building plane, windows, doorways, overhanging eaves, and shutters. Non-residential buildings shall not include large expanses of undifferentiated facades or long plain wall sections. Mechanical equipment, utilities, and non-public facilities (i.e., refuse containers or outside storage) shall be designed away from primary public access areas to the greatest extent practicable.

For all non-residential buildings and associated development proposals, only ground level (<4 ft.) and non-residential building-mounted lighting not exceeding 14 feet in height is permitted, in addition to all other applicable requirements in 1-19-6.500 of the Zoning Ordinance. Lighting for all new non-residential buildings and associated development shall include elements that reduce negative impacts to wildlife migration, nocturnal habits, and circadian rhythms, such as the utilization of lights with amber or yellow tints instead of blue or white light and the use of timers, motion detectors, and light-sensitive switches to actively regulate the emission of light from light fixtures.

If any of the following elements are proposed in association with non-residential site improvements, they shall be uniquely designed and styled with treatments and materials compatible with the rural and natural setting: site entrance walls, bridges, guardrails (provided ASHTO standards are met), fencing, signage, and lighting.

Additional Requirements in the Sugarloaf Rural Heritage Overlay Zoning District

All applications for subdivision, site development plan, individual zoning map amendments, or floating zones shall include correspondence from the Maryland Department of Natural Resources' Wildlife and Heritage Service (DNR) that documents the presence/absence of any rare, threatened, or endangered species and/or habitats on site. On sites where a rare, threatened, or endangered species or habitat is identified by DNR and if DNR requires measures to minimize adverse impacts on these species or habitats, a mitigation plan is required to minimize the identified adverse impacts, to the greatest extent practicable, on such species or habitats. If forest interior dwelling bird species (FIDS) are present, forest removal and habitat disturbance may be prohibited during the April to August breeding season, and possibly between February and August if certain early nest FIDS (e.g., barred owl) are present.

Applications submitted for site development plan, special exception, individual zoning map amendments, or floating zone approval shall include an environmental and natural features map at a minimum scale of 1 inch = 100 feet that reflects the existing conditions (e.g., pre-development) and features of the site proposed for development, including the following:

- A. Intermittent and perennial streams, drainage courses, and flow paths, including stream setbacks as required in 1-19-9.400 of this chapter
- B. Areas of 100-year floodplain as depicted by the Federal Emergency Management Agency (FEMA) flood insurance rate maps or amendments thereto, including floodplain as required in 1-19-9.110 of this chapter
- C. Topography at a minimum of 5 foot contours unless otherwise required by the Division
- D. Moderate Slopes (15% to <25%) and Steep Slopes (25% and greater)
- E. Wet soils and flooding soils, including buffers
- F. Tree lines, forested areas, and rock formations and outcroppings
- G. Wetlands and their buffers, including total acreage
- H. Any other relevant information as required by the Division

To ensure safe and efficient development that carefully considers the impacts on site design, the transportation network, natural resources, and the rural character of the area, site development plan approval from the Planning Commission is required prior to establishment or development of a Wholesale Nursery that proposes any structure or greenhouse or other such indoor growing facility.

The following uses are prohibited in the Sugarloaf Rural Heritage Overlay Zoning District:

Sawmill; springwater harvesting and storage; recreational vehicle storage facility; carnival/circus; rodeo; shooting range/club-trap, skeet, rifle, archery; aircraft landing and storage areas private-commercial use; outdoor sports recreation facility; borrow pit operations; industrial waste landfill; rubble landfill; resource recovery facility-separated recyclables; limited food waste composting-commercial activity; unlimited wood waste recycling facility; sludge amended yard waste; solid waste composting; sludge pit.

Tree cutting and forestry activities

(1) Forest cutting or clearing activities in connection with land development shall be minimized. All activities to which the forest resource regulations in Chapter 1-21 of this Code apply shall be subject to the regulations and requirements set forth in that Chapter. In addition to the requirements in Chapter 1-21, no more than 40,000 square feet shall be cleared for each home site. For all permitted nonresidential uses, site development plan approval shall require that site clearing is minimized.

(2) The following shall be included with the application for a grading permit for commercial logging or timber harvest operations in which 5,000 or more square feet of earth will be disturbed:

A. A timber harvest plan that includes the following materials:

1. A forest harvest map that graphically depicts the following:

- steep slopes and moderate slopes
- intermittent and perennial streams and associated drainage networks/flow paths
- locations of all crossings of perennial and intermittent streams
- wetlands, springs, seeps
- property boundaries
- locations of plots for harvest
- location of all forested areas on the parcel/lot
- streamside management zone/riparian area
- no-cut areas
- planned skid trails – numbers and locations
- planned haul roads – numbers and locations
- planned landing area(s)- location(s) and approximate size(s)
- site entrance/access location(s)
- map title, scale, north arrow

2. A written narrative that addresses the following:

- Landowner objectives
- Size of parcel(s)
- Total acreage in planned harvest
- Location of forest
- Type of cutting (e.g., intermediate thinning, clearcut, shelterwood, seed tree, uneven-aged selection, etc.)
- Description of forest stand characteristics (pre- and post-harvest), including species composition, age class diversity, tree species diversity, presence of non-native, invasive species and measures to manage non-native invasive species post-harvest
- Flagging and tree marking guide details for log landing areas, streamside management zones, and contemplated skids trails and haul roads
- Techniques, methods, and devices proposed to minimize runoff and erosion, and to reduce sedimentation in perennial and intermittent streams, river, lakes, and ponds from harvest areas, haul roads, skid trails, log landings, and site entrances
- Name, address, phone number, email address of property owner and report preparer

B. Review and approval of a timber harvest plan and a forest harvest map by the Frederick County Forest Conservancy Board, following a site inspection of the property by the Forestry Board.

Sugarloaf Rural Heritage Overlay Zoning District Regulations

- C. Approval of an erosion and sediment control plan by the Frederick Soil Conservation District.
- D. Approval of a stream crossing permit by the Maryland Department of the Environment for perennial and intermittent stream crossings or wetland impacts.
- E. A review by the Maryland Department of Natural Resources' Wildlife and Heritage Service (DNR) that documents the presence/absence of any rare, threatened, or endangered species and/or habitats on site. On sites where a rare, threatened, or endangered species or habitat is identified by DNR and if DNR requires measures to minimize adverse impacts on these species or habitats, a mitigation plan is required to minimize the identified adverse impacts, to the greatest extent practicable, on such species or habitats. If forest interior dwelling bird species (FIDS) are present, forest removal and habitat disturbance may be prohibited during the April to August breeding season, and possibly between February and August if certain early nest FIDS (e.g., barred owl) are present.

Within a Timber Harvest Streamside Management Zone, the following requirements apply,

- 60 square feet of basal area per acre with evenly distributed trees, which are six (6) inches or greater in diameter, must be maintained post-harvest
- No tree harvest or removal shall occur within 50 feet of the banks of a perennial or intermittent stream, or a river, lake, or pond
- No refueling or cleaning of equipment shall occur
- No log landing areas are permitted
- Skid trails and haul roads shall be minimized

1-19-10.700 – Solar Facility – Commercial Floating Zone District

(B)(5) Within the Sugarloaf Rural Heritage Overlay Zoning District, the following standards apply: Solar facilities or panels may not be constructed or installed on gradients of 15% or greater; solar facilities or panels must maintain a 100 foot setback from all perennial and intermittent streams. In areas not required to be used for forest mitigation as specified in Chapter 1-21 of this Code, native grasses and wildflowers shall be planted; No more than 12% of the existing forest cover on a lot, parcel, or tract may be removed or cleared for the construction or installation of solar facilities or panels.

1-19-8.332 Communication Towers in RC and A Districts

- (I) Within the Sugarloaf Rural Heritage Overlay District, all special exception approvals must also comply with the following:

Communication towers shall be camouflaged, disguised, or concealed to provide an appearance, texture, and color that matches the native vegetation of the area and maintains a physical and locational contextual scale. If a communication tower or antenna is incorporated into, on, or directly adjacent to an existing building or other infrastructure, the communication tower or antenna shall be designed to be compatible with the scale, size, and architectural style of the building, surrounding buildings, and surrounding infrastructure.

Article XI: Definitions

1-19-11.100 Definitions

Timber Harvest Streamside Management Zone

A minimally-disturbed area at least 50 feet in width on all sides of a perennial or intermittent stream, river, lake, or pond.

Private Park

A parcel or contiguous parcels consisting of 100 or more acres owned by a non-governmental entity or organization, managed primarily for environmental conservation, and maintained in a natural landscape condition that may be open and accessible to the public and where admission fees may be charged. A private park may include natural or paved trails, scenic viewing areas, parking facilities, forestry activities, tot lots, a caretaker residence, and private offices for the operation of the private park.

1-19-8.403 Permitted Uses

Private Park

The following provisions shall apply to Private Parks in the Resource Conservation District

- 1) The minimum lot area, lot width, yard setbacks, and heights shall be as provided for in 1-19-6.100.
- 2) The subject property must have road frontage and access on a minimum 20-foot-wide paved public road.
- 3) The requirements of 1-19-7.200 and, if applicable, 1-19-7.700 (Sugarloaf Rural Heritage Overlay District) of this Code must be met.
- 4) The following accessory uses to a private park are permitted with site development plan approval after establishment of a private park: a visitors' center, gift shop, walk-up concession stands, pavilions or open structures for gatherings.
- 5) The following uses and facilities are not permitted in conjunction with or accessory to a Private Park: recreational vehicle campgrounds, golf courses or golf driving ranges, swimming pools, fairgrounds, zoos, and hotels, motels, or lodges.

Sugarloaf Rural Heritage Overlay Zoning District Regulations

1-19-5.310 Use Table

Zoning Districts														
Uses	RC	A	R1	R3	R5	R8	R1 2	R1 6	VC	MX	GC	OR I	LI	GI
Open Space and Institutional														
Airports, public ****													PS	PS
Cemetery/memori- al gardens		PS	PS											
Fairground											PS		PS	PS
Shooting range/club - trap, skeet, rifle, archery	E	E											PS	PS
Aircraft landing and storage areas, private		E											E	E
Aircraft landing and storage areas, private - commercial use		E											E	E
Tent campground	E	E												
Rustic retreat/camp/out door club	E	E												
<u>PRIVATE PARK</u>	<u>PS</u>													

1-19-6.100 Design Requirements for Specific Districts

Use Classification	Minimum Lot Area	Minimum Lot Area per Unit	Lot Width	Front Yard	Side Yard	Rear Yard	Height
--------------------	------------------	---------------------------	-----------	------------	-----------	-----------	--------

Resource Conservation District RC

Natural Resources	10 acres		300	50	50	50	30'
Residential							
Single family	10 acres	10 acres	300	50	50	50	30'
Mobile Home	10 acres	10 acres	300	50	50	50	30'
Animal Care & Services	10 acres		300	50	50	50	30'
Open Space Uses	10 acres		300	50	50	50	30'
Institutional	10 acres		300	50	50	50	30'
Governmental & Public Utility	10 acres		300	50	50	50	30'
Nongovernmental Utility	10 acres		300	50	50	50	30'
PRIVATE PARK	<u>100</u> <u>ACRES</u>		<u>300</u>	<u>50</u>	<u>50</u>	<u>50</u>	<u>30'</u>

Frederick County Streams and Use Classes

Maryland's Designated Uses (COMAR 26.08.02)

- Use I: Water contact recreation and protection of nontidal water aquatic life
- Use II: Support of estuarine and marine aquatic life and shellfish harvesting (not all subcategories apply to each tidal water segment)
 - Shellfish harvesting and subcategories unique to Chesapeake Bay only
- Use III: Nontidal cold water – usually considered natural trout waters
- Use IV: Recreational trout waters – water are stocked with trout

If the letter "P" follows the use class listing, that particular stream has been designated as a public water supply. The designated use and applicable use classes are found in the following table:

Designated Uses	Use Classes							
	I	I-P	II	II-P	III	III-P	IV	IV-P
Growth and Propagation of fish (not trout), other aquatic life and wildlife	✓	✓	✓	✓	✓	✓	✓	✓
Water Contact Sports	✓	✓	✓	✓	✓	✓	✓	✓
Leisure activities involving direct contact with surface water	✓	✓	✓	✓	✓	✓	✓	✓
Fishing	✓	✓	✓	✓	✓	✓	✓	✓
Agricultural Water Supply	✓	✓	✓	✓	✓	✓	✓	✓
Industrial Water Supply	✓	✓	✓	✓	✓	✓	✓	✓
Propagation and Harvesting of Shellfish			✓	✓				
Seasonal Migratory Fish Spawning and Nursery Use				✓	✓			
Seasonal Shallow-Water Submerged Aquatic Vegetation Use				✓	✓			
Open-Water Fish and Shellfish Use				✓	✓			
Seasonal Deep-Water Fish and Shellfish Use				✓	✓			
Seasonal Deep-Channel Refuge Use				✓	✓			
Growth and Propagation of Trout					✓	✓		
Capable of Supporting Adult Trout for a Put and Take Fishery							✓	✓
Public Water Supply		✓		✓		✓		✓

Sub-Basin 02-14-03: Middle Potomac River Area.

Designated Use Class and Waterbody	Latitude	Longitude	Limits
(1) Class I-P: Potomac River and all tributaries except those designated below as Class III-P or Class IV-P	39.221736	-77.456451	From Frederick/Montgomery County line to confluence with Shenandoah River
(2) Class II: None.			
(3) Class III: None.			
(4) Class III-P:			
(a) Tuscarora Creek and all tributaries	39.458359	-77.375099	
(b) Carroll Creek and all tributaries	39.423513	-77.429438	Upstream of U.S. Route 15
(c) Rocky Fountain Run and all tributaries	39.332070	-77.422527	

Frederick County Streams and Use Classes

(d) Fishing Creek and all tributaries	39.505696	- 77.391445	
(e) Hunting Creek and all tributaries	39.550482	- 77.358179	
(f) Owens Creek and all tributaries	39.579028	- 77.332576	
(g) Friends Creek and all tributaries	39.719868	- 77.389272	
(h) Catoctin Creek and all tributaries	39.450300	- 77.562603	Upstream of Alternate U.S. Route 40
(i) Little Bennett Creek and all tributaries	39.279411	- 77.314709	Upstream of MD Rt. 355
(j) Furnace Branch and all tributaries	39.243999	- 77.439955	
(k) Ballenger Creek and all tributaries	39.362694	- 77.410124	
(l) Bear Branch and all tributaries	39.292638	- 77.405135	From confluence with Bennett Creek upstream
(m) Middle Creek and all tributaries	39.448829	- 77.603343	Upstream of the confluence with an unnamed trib south of Geaslin Drive
(n) Unnamed tributary to Talbot Branch and all tributaries to this unnamed tributary	39.455887	- 77.160651	Stream flows in southerly direction. Mouth of stream joins Talbot Branch near intersection of Black Ankle Road and Talbot Run Road
(o) Unnamed tributary to Talbot Branch and all tributaries to this unnamed tributary	39.454004	- 77.154174	Stream flows in northwesterly direction. Mouth of stream joins Talbot Branch 500 meters east of the intersection of Black Ankle Road and Talbot Run Road
(p) Unnamed tributary to Big Pipe Creek and all tributaries	39.675821	- 76.941553	Upstream from confluence with another unnamed tributary just south of Wine Road
(q) Bennett Creek and all tributaries	39.310961	- 77.231394	From a point, 700 yards to the east of the intersection of Moxley and Clarksburg Road, upstream
(r) Unnamed tributary to Bennett Creek	39.303758	- 77.286898	Near intersection of Prices Distillery Road and Haines Road
(5) Class IV: None.			
(6) Class IV-P:			
(a) Monocacy River and tributaries except those designated above as Class III-P	39.398435	- 77.366868	Upstream of U.S. Rt. 40
(b) Catoctin Creek	39.309777	- 77.567051	Mainstem only, from mouth upstream to Alternate U.S. Rt. 40
	39.450300	- 77.562603	
(c) Israel Creek and all tributaries	39.327756	- 77.682559	

Sugarloaf Planning Area

Small Area Plan - Community Profile

Households and Population

830

Homes



Average Household Size:

2.68 Countywide | 2.73 Sugarloaf Area

The households that are located within the Sugarloaf Planning Area comprise nearly 1% of the County's total number of households.



The Sugarloaf Planning Area has a total of 2,200 residents, representing about 1% of the County's total population.



Single, female-headed households are slightly more prevalent in Sugarloaf Planning Area (11%) than in the County (10%).



Sugarloaf Planning Area:

Owners vs. Renters

93% are homeowners

7% are renters

Age and Race


The median age in the Sugarloaf

✓ Planning Area is 50, compared to 39 in the County.

41% of residents in the Sugarloaf


✓ Planning Area are **55 and older**. Only 17% are under 18 years of age.

Sugarloaf Race and Ethnicity




White	91.1
Black/Afr. Amer.	1.8
Asian	3.2
Hispanic	2.1
Other race	1.7

County Race and Ethnicity



White	74.8%
Black/Afr. Amer.	8.8%
Asian	4.6%
Hispanic	8.8%
Other race	3.0%

Education and Income



51% of Sugarloaf residents have post-secondary education with Bachelor's, Graduate, or Professional degrees compared to 40% in the County.



59% of households earn \$100,000 or more, compared to 44% in the County.



The Sugarloaf Planning Area's **median household income** of \$123,800 is **40%** higher than in the County as a whole.

SOURCES

US Census 2010 | 2013-2017 ACS 5-Year Estimates | Quarterly Census Employment & Wages (QCEW), DOL 2017

CREATED BY: Livable Frederick, Division of Planning and Permitting, 30 North Market Street, Frederick, MD 21701

Note: The Sugarloaf Planning Area is defined by the Census Tract 752201, which includes a small area to the north adjacent to the study area boundary.

December 2019



www.livablefrederick.org

Frederick County Council 2020 Climate Emergency Resolution

THE EFFECTIVE DATE OF THIS RESOLUTION IS July 21, 2020
RESOLUTION NO. 20-22

RESOLUTION OF
THE COUNTY COUNCIL
OF FREDERICK COUNTY, MARYLAND

Re: Climate Emergency

A RESOLUTION establishing a Climate Emergency Mobilization Workgroup and committing the Frederick County Council to consider policy and legislative actions through the lens of climate change.

WHEREAS, our present climate crisis poses an immediate and long-term threat to the well-being of all communities, including Frederick County; and

WHEREAS, the adverse impacts of climate change test our infrastructure, emergency and social services; influence our access to food, water, and energy; disrupt commerce and our quality of life; and

WHEREAS, the harm already caused by climate change demonstrates the effect temperature changes have had on ecological stability and safety, as attested by increased wildfires, floods, rising seas, climate refugees, diseases, droughts, and the ongoing mass extinction of species due to these changes; and

WHEREAS, restoring a safer and more stable climate requires an emergency mobilization to reach net zero greenhouse gas emissions within a few decades, to improve carbon sequestration, and to implement measures to protect people and nature from the adverse consequences of abrupt climate change; and

WHEREAS, Section 203 of the Frederick County Charter allows the Council to appoint special ad hoc committees for inquiry and fact finding.

NOW, THEREFORE, BE IT RESOLVED by the County Council of Frederick County, Maryland, that climate change is threatening our county, state, nation and the world as we know it.

AND BE IT FURTHER RESOLVED:

- That the Frederick County Council commits to implementing policy and legislative actions through the lens of climate change.
- That the Frederick County Council commits to equitable climate emergency mobilization efforts to address global warming, reduce county-wide greenhouse gas emissions 50% from 2010 levels by 2030 and 100% no later than 2050, and employ efforts to safely drawdown carbon from the atmosphere.

- That the Frederick County Council establishes an ad-hoc Climate Emergency Mobilization Workgroup in coordination with the City of Frederick to make recommendations to the County Council to achieve these emission goals.
- That the Workgroup will be comprised of the two sponsors of this resolution or their designees and members of the community who may include, but are not limited to, representatives of the following groups:

Clean Water Action
Climate Change Working Group
Downtown Frederick Partnership
Electric Vehicle Association of Greater Washington, DC (EVADC)
Food Security Network
Frederick County Building Industry Association
Frederick County Chamber of Commerce
Frederick County Farm Bureau
Frederick County Food Council
Healthy Soils Frederick
Multifaith Alliance of Climate Stewards of Frederick County (MACS)
Sierra Club Catoctin Group
As well as representatives of public health, higher education, the scientific communities and other recognized and relevant stakeholders in the County.
- That the Workgroup will consider four main Climate Emergency concerns of specific relevance to Frederick County:
 - Energy, Transportation, and Buildings
 - Agriculture, Forestry, and Sequestration
 - Health and Extreme Weather Adaptation and Resilience
 - Public Engagement and Education
- That six months following the first meeting, the Climate Emergency Mobilization Workgroup will present a status report on the four main Climate Emergency concerns to the County Council on the progress of the Workgroup to date.
- That twelve months following the first meeting, the Climate Emergency Mobilization Workgroup will submit a final report to the County Council and to the public including legislative, administrative, and community recommendations to assist the County with meeting the goals of this resolution. Upon submission of this report, the County Council or their representatives, may submit questions/requests to the

Frederick County Council 2020 Climate Emergency Resolution


workgroup for additional information. The workgroup will have eight weeks to respond to any requests after which time the workgroup will be dissolved.

- That the Frederick County Council will communicate with and educate the public about the climate emergency, including the efforts of the Climate Emergency Mobilization Workgroup.
- That this Resolution shall take effect on July 21, 2020.

The undersigned hereby certifies that this Resolution was approved and adopted on the 21st day of July, 2020.

COUNTY COUNCIL OF
FREDERICK COUNTY, MARYLAND

By:


M.C. Keegan-Ayer, President 

Sugarloaf Survey District Form (pp 1-12) (survey file F-7-32)

F-7-32

Stronghold Survey District
Dickerson vicinity
Private; some public access at regular times

Ca. 1812; 1900-1954

The Stronghold Survey District, covering about 400 acres including the southern slopes and the summit of Sugarloaf Mountain, contains the principal buildings associated with Henry Gordon Strong (1869-1954) who developed a private enclave with two large Georgian Revival mansions and a network of trails, overlooks, and formal gardens for the benefit of his family and the education of underprivileged children from Chicago. For the more specific education of children both local and from Chicago, Strong built and funded a vocational school and two local schools, one of which, the Halstead School, is located within the survey district. The district also includes a designed plaza at the intersection of Comus and Sugarloaf Mountain Roads, surrounded by the Georgian Revival vocational school, now the headquarters of Stronghold, Inc., which operates the Sugarloaf Mountain Park as a public access nature conservancy, and several vernacular buildings, some occupied as residences by park employees, and others used as storage and maintenance buildings. Most structures date from the period about 1910-1930, but two of the dwellings on or near the plaza have some log structure and could date as early as the first decade of the 19th century. The Strong Mausoleum, a stone funerary structure built about 1954, is located within sight of the plaza.

F-7-32

Stronghold Survey District
Dickerson
Frederick County

Historic Context:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery
Counties, and Baltimore City)

Chronological/Development Period:

Industrial/Urban Dominance, A.D. 1870-1930

Prehistoric/Historic Period Themes

Architecture, Landscape Architecture and Community Planning
Social/Educational/Cultural

Resource Types:

Category: District

Historic Environment: Rural

Historic Function and Use:

Domestic/single dwelling/residence
Domestic/single dwelling/mansion
Education/school/schoolhouse
Education/school/technical school
Recreation and Culture/outdoor recreation/park
Agriculture/subsistence/agricultural outbuilding & barn

Known Design Source: None

M110 P26

Survey No. F-7-32

Maryland Historical Trust
State Historic Sites Inventory Form

MARYLAND INVENTORY OF
 HISTORIC PROPERTIES

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic

and/or common Stronghold Survey District

2. Location

street & number 7900 blk. Sugarloaf Mountain Road at Comus Road not for publicationcity, town Dickerson vicinity of congressional district 6thstate Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use	
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture	<input type="checkbox"/> museum
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial	<input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational	<input type="checkbox"/> private residence
<input type="checkbox"/> site			<input type="checkbox"/> entertainment	<input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> accessible	<input type="checkbox"/> government	<input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> industrial	<input type="checkbox"/> transportation
	<input type="checkbox"/> x not applicable	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> military	<input checked="" type="checkbox"/> other: recreation
		<input type="checkbox"/> no		

4. Owner of Property (give names and mailing addresses of all owners)

name Stronghold, Inc.

street & number 7901 Comus Road telephone no.:

city, town Dickerson state and zip code Md. 20842

5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber

street & number 100 W. Patrick Street folio

city, town Frederick state Md. 21701

6. Representation in Existing Historical Surveys

title MHT Inventory of Historic Properties Sugarloaf Mt. Historic District (F-7-120)

date 1977 federal state county local

repository for survey records Md. SHPO

city, town Crownsville state MD

7. Description

Survey No. F-7-32

Condition		Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		date of move _____

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 13

The Stronghold Survey District encompasses approximately 400 acres on the southern slope of Sugarloaf Mountain, including the 1,282-ft. summit, part of the lands of the Sugarloaf Mountain Park, a privately endowed nature conservancy area and National Natural Landmark, just north of the Frederick-Montgomery County boundary in Frederick County, Maryland. The district is primarily heavily wooded mountain land laid out with winding drives, hiking trails, and paths interspersed with scenic overlooks built of the natural stone of the mountain, but it also includes 13 principal structures built mostly from about 1910 to about 1930, with a few surviving buildings of the last quarter of the 19th century and a 1954 stone mausoleum. The early 20th century buildings and the park structures are associated with Henry Gordon Strong (1869-1954) and his efforts and plans to create a private enclave on Sugarloaf Mountain. The buildings include his own stone mansion, a Georgian Revival design by Philadelphia architect Percy Ashe; Westwood, a somewhat smaller mansion in the same general style built for Mrs. Ella Denison, Strong's sister; a brick vocational school building erected as part of Strong's philanthropic interests; the Halstead School, also erected by Strong and moved to the vicinity of the park entrance in 1991; a frame barn, three dwellings, two of which predate 1900 and one of which was moved from its original location near the barn; and the stone mausoleum in which Strong and his wife are buried, built in 1954. The concentration of buildings is around the intersection of Comus Road and Sugarloaf Mountain Road, at which is located a paved plaza set off by Georgian Revival design brick gates and walls with the more rustic entrance to the park on the north side and the vocational school on the south side. The buildings are in active use as the park headquarters and the homes of the Stronghold corporation's employees or, in the case of the Strong Mansion, as a rental property for private parties and meetings. The park is heavily visited on weekends and for special events during the year. Dates for the buildings were provided principally by Mr. Benjamin Smart, the park superintendent, based on his research in land records, personal interviews with local residents, and newspaper research on the Strong family.

The 400-acre survey district is part of a much larger area of several thousand acres including both Stronghold, Inc. lands and private properties which is the subject of a National Register nomination effort by the Sugarloaf Regional Trails, a volunteer organization of citizens interested in the conservation of the entire Sugarloaf Mountain area, including both the natural and built environment, for recreational and educational purposes. This nomination project has been on-going since the late 1970's and the latest document produced by the group is currently being revised for submission to the Governor's Consulting Committee. This inventory form is intended to document the Stronghold buildings in a more detailed manner than the multiple-resource approach of the NR nomination. Several of the privately owned individual buildings being covered by the NR nomination are the subjects of separate inventory forms. The inventory list for the Frederick County Urbana Planning Regic

8. Significance

Survey No. F-7-32

Period	Areas of Significance—Check and justify below							
— prehistoric	<input type="checkbox"/>	archeology-prehistoric	<input type="checkbox"/>	community planning	<input checked="" type="checkbox"/>	landscape architecture	<input type="checkbox"/>	religion
— 1400-1499	<input type="checkbox"/>	archeology-historic	<input checked="" type="checkbox"/>	conservation	<input type="checkbox"/>	law	<input type="checkbox"/>	science
— 1500-1599	<input type="checkbox"/>	agriculture	<input type="checkbox"/>	economics	<input type="checkbox"/>	literature	<input type="checkbox"/>	sculpture
— 1600-1699	<input checked="" type="checkbox"/>	architecture	<input type="checkbox"/>	education	<input type="checkbox"/>	military	<input checked="" type="checkbox"/>	social/humanitarian
— 1700-1799	<input type="checkbox"/>	art	<input type="checkbox"/>	engineering	<input type="checkbox"/>	music	<input type="checkbox"/>	theater
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/>	commerce	<input type="checkbox"/>	exploration/settlement	<input type="checkbox"/>	philosophy	<input type="checkbox"/>	transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/>	communications	<input type="checkbox"/>	industry	<input type="checkbox"/>	politics/government	<input type="checkbox"/>	other (specify)
			<input type="checkbox"/>	invention				

Specific dates	C. 1812; 1902-1954	Builder/Architect	Percy Ashe, architect
-----------------------	--------------------	--------------------------	-----------------------

check: Applicable Criteria: A B C D
and/or

Applicable Exception: A B C D E F G

Level of Significance: national state local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Stronghold Survey District is highly significant in the theme of architecture for the variety of structures and styles represented in the buildings. The Strong Mansion and Westwood, the formal gates and the vocational school building reflect the Georgian Revival style designs of Percy Ashe, the Philadelphia architect for Henry Gordon Strong (1869-1954), the owner and guiding spirit of the Sugarloaf Mountain enclave which is included in the 400 acres of the survey district. They are representative of Strong's concept of a private architectural village in which he could indulge his appreciation of nature, the arts, and philanthropy. In addition to these high style buildings of the period 1911-1928, the district contains vernacular structures, some partially of logs and most in frame, of the period about 1850-1900, although exact dates are yet to be determined. These include the Halstead School, a barn and a garage, and three dwellings, one of which, the Snyder Cottage, was probably the work of the architect Ashe in about 1909. In addition to Ashe, the landscape architect Robert Marshall was responsible for the overlooks and hiking trails on the mountain slopes and the formal gardens near the Strong Mansion. The district is also representative of the early 20th century conservation efforts of Strong, whose wealth allowed him to acquire over several years from 1899 to about 1910 the summit and surroundings of Sugarloaf Mountain whose striking location with views over the Potomac and Monocacy Valleys and isolated elevation provided a natural landscape of rocks, wooded areas, and farms in which Strong wanted to establish a private reserve for his family's benefit, but also to pursue philanthropic goals involved in his inheritance. In this natural setting, Strong wanted to establish a school for underprivileged boys from Chicago, his hometown, where they could have a basic education and learn skills to support themselves. This involves another theme, education, in which the survey district is also significant. Although Strong's educational aims were not unique, the Buckingham School for Boys near Buckeystown having been established in the 1890's by the Baker family, his vision of locating the schools in an environment of natural and designed features under his supervision and guidance was very enlightened for the first decade of the 20th century. In reality, Strong's goals were only partially achieved. The planned Georgian Revival mansion for himself was completed as only one wing of the design. The vocational school apparently did not operate for a prolonged period, but Strong did build at least two schools both for his Chicago boys and also for the use of local children, funded and furnished largely by him. One of these, the Halstead School, is within the survey district, having been moved twice.

9. Major Bibliographical References

Survey No. F-7-32

MHT Inventory form F-7-120 Sugarloaf Mountain Historic District
Smart, Mr. Benjamin, Superintendent, Stronghold, Inc.

10. Geographical Data

Acreage of nominated property 400 acres

Quadrangle name Buckeyestown, Md.-Va.

Quadrangle scale 1: 24000

UTM References do NOT complete UTM references

Verbal boundary description and justification

Approximately 400 acres as shown on the attached quad map section, encompassing the mountain summit, the principal trails and drives and the buildings associated with Gordon Strong's ownership.

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code
11. Form Prepared By			
name/title Janet L. Davis, Historic Sites Surveyor			
organization Frederick County Planning & Zoning Dept. date September 1993			
street & number 12 E. Church Street		telephone 696-2958	
city or town Frederick		state	MD 21701

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023

PS-2746

Stronghold Survey District
Frederick County

Survey No. F-7-32

7.1 Description

should be consulted for further information on other individual sites in the vicinity of Sugarloaf Mountain.

Following are brief descriptions of the principal buildings in the survey district:

Strong Mansion: The three-story concrete and stone mansion built in 1911 is the west wing of a much larger symmetrical Georgian design by Percy Ashe with terraces, balustrades, and formal gardens surrounding it. Completion of the entire composition was canceled reportedly by internal family objections to the scale and ostentation of the proposed structure. The existing building is a roughly square plan, hipped roof building with three bays on the west elevation. The walls are ashlar stone and the roof, although not clearly observed in this survey, is probably slate. The entrance is in the center bay on the ground floor, sheltered by an entry portico. The windows on the second story have blind arches in the stone above each opening. French windows fill the second story openings and the third story has smaller casement windows. The interior was not accessible for this survey; however, a photograph of the drawing room or living room published in a 1979 Frederick News-Post article shows a formally designed space with large floor to ceiling French windows with fanlights and furniture probably mostly Classical Revival or Neo-Classical in style.

Westwood: The smaller Georgian Revival mansion was built about 1913 for Gordon Strong's sister, Mrs. Ella Denison. It is currently the home of the park superintendent. The two story mansion has five bays and a full-height columned portico over the center three bays. The walls are plastered and the ground floor windows have blind arches and casements as in the Strong Mansion, although on a smaller scale. The center bay on the first story has a fanlighted entrance and the second story center bay has a decorative cast iron window basket railing. The roof, not visible from the park road in front of the building, is probably hipped and covered with slate. The interior was not accessible for this survey.

Vocational school (Park Administration offices): The long, rectangular, one-story brick school building erected about 1915 is located on the south side of the plaza at the intersection of Comus and Sugarloaf Mountain Roads. It has a center entrance to a hall which originally gave access to the two sides of the building in which were located workshops and classrooms. The exterior has windows in a regular progression along the north side flanking the slightly projecting center bay and entrance. Subsidiary entrances with molded Classical Revival surrounds are located at the east and west ends of the north elevation. The interior was not fully accessible for the survey, but at least some rooms have been partitioned for use as offices.

Snyder Cottage: The 1-1/2 story frame Colonial Revival Cape Cod house was built about 1909, probably to house school employees or students at the vocational school. It stands on the east side of the plaza at the point of

Stronghold Survey District
Frederick County

Survey No. F-7-32

7.2 Description (Continued)

intersection between the two roads meeting at the plaza. It is currently occupied by Stronghold personnel as living quarters. It has a three-bay west elevation with clapboard siding and a shingle roof with three dormers on the west side. The center entrance has a pediment above the door and a molded architrave.

Plaza gates: Located in front of the Snyder Cottage and on the opposite or west side of the plaza are two formal gateways in the Georgian Revival style with brick wing walls topped by stone caps. The eastern gate has globe finials and a wood picket gate. The western one has a decorative cast iron gate, through which a man-made pond is visible in the western quadrant of the plaza. The gates were presumably designed by Percy Ashe, as were most of the early 20th century buildings, and built about 1910-1915.

Baxter House: The Baxter House is located on the south side of Comus Road east of the vocational school and southeast of the Snyder Cottage. It was possibly built about 1900 and was originally located about 75 yards northwest of its present location within the current park entrance, the location being marked by the free-standing stone chimney stack left when the house was moved about 1914. It apparently had some log structure in its original form, indicating that it may have been a smaller, mid-19th century building to which the frame surviving section was added in the last quarter of the 19th century. Currently it has five bays with a center entrance under a cantilevered hood and artificial siding. The sash is 6/6 flanked by replacement shutters. The Baxter House was Strong's original residence prior to the erection of the mansion. It is occupied as a residence by a park employee.

Halstead School: The frame one-story schoolhouse is currently located north of the park entrance, having been moved twice since its construction about 1910. Its original location was possibly just on or over the Montgomery County border and was moved in the mid-20th century to a position behind the vocational school temporarily until plans for its restoration could be finalized. In 1991, it was moved to its present location and its exterior was rehabilitated. The interior is not yet complete and plans are to use the school as an interpretive display area about Sugarloaf and its history. The school is in the typical late 19th century-early 20th century form of rural schoolhouses, having a gable facade with three bays and large 6/6 windows. The side elevations have three bays each. The exterior is covered with board and batten and a modern replacement wood porch rises to the center entrance, a paneled door under a plain transom. A small gable window lights the attic level. The school was named for Strong's mother, whose maiden name was Halstead.

Barn: The one-story frame barn is a rectangular frame structure which was built about 1910, although parts of it may pre-date Strong's ownership, since it was associated with the Baxter House. Currently it is a long, shingled building with attached storage sheds incorporated in it. Some of these have open sides on the south, while others have sliding or garage-type doors.

Garage: Located directly east of the barn is a frame garage, probably also dating from about 1910. It has vertical board siding and sliding doors on the west gable end.

Stronghold Survey District
Frederick County

Survey No. F-7-32

7.3 Description (Continued)

Mausoleum: The small stone mausoleum was built in 1954 after Strong's death. It has ashlar limestone walls and an entrance on the south gable end. The roof is covered with wood shingles. The entrance has a cast iron gate through which the interior with the undecorated tombs of Strong and his wife, who died in 1949.

Farm Cottage: The 1-1/2 story building was not closely observed for the survey, but the park superintendent described it as having some log structure with alterations in about 1948. It is said to have served as a field hospital in the Civil War during a skirmish near an observation post on the mountain in 1862. In 1977, its date was estimated by Sugarloaf Regional Trails as 1812, but no descriptive information was provided at that time to support this date. Further examination is required.


Formal gardens, trails and overlooks: The many trails and overlooks around the mountain summit include four scenic viewpoints, West View, East View, Potomac Overlook, and Bill Lambert Overlook. They are terraced and buttressed with native rock from the mountain and are designed to blend with the natural surroundings. Near the Strong Mansion are formal gardens with terraces, planting beds, balustrades, and lawns. All of these features were the work of Robert Marshall, landscape architect, in the period 1910-circa 1920.

Stronghold Survey District
Frederick County

Survey No. F-7-32

8.1 Significance (Continued)


The Stronghold Survey District is unique in Frederick County, but its statewide context is unclear. Certainly wealthy patrons established private schools in other parts of the state. One example is the Tome Institute in Cecil County, which is a National Register-listed property of the early 20th century with architectural and educational significance. The Buckingham School for Boys in Frederick County is another NR-listed complex of the same importance. Stronghold may be the only such assemblage of both natural and built features under the themes of architecture, landscape architecture, and education.



F-7-32
Stronghold Survey District
Frederick County

Janet Davis
September 1993
Not to Scale

Sugarloaf Survey District Form (pp 1-12) (survey file F-7-32)



1 MILE
FEET

Heavy-duty

F-7-32
Stronghold Survey District
Frederick County
USGS Buckeystown, Md.-Va.
1:24000



Livable Frederick Planning and Design Office
Division of Planning and Permitting
Frederick County Government

30 North Market Street
Frederick, MD 21701

