

GENERAL INFORMATION FOR MINOR PLANS AND PROJECTS

SWM NOTES:

1. Stormwater quality management shall be address through the use of vegetated filtering and other Best Management Practices as outlined in the Maryland Stormwater Design Manual, Chapter 5 (latest revision).
2. The area disturbed shall not infringe upon wooded area or degrade the current land use.
3. All disturbed area shall be returned to a comparable or better condition than what previously existed.
4. Regraded areas shall not further impact other properties with respect to drainage.
5. The top six-inch backfill layer located within grass and/or other pervious areas is not to be compacted.

BASIC SEQUENCE OF CONSTRUCTION:

1. Miss Utility shall be contacted at 1-800-257-7777 a minimum of 48 hours prior to start of construction.
2. Contact the sediment control inspector at 301-600-3507 a minimum of 48 hours prior to start of construction for a preconstruction meeting.
3. Install silt fence, stabilized construction entrance and other sediment controls.
4. Grade areas as outlined on the approved plans and stabilize with seed and mulch.
5. Contact Utility Company for relocation of utility poles to backside of ditchline.
6. Contact inspector for review and approval of road layback.

FOR UTILITY WORK ONLY AND/OR OFF-SITE UTILITY WORK:

1. Disturbed area can not exceed 5,000 square feet.
2. Place all excavated material on high side of trench.
3. Only do as much work as can be done in one day to allow for proper backfilling, final grading, seeding and mulching of all disturbed areas.
4. Any sediment control measures disturbed by construction will be repaired the same day.